



IFB No. DACW09-03-B-0011

U.S. ARMY CORPS  
OF ENGINEERS  
LOS ANGELES DISTRICT

---

# **Maintenance Dredging Oceanside Harbor**

## **San Diego County, California**

### **Construction Solicitation and Specifications**

#### **Unrestricted**

---

**AUGUST 2003**

**BEFORE SIGNING AND MAILING THIS BID, PLEASE TAKE NOTE OF THE  
FOLLOWING, AS FAILURE TO PERFORM ANY ONE OF THESE ACTIONS MAY  
CAUSE YOUR BID TO BE REJECTED.**

1. **AMENDMENTS:** Have you acknowledged receipt of ALL Amendments? If in doubt as to the number of Amendments issued, please contact our office.
2. **AMENDED BID PAGES:** If any of the Amendments furnished amended bid pages, the amended bid pages must be used in submitting your bid.
3. **LATE BIDS:** In order for a late mailed bid to be considered, generally it must have been sent by either registered or certified mail not later than the fifth calendar day prior to the date specified for the receipt of bids.
4. **BID GUARANTEE:** Sufficient bid guarantee in proper form must be furnished with your bid for jobs exceeding \$100,000.
5. **MISTAKE IN BID:** Have you reviewed your bid prices for possible errors in calculations or work left out?
6. **TELEGRAPHIC MODIFICATIONS:** If you modify your bid by telegram, be sure to allow sufficient time for the telegram to reach us prior to the time set for bid opening. Any doubt should be resolved in favor of allowing Extra Time. FAX transmittals for bids and bid modifications are not acceptable.
7. **BID DOCUMENTS:** Bidders are cautioned to complete and include at least the following documents in their bid:
  - a. A Standard Form (SF) 1442 "Solicitation, Offer, and Award" with acknowledgment of amendments, if any;
  - b. A completed bidding schedule Section 00010
  - c. The section titled "Representation & Certifications, Section 00600
  - d. A bid bond (SF 24); and
  - e. Any other documents required by the solicitation.

**CAUTION TO BIDDERS**

**TABLE OF CONTENTS****DIVISION 0 - BIDDING REQUIREMENTS, CONTRACTS FORMS AND  
CONTRACT CONDITIONS**

Section 001442	Solicitation, Offer, and Award (SF 1442)
Section 00010bs	Bidding Schedule
Section 00010	Solicitation contract form
Section 00100	Instructions to Bidders
Section 00600	Representations and Certifications
Section 00700	Contract Clauses
Section 00800	Special Contract Requirements
Section 00850	Rates of Wages

**DIVISION 1 - GENERAL REQUIREMENTS**

Section 01200a	General Requirements
Section 01200b	Construction Signs
Section 01270	Measurement and Payment
Section 01330a	Submittal Procedures
Section 01330b	Submittal Register (ER 4288)
Section 01330c	Submittal Form (4025)
Section 01354	Environmental Protection for Civil Works
Section 01420	Sources for Reference Publications
Section 01451a	Contractor Quality Control

**DIVISION 2 - SITE WORK**

Section 02000	Mobilization and Demobilization
Section 02020	Dredging

<b>SOLICITATION, OFFER, AND AWARD</b> (Construction, Alteration, or Repair)		1. SOLICITATION NO.  DACW09-03-B-0011	2. TYPE OF SOLICITATION <input checked="" type="checkbox"/> SEALED BID (IFB) <input type="checkbox"/> NEGOTIATED (RFP)	3. DATE ISSUED  8 August 2003	PAGE OF PAGES  1 2
IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.					
4. CONTRACT NO.		5. REQUISITION/PURCHASE REQUEST NO.		6. PROJECT NO.	
7. ISSUED BY  Los Angeles District, COE CESPL-CT-West Region Branch P.O. Box 532711 Los Angeles, CA 90053-2325		CODE	8. ADDRESS OFFER TO  Los Angeles District, COE CESPL-CT-West Region Branch P.O. Box 532711 Los Angeles, CA 90053-2325		
9. FOR INFORMATION CALL:		A. NAME Mary Ann Powers		B. TELEPHONE NO. (Include area code) (NO COLLECT CALLS) (213) 452-3254	

### SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS (Title, identifying no., date):

OCEANSIDE HARBOR MAINTENANCE DREDGING, OCEANSIDE, SAN DIEGO COUNTY, CALIFORNIA

This project consists of annual maintenance dredging of the federal navigation channels of Oceanside Harbor and placement of the material either on the beach or in the nearshore. Amount of dredge material available annually varies from 125,000 cubic meters to 250,000 cubic meters. Multi-year contract for 3 cycles.

The estimated cost of this acquisition is between \$5,000,000.00 - \$10,000,000.00

Any contract awarded as a result of this solicitation is made pursuant to the Small Business Competitiveness Demonstration Program.

11. The Contractor shall begin performance within <u>10</u> calendar days and complete it within <u>65</u> calendar days after receiving <input type="checkbox"/> award, <input checked="" type="checkbox"/> notice to proceed. This performance period is <input checked="" type="checkbox"/> mandatory, <input type="checkbox"/> negotiable. (See _____.)	
12A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? (If "YES," indicate within how many calendar days after award in Item 12B.) <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	12B. CALENDAR DAYS  10
13. ADDITIONAL SOLICITATION REQUIREMENTS:	
A. Sealed offers in original and <u>0</u> copies to perform the work required are due at the place specified in Item 8 by <u>1:00 P.M.</u> (hour) local time <u>Sept. 9, 2003</u> (date). If this is a sealed bid solicitation, offers will be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.	
B. An offer guarantee <input checked="" type="checkbox"/> is, <input type="checkbox"/> is not required.	
C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.	
D. Offers providing less than <u>60</u> calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.	

## OFFER (Must be fully completed by offeror)

14. NAME AND ADDRESS OF OFFEROR (Include ZIP Code)

15. TELEPHONE NO. (Include area code)

16. REMITTANCE ADDRESS (Include only if different than Item 14)

CODE

FACILITY CODE

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within \_\_\_\_\_ calendar days after the date offers are due. (Insert any number equal to or greater than the minimum requirement stated in Item 13D. Failure to insert any number means the offeror accepts the minimum in Item 13D.)

AMOUNTS 

18. The offeror agrees to furnish any required performance and payment bonds.

## 19. ACKNOWLEDGMENT OF AMENDMENTS

(The offeror acknowledges receipt of amendments to the solicitation - give number and date of each)

AMENDMENT NO.

DATE

20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER  
(Type or print)

20B. SIGNATURE

20C. OFFER DATE

## AWARD (To be completed by Government)

21. ITEMS ACCEPTED:

22. AMOUNT

23. ACCOUNTING AND APPROPRIATION DATA

24. SUBMIT INVOICES TO ADDRESS SHOWN IN  
(4 Copies unless otherwise specified)ITEM 

25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO

☐ 10 U.S.C 2304(c) ( ) ☐ 41 U.S.C 253(c) ( )

26. ADMINISTERED BY

CODE

27. PAYMENT WILL BE MADE BY

## CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

☐ 28. NEGOTIATED AGREEMENT Contractor is required to sign this document and return \_\_\_\_\_ copies to issuing office.) Contractor agrees to furnish and deliver all items or perform all work requirements identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this contract.

☐ 29. AWARD (Contractor is not required to sign this document.) Your offer on this solicitation is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.

30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN (Type or print)

31A. NAME OF CONTRACTING OFFICER (Type or print)

30B. SIGNATURE

30C. DATE

31B. UNITED STATES OF AMERICA  
BY31C. AWARD  
DATE

## SECTION 00010

BIDDING SCHEDULE

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Amount</u>
1.	MOBILIZATION AND DEMOBILIZATION, FIRST YEAR CYCLE	1	Job	Lump Sum	\$ _____
2.	DREDGING, FIRST YEAR CYCLE: ENTRANCE CHANNEL and ADVANCE MAINTENANCE AREA, DEL MAR and OCEANSIDE CHANNELS				
2A.	First 80,000 m <sup>3</sup>	80,000	Cubic Meters	\$ _____	\$ _____
2B.	Over 80,000 m <sup>3</sup>	60,000	Cubic Meters	\$ _____	\$ _____

OPTION ITEMS

3.	MOBILIZATION AND DEMOBILIZATION, SECOND YEAR CYCLE	1	Job	Lump Sum	\$ _____
4.	DREDGING, SECOND YEAR CYCLE: ENTRANCE CHANNEL and ADVANCE MAINTENANCE AREA, DEL MAR and OCEANSIDE CHANNELS				
4A.	First 80,000 m <sup>3</sup>	80,000	Cubic Meters	\$ _____	\$ _____
4B.	Over 80,000 m <sup>3</sup>	60,000	Cubic Meters	\$ _____	\$ _____
5.	MOBILIZATION AND DEMOBILIZATION, THIRD YEAR CYCLE	1	Job	Lump Sum	\$ _____
6.	DREDGING, THIRD YEAR CYCLE: ENTRANCE CHANNEL and ADVANCE MAINTENANCE AREA, DEL MAR and OCEANSIDE CHANNELS				
6A.	First 80,000 m <sup>3</sup>	80,000	Cubic Meters	\$ _____	\$ _____
6B.	Over 80,000 m <sup>3</sup>	60,000	Cubic Meters	\$ _____	\$ _____

TOTAL BID	TOTAL ESTIMATED AMOUNT	\$ _____.
-----------	------------------------	-----------

## NOTES:

1. All extensions of the unit prices shown will be subject to verification by the Government. In cases of variation between the unit price and extension, the unit price will be considered to be the bid.
2. If a bid or modification to a bid based on unit prices is submitted which provides for a lump sum adjustment to the total amount, the application of the lump sum adjustment to each unit price in the Schedule must be stated. If it is not stated, the bidder agrees that the lump sum adjustment shall be applied on a pro-rata basis to every unit price in the Schedule.
3. Amounts and prices shall be indicated in either figures or words, NOT BOTH.
4. Bids shall be submitted on all items of the Schedule.
5. All quantities not identified as Lump Sum are considered to be Estimated.
6. The Option Items may be exercised in accordance with SECTION: INSTRUCTIONS TO BIDDERS. Exercises of the options will be made by the Contracting Officer in writing. For determination of low bidder, see paragraph in SECTION 00100: INSTRUCTIONS, CONDITIONS, AND NOTICE TO BIDDERS
7. The Contractor shall furnish all plant, labor, material, equipment, etc., necessary to perform all work in strict accordance with the terms and conditions set forth in the contract to include all attachment thereto.

**Section 00010**  
**Solicitation Contract Form**

CLAUSES INCORPORATED BY FULL TEXT

1. All extensions of the unit prices shown will be subject to verification by the Government. In case of variation between the unit price and the extension, the unit price will be considered to be the bid.
2. If a modification to a bid based on unit prices is submitted which provides for a lump sum adjustment to the total estimated amount, the application of the lump sum adjustment to each unit price in the Price Schedule must be stated. If it is not stated, the bidder agrees that the lump sum adjustment shall be applied on a pro rata basis to every unit price in the Price Schedule.
3. Prices must be submitted on all individual items of the Price Schedule, otherwise the bid will be considered non-responsive and will be rejected.
4. For the purpose of initial evaluation of bids, the following will be utilized in resolving arithmetic discrepancies found on the face of the Price Schedule as submitted by the bidder:
  - a. Obviously misplaced decimal points will be corrected;
  - b. In case of discrepancy between the unit price and the extended price, the unit price will govern;
  - c. Apparent errors in extensions of unit prices will be corrected;
  - d. Apparent errors in addition of lump sum and extended prices will be corrected.
5. For the purpose of bid evaluation, the Government will proceed on the assumption that the bidder intends the bid to be evaluated on the basis of unit prices the totals arrived at by the resolution of arithmetic discrepancies as provided above and the bid will be so reflected on the abstract of bids.
6. The lump sum "LS" line items in the Price Schedule are not "Estimated Quantity" line items and are not subject to the "Variation in Estimated Quantity" contract clause.
7. The Contract Clause 52.232-27, "Prompt Payment for Construction Contracts" requires that the name and address of the contractor official, to whom payment is to be sent, be the same as that in the contract or in a proper Notice of Assignment.
8. Principal Contracting Officer. The Contracting Officer who signs this contract will be the Principal Contracting Officer for this contract. However, any Contracting Officer assigned to the Los Angeles District, contracting within his authority, may take formal action on this contract when the Principal Contracting Officer is unavailable and the action needs to be taken.
9. Amounts and prices shall be indicated in either words or figures, NOT BOTH.
10. Payment of Electronic Funds Transfer (EFT) is the mandatory method of payment. The Contractors attention is directed to Contract Clause NO. 52.232-33 "Mandatory Information for Electronic Funds Transfer" located in Section 00800.
11. The bidder shall distribute his indirect costs (overhead, profit, bond, etc.,) over all items in the Price Schedule. The Government will review all submitted Price Schedules for any unbalancing of the items. Any submitted Price Schedule determined to be unbalanced may be considered nonresponsive and cause the bidder to be ineligible for contract award.
12. The bidder shall furnish all plant, labor, material, equipment, etc., necessary to perform all work in strict accordance with the terms and conditions set forth in the contract in include all attachments thereto.
13. Some quantities are ESTIMATED, the bidders prices MUST BE FIRM.

14. Bidder is cautioned to check his Price Schedule carefully prior to submission. If the Price Schedule contains unit prices, they should be round off to the second decimal point only NOT EXTENDED FURTHER.

15. Bidders attention is directed to Section 00100 "Instructions to Bidders" Clause No. 52.0214-400, entitled "Directions for Submitting Bids". Please note that there are Special Instructions Pertaining to Hand-Carried Bids.

16. Contractor is required to fill in Cage code (Reference Section 00600, entitled "Required Central Contractor Registration" Mar 1998) and DUNS Number (Reference Section 00600, entitled, "Data Universal Numbering System (DUNS) Number" Jun1999) in Block No. 15 on Standard Form 1442, Name and Address Block (Cage Code under Code and DUNS No. under Facility Code respectively).

17. The Government contemplates award on one contract to the responsive, responsible bidder who submits the low bid for the total of all the items in the Price Schedule.



CERTIFICATE OF CORPORATE PRINCIPAL

1) IF THE OFFEROR IS A JOINT VENTURE, COMPLETE THE FOLLOWING:

_____ (Company Name)	_____ (Signature)	_____ (Title)
-------------------------	----------------------	------------------

_____ (Company Name)	_____ (Signature)	_____ (Title)
-------------------------	----------------------	------------------

_____ (Company Name)	_____ (Signature)	_____ (Title)
-------------------------	----------------------	------------------

2) IF THE OFFEROR IS PARTNERSHIP, LIST FULL NAME OF ALL PARTNERS:

_____ (Company Name)	_____ (Signature)	_____ (Title)
-------------------------	----------------------	------------------

_____ (Company Name)	_____ (Signature)	_____ (Title)
-------------------------	----------------------	------------------

_____ (Company Name)	_____ (Signature)	_____ (Title)
-------------------------	----------------------	------------------

3) IF THE OFFEROR IS A CORPORATION, THE FOLLOWING CERTIFICATION SHOULD BE COMPLETED:

CERTIFICATION AS TO CORPORATE PRINCIPAL

I, \_\_\_\_\_, certify that I am the Secretary of the corporation named as principal in the within contract; that \_\_\_\_\_, who signed the said contract on behalf of the principal, was the \_\_\_\_\_ of the corporation; that I know his signature and that his signature is genuine; and that said contract was duly signed, sealed and attested for in behalf of said corporation by authority of its governing body.

\_\_\_\_\_  
CORPORATE PRINCIPAL

CORPORATE SEAL

\_\_\_\_\_  
SECRETARY

**Section 00100**  
**Bidding Schedule/Instructions to Bidders**

52.0000-4010 INQUIRIES .....	2
52.0000-4023 SAFETY REQUIREMENTS .....	2
52.0001-4004 BID RESULTS .....	2
52.211-1 AVAILABILITY OF SPECIFICATIONS LISTED IN THE GSA INDEX OF FEDERAL SPECIFICATIONS, STANDARDS AND COMMERCIAL ITEM DESCRIPTIONS, FPMR PART 101-29 (AUG 1998).....	2
52.211-2 AVAILABILITY OF SPECIFICATIONS LISTED IN THE DOD INDEX OF SPECIFICATIONS AND STANDARDS (DODISS) AND DESCRIPTIONS LISTED IN THE ACQUISITION MANAGEMENT SYSTEMS AND DATA REQUIREMENTS CONTROL LIST, DOD 5010.12-L (DEC 1999).....	3
52.211-14 NOTICE OF PRIORITY RATING FOR NATIONAL DEFENSE USE (SEP 1990).....	3
52.214-3 AMENDMENTS TO INVITATIONS FOR BIDS (DEC 1989) .....	3
52.214-4 FALSE STATEMENTS IN BIDS (APR 1984).....	3
52.214-5 SUBMISSION OF BIDS (MAR 1997) .....	3
52.214-7 LATE SUBMISSIONS, MODIFICATIONS, AND WITHDRAWALS OF BIDS (NOV 1999).....	4
52.214-18 PREPARATION OF BIDS--CONSTRUCTION (APR 1984) .....	4
52.214-19 CONTRACT AWARD--SEALED BIDDING--CONSTRUCTION (AUG 1996) .....	5
52.214-34 SUBMISSION OF OFFERS IN THE ENGLISH LANGUAGE (APR 1991).....	5
52.214-35 SUBMISSION OF OFFERS IN U.S. CURRENCY (APR 1991).....	5
52.0214-4583 TELEGRAPHIC BIDS/OFFERS ARE NOT ACCEPTABLE .....	6
52.0214-4584 FACSIMILE BIDS/OFFERS.....	6
52.0214-4599 EVALUATION FOR AWARD .....	6
52.214-5000 APPARENT CLERICAL MISTAKES (MAR 1995)--EFARS .....	6
52.0214-5001 DIRECTIONS FOR SUBMITTING BIDS (APR 2002) .....	6
52.216-1 TYPE OF CONTRACT (APR 1984).....	9
52.217-5 EVALUATION OF OPTIONS (JUL 1990) .....	9
52.219-4003 SMALL BUSINESS AND SMALL DISADVANTAGED BUSINESS SUBCONTRACTING.....	9
52.225-9 BUY AMERICAN ACT—CONSTRUCTION MATERIALS (MAY 2002).....	9
52.225-10 NOTICE OF BUY AMERICAN ACT REQUIREMENT--CONSTRUCTION MATERIALS (MAY 2002) .....	11
52.225-13 RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUL 2000).....	12
52.225-15 SANCTIONED EUROPEAN UNION COUNTRY END PRODUCTS (FEB 2000).....	13
52.228-1 BID GUARANTEE (SEP 1996).....	13
52.228-4506 INDIVIDUAL SURETIES IN SUPPORT OF BID BONDS.....	13
52.228-4507 BID GUARANTEE FORM AND AMOUNT .....	14
52.232-38 SUBMISSION OF ELECTRONIC FUNDS TRANSFER INFORMATION WITH OFFER (MAY 1999) .....	14
52.233-2 SERVICE OF PROTEST (AUG 1996).....	14
52.236-27 SITE VISIT (CONSTRUCTION) (FEB 1995) – ALTERNATE I (FEB 1995) .....	15
52.252-1 SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998) .....	15

CLAUSES INCORPORATED BY FULL TEXT

52.0000-4010 INQUIRIES

Perspective bidders/offerors should submit inquiries related to this solicitation by writing or calling the following (collect calls will not be accepted:

(1) For inquiries of a contractual nature (solicitation requirements, interpretation of contractual language) call:

Mary Ann Powers

(213) 452-3254

For bid results only, call (213) 452-3235.

(2) All technical questions on the specification or drawings will be submitted in writing to:

Address:

U.S. Army Corps of Engineers

Los Angeles District, Attn: CESPL-CT

P. O. Box 532711

Los Angeles, CA 90053-2325.

(3) Please include the solicitation number, project title and location of project with your questions. Written inquiries must be received by this office not later than 14 calendar days prior to bid opening date/date set for receipt of offers.

(4) Oral explanations or instructions are not binding. Any information given to a bidder/offeror which impacts the bid/offer will be given in the form of a written amendment to the solicitation.

52.0000-4023 SAFETY REQUIREMENTS

The bidder's attention is directed to the latest version of U.S Army Corps of Engineers Safety and Health Manual, EM 385-1-1, which will be strictly enforced. This publication may be obtained from the US Army Engineer District, Los Angeles, ATTN: Safety Office, P.O. Box 532711, Los Angeles, California 90053-2325.

52.0001-4004 BID RESULTS

The telephone number for bid results after the opening is Area Code (213) 452-3235.

52.211-1 AVAILABILITY OF SPECIFICATIONS LISTED IN THE GSA INDEX OF FEDERAL SPECIFICATIONS, STANDARDS AND COMMERCIAL ITEM DESCRIPTIONS, FPMR PART 101-29 (AUG 1998)

(a) The GSA Index of Federal Specifications, Standards and Commercial Item Descriptions, FPMR Part 101-29, and copies of specifications, standards, and commercial item descriptions cited in this solicitation may be obtained for a fee by submitting a request to--GSA Federal Supply Service, Specifications Section, Suite 8100, 470 East L'Enfant Plaza, SW, Washington, DC 20407, Telephone (202) 619-8925, Facsimile (202) 619-8978.

(b) If the General Services Administration, Department of Agriculture, or Department of Veterans Affairs issued this solicitation, a single copy of specifications, standards, and commercial item descriptions cited in this solicitation may be obtained free of charge by submitting a request to the addressee in paragraph (a) of this provision. Additional copies will be issued for a fee.

52.211-2 AVAILABILITY OF SPECIFICATIONS LISTED IN THE DOD INDEX OF SPECIFICATIONS AND STANDARDS (DODISS) AND DESCRIPTIONS LISTED IN THE ACQUISITION MANAGEMENT SYSTEMS AND DATA REQUIREMENTS CONTROL LIST, DOD 5010.12-L (DEC 1999)

Copies of specifications, standards, and data item descriptions cited in this solicitation may be obtained--

(a) From the ASSIST database via the Internet at <http://assist.daps.mil>; or

(b) By submitting a request to the--Department of Defense Single Stock Point (DoDSSP), Building 4, Section D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, Telephone (215) 697-2667/2179, Facsimile (215) 697-1462.

(End of provision)

52.211-14 NOTICE OF PRIORITY RATING FOR NATIONAL DEFENSE USE (SEP 1990)

Any contract awarded as a result of this solicitation will be DX rated order; DO rated order certified for national defense use under the Defense Priorities and Allocations System (DPAS) (15 CFR 700), and the Contractor will be required to follow all of the requirements of this regulation. [Contracting Officer check appropriate box.]

(End of provision)

52.214-3 AMENDMENTS TO INVITATIONS FOR BIDS (DEC 1989)

(a) If this solicitation is amended, then all terms and conditions which are not modified remain unchanged.

(b) Bidders shall acknowledge receipt of any amendment to this solicitation (1) by signing and returning the amendment, (2) by identifying the amendment number and date in the space provided for this purpose on the form for submitting a bid, (3) by letter or telegram, or (4) by facsimile, if facsimile bids are authorized in the solicitation. The Government must receive the acknowledgment by the time and at the place specified for receipt of bids.

(End of provision)

52.214-4 FALSE STATEMENTS IN BIDS (APR 1984)

Bidders must provide full, accurate, and complete information as required by this solicitation and its attachments. The penalty for making false statements in bids is prescribed in 18 U.S.C. 1001.

(End of provision)

52.214-5 SUBMISSION OF BIDS (MAR 1997)

(a) Bids and bid modifications shall be submitted in sealed envelopes or packages (unless submitted by electronic means) (1) addressed to the office specified in the solicitation, and (2) showing the time and date specified for receipt, the solicitation number, and the name and address of the bidder.

(b) Bidders using commercial carrier services shall ensure that the bid is addressed and marked on the outermost envelope or wrapper as prescribed in subparagraphs (a)(1) and (2) of this provision when

delivered to the office specified in the solicitation.

(c) Telegraphic bids will not be considered unless authorized by the solicitation; however, bids may be modified or withdrawn by written or telegraphic notice.

(d) Facsimile bids, modifications, or withdrawals, will not be considered unless authorized by the solicitation.

(e) Bids submitted by electronic commerce shall be considered only if the electronic commerce method was specifically stipulated or permitted by the solicitation.

(End of provision)

#### 52.214-7 LATE SUBMISSIONS, MODIFICATIONS, AND WITHDRAWALS OF BIDS (NOV 1999)

(a) Bidders are responsible for submitting bids, and any modifications or withdrawals, so as to reach the Government office designated in the invitation for bids (IFB) by the time specified in the IFB. If no time is specified in the IFB, the time for receipt is 4:30 p.m., local time, for the designated Government office on the date that bids are due.

(b)(1) Any bid, modification, or withdrawal received at the Government office designated in the IFB after the exact time specified for receipt of bids is "late" and will not be considered unless it is received before award is made, the Contracting Officer determines that accepting the late bid would not unduly delay the acquisition; and--

(i) If it was transmitted through an electronic commerce method authorized by the IFB, it was received at the initial point of entry to the Government infrastructure not later than 5:00 p.m. one working day prior to the date specified for receipt of bids; or

(ii) There is acceptable evidence to establish that it was received at the Government installation designated for receipt of bids and was under the Government's control prior to the time set for receipt of bids.

(2) However, a late modification of an otherwise successful bid that makes its terms more favorable to the Government, will be considered at any time it is received and may be accepted.

(c) Acceptable evidence to establish the time of receipt at the Government installation includes the time/date stamp of that installation on the bid wrapper, other documentary evidence of receipt maintained by the installation, or oral testimony or statements of Government personnel.

(d) If an emergency or unanticipated event interrupts normal Government processes so that bids cannot be received at the Government office designated for receipt of bids by the exact time specified in the IFB and urgent Government requirements preclude amendment of the IFB, the time specified for receipt of bids will be deemed to be extended to the same time of day specified in the solicitation on the first work day on which normal Government processes resume.

(e) Bids may be withdrawn by written notice received at any time before the exact time set for receipt of bids. If the IFB authorizes facsimile bids, bids may be withdrawn via facsimile received at any time before the exact time set for receipt of bids, subject to the conditions specified in the provision at 52.214-31, Facsimile Bids. A bid may be withdrawn in person by a bidder or its authorized representative if, before the exact time set for receipt of bids, the identity of the person requesting withdrawal is established and the person signs a receipt for the bid.

(End of provision)

#### 52.214-18 PREPARATION OF BIDS--CONSTRUCTION (APR 1984)

(a) Bids must be (1) submitted on the forms furnished by the Government or on copies of those forms, and (2) manually signed. The person signing a bid must initial each erasure or change appearing on any bid form.

(b) The bid form may require bidders to submit bid prices for one or more items on various bases, including--

- (1) Lump sum bidding;
- (2) Alternate prices;
- (3) Units of construction; or
- (4) Any combination of subparagraphs (1) through (3) above.

(c) If the solicitation requires bidding on all items, failure to do so will disqualify the bid. If bidding on all items is not required, bidders should insert the words "no bid" in the space provided for any item on which no price is submitted.

(d) Alternate bids will not be considered unless this solicitation authorizes their submission.

(End of provision)

#### 52.214-19 CONTRACT AWARD--SEALED BIDDING--CONSTRUCTION (AUG 1996)

(a) The Government will evaluate bids in response to this solicitation without discussions and will award a contract to the responsible bidder whose bid, conforming to the solicitation, will be most advantageous to the Government, considering only price and the price-related factors specified elsewhere in the solicitation.

(b) The Government may reject any or all bids, and waive informalities or minor irregularities in bids received.

(c) The Government may accept any item or combination of items, unless doing so is precluded by a restrictive limitation in the solicitation or the bid.

(d) The Government may reject a bid as nonresponsive if the prices bid are materially unbalanced between line items or subline items. A bid is materially unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated in relation to cost for other work, and if there is a reasonable doubt that the bid will result in the lowest overall cost to the Government even though it may be the low evaluated bid, or if it is so unbalanced as to be tantamount to allowing an advance payment.

(End of provision)

#### 52.214-34 SUBMISSION OF OFFERS IN THE ENGLISH LANGUAGE (APR 1991)

Offers submitted in response to this solicitation shall be in the English language. Offers received in other than English shall be rejected.

(End of provision)

#### 52.214-35 SUBMISSION OF OFFERS IN U.S. CURRENCY (APR 1991)

Offers submitted in response to this solicitation shall be in terms of U.S. dollars. Offers received in other than U.S. dollars shall be rejected.

(End of provision)

52.0214-4583 TELEGRAPHIC BIDS/OFFERS ARE NOT ACCEPTABLE

Any telegram to modify or withdraw a bid/offer sent to this office must be physically delivered to the office designated for receipt of bid/offer by the date and time set for bid opening/receipt of proposals. No one from this office will be dispatched to the local telegraph office to pick up any telegram for any reason.

52.0214-4584 FACSIMILE BIDS/OFFERS

Facsimile bids/offers, modifications thereto, or cancellations of bids/offers will not be accepted.

52.0214-4599 EVALUATION FOR AWARD

The Government contemplates award of one contract to the responsive, responsible bidder who submits the low bid for the total of all the items in the Bidding Schedule.

52.214-5000 APPARENT CLERICAL MISTAKES (MAR 1995)--EFARS

(a) For the purpose of initial evaluations of bids, the following will be utilized in the resolving arithmetic discrepancies found on the face of bidding schedule as submitted by the bidder:

- (1) Obviously misplaced decimal points will be corrected;
- (2) Discrepancy between unit price and extended price, the unit price will govern;
- (3) Apparent errors in extension of unit prices will be corrected;
- (4) Apparent errors in addition of lump-sum and extended prices will be corrected.

(b) For the purpose of bid evaluation, the government will proceed on the assumption that the bidder intends his bid to be evaluated on basis of the unit prices, the totals arrived at by resolution of arithmetic discrepancies as provided above and the bid will be so reflected on the abstract of bids.

(c) These correction procedures shall not be used to resolve any ambiguity concerning which bid is low.

(End of statement)

52.0214-5001 DIRECTIONS FOR SUBMITTING BIDS (APR 2002)

Envelopes containing bids must be sealed, marked and addressed as follows:

MARK ENVELOPES:

Bid under IFB No. DACW09-03-B-0011  
Bid Opening Date: 4 SEPTEMBER 2003 @ 1:00 P.M.

ADDRESS ENVELOPES TO:

Department of the Army  
U. S. Army Engineer District, Los Angeles  
ATTN: Contracting Division  
C/O: Mary Ann Powers  
P. O. Box 532711  
Los Angeles, CA 90053-2325

SPECIAL INSTRUCTIONS PERTAINING TO HAND-CARRIED BIDS:

Due to security precautions, all Corps of Engineers visitors/couriers are now required to check in at the Public Affairs Office (PAO), Suite 980, Wilshire Blvd, Los Angeles, CA. Bidders are no longer permitted

to hand-carry their bids directly to Contracting Division without an authorized escort. **Bids may NOT be left unattended at the Public Affairs Office (PAO), Suite 980.**

Bidders who desire to hand-deliver their bids prior to the scheduled bid opening time/date must notify the Contracting Division to arrange for receipt of their bid by Contracting Division personnel. Normally the contact will be the Contract Specialist designated above. In the event the Contract Specialist cannot be reached, please call the main Contracting Division telephone number, 213-452-3231 or the following alternative telephone numbers -3233, -3245, -3234, or -3235, in order to request assistance.

**30 minutes prior to the scheduled bid opening time/date**, the Bid Opening Officer will be in the Public Affairs Office (PAO) Suite 980, to accept bids. After visitor in-processing, all bidders will subsequently be escorted to Bid Opening Room, where the bids will be publicly opened and read.

**In order to expedite visitor processing, bidders are encouraged to complete the information requested on the Notice of Visitor(s) Form (attached). The completed form can be faxed to the Contract Specialist at (213)452-4184 or 4187, prior to the date for receipt of bids. In addition, no more than 2 visitors per firm will be permitted within the building. No exceptions will be made. The offeror is responsible for compliance with the security requirements and shall ensure that any company representative, courier or delivery personnel are aware of these special procedures pertaining to hand carried bids.**



<b>NOTICE OF VISITOR(S)</b>		
<b>1. Date(s) of Visit (<i>Inclusive</i>)</b>		<b>2. Arrival Time</b>
<b>3. Name of Visitor(s) (<i>Last, First</i>)</b>		<b>4. Agency/Company of Visitor</b>
<b>5. Name of Person Being Visited (<i>Include Div, Br, Sec</i>)</b>	<b>6. Suite Number</b>	<b>7. Telephone Number</b>
<b>8. Contact Person (<i>if other than Person Being Visited</i>)</b>		<b>9. Telephone Number</b>
<b>10. Other Comments or Instructions</b>		
<ul style="list-style-type: none"><li>- All visitors must report to the Public Affairs Office, Suite 980</li><li>- Visitors must use the Visitor Tag provided.</li><li>- Visitors must be escorted to Corps of Engineers floors</li><li>- Parking validation is only available for Engineering Division, Construction-Operations, and Information Management field personnel.</li><li>- Delivery personnel will be validated for 30 minutes only.</li></ul>		

52.216-1 TYPE OF CONTRACT (APR 1984)

The Government contemplates award of a firm-fixed price contract resulting from this solicitation.

(End of clause)

52.217-5 EVALUATION OF OPTIONS (JUL 1990)

(a) Except when it is determined in accordance with FAR 17.206(b) not to be in the Government's best interests, the Government will evaluate offers for award purposes by adding the total price for all options to the total price for the basic requirement. Evaluation of options will not obligate the Government to exercise the option(s).

(b) The Government may reject an offer as nonresponsive if it is materially unbalanced as to prices for the basic requirement and the option quantities. An offer is unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated for other work.

(End of provision)

52.219-4003 SMALL BUSINESS AND SMALL DISADVANTAGED BUSINESS  
SUBCONTRACTING

Offerors are cautioned that failure to comply in good faith with the CONTRACT CLAUSE entitled (1) "Utilization of Small, Small Disadvantaged and Women-Owned Small Business Concerns, FAR 52-219-8" and (2) Small, Small Disadvantaged and Women-Owned Small Business Subcontracting Plan, FAR 52.219-9 (Alternate I)," when applicable, will be a material breach of contract. In order to assist prime contractors in developing a source list of Small and Small Disadvantaged Business Concerns, you are encouraged to contact Minority Contractor Associations, the Minority Business Development Agency, and the appropriate General Business Service Centers in your standard Metropolitan Statistical Area, addresses of which may be obtain from:

Write: US Army Engineer District, Los Angeles  
ATTN: CESPL-DD-B  
P.O. Box 532711  
Los Angeles, California 90053-2325  
Telephone: Daniel Hanas  
Small and Disadvantaged Business Utilization  
Specialist  
Area Code (213) 452-3937

52.225-9 BUY AMERICAN ACT—CONSTRUCTION MATERIALS (MAY 2002)

(a) Definitions. As used in this clause--

Component means an article, material, or supply incorporated directly into a construction material.

Construction material means an article, material, or supply brought to the construction site by the Contractor or a subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

Cost of components means--

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the end product (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the end product.

Domestic construction material means--

(1) An unmanufactured construction material mined or produced in the United States; or

(2) A construction material manufactured in the United States, if the cost of its components mined, produced, or manufactured in the United States exceeds 50 percent of the cost of all its components. Components of foreign origin of the same class or kind for which nonavailability determinations have been made are treated as domestic.

Foreign construction material means a construction material other than a domestic construction material.

United States means the 50 States and the District of Columbia, U.S. territories and possessions, Puerto Rico, the Northern Mariana Islands, and any other place subject to U.S. jurisdiction, but does not include leased bases.

(b) Domestic preference. (1) This clause implements the Buy American Act (41 U.S.C. 10a-10d) by providing a preference for domestic construction material. The Contractor shall use only domestic construction material in performing this contract, except as provided in paragraphs (b)(2) and (b)(3) of this clause.

(2) This requirement does not apply to the construction material or components listed by the Government as follows: none [Contracting Officer to list applicable excepted materials or indicate "none"]

(3) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(2) of this clause if the Government determines that

(i) The cost of domestic construction material would be unreasonable. The cost of a particular domestic construction material subject to the requirements of the Buy American Act is unreasonable when the cost of such material exceeds the cost of foreign material by more than 6 percent;

(ii) The application of the restriction of the Buy American Act to a particular construction material would be impracticable or inconsistent with the public interest; or

(iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American Act. (1)(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(3) of this clause shall include adequate information for Government evaluation of the request, including--

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American Act applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(3)(i) of this clause.

(3) Unless the Government determines that an exception to the Buy American Act applies, use of foreign construction material is noncompliant with the Buy American Act.

(d) Data. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison

Construction material description	Unit of measure	Quantity	Price (dollars) \1\
Item 1			
Foreign construction material....			
Domestic construction material...			
Item 2			
Foreign construction material....			
Domestic construction material...			

Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued).

List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.

Include other applicable supporting information.

(End of clause)

(a) Definitions. Construction material, domestic construction material, and foreign construction material, as used in this provision, are defined in the clause of this solicitation entitled "Buy American Act--Construction Materials" (Federal Acquisition Regulation (FAR) clause 52.225-9).

(b) Requests for determinations of inapplicability. An offeror requesting a determination regarding the inapplicability of the Buy American Act should submit the request to the Contracting Officer in time to allow a determination before submission of offers. The offeror shall include the information and applicable supporting data required by paragraphs (c) and (d) of the clause at FAR 52.225-9 in the request. If an offeror has not requested a determination regarding the inapplicability of the Buy American Act before submitting its offer, or has not received a response to a previous request, the offeror shall include the information and supporting data in the offer.

(c) Evaluation of offers. (1) The Government will evaluate an offer requesting exception to the requirements of the Buy American Act, based on claimed unreasonable cost of domestic construction material, by adding to the offered price the appropriate percentage of the cost of such foreign construction material, as specified in paragraph (b)(3)(i) of the clause at FAR 52.225-9.

(2) If evaluation results in a tie between an offeror that requested the substitution of foreign construction material based on unreasonable cost and an offeror that did not request an exception, the Contracting Officer will award to the offeror that did not request an exception based on unreasonable cost.

(d) Alternate offers.

(1) When an offer includes foreign construction material not listed by the Government in this solicitation in paragraph (b)(2) of the clause at FAR 52.225-9, the offeror also may submit an alternate offer based on use of equivalent domestic construction material.

(2) If an alternate offer is submitted, the offeror shall submit a separate Standard Form 1442 for the alternate offer, and a separate price comparison table prepared in accordance with paragraphs (c) and (d) of the clause at FAR 52.225-9 for the offer that is based on the use of any foreign construction material for which the Government has not yet determined an exception applies.

(3) If the Government determines that a particular exception requested in accordance with paragraph (c) of the clause at FAR 52.225-9 does not apply, the Government will evaluate only those offers based on use of the equivalent domestic construction material, and the offeror shall be required to furnish such domestic construction material. An offer based on use of the foreign construction material for which an exception was requested--

(i) Will be rejected as nonresponsive if this acquisition is conducted by sealed bidding; or

(ii) May be accepted if revised during negotiations.

(End of provision)

#### 52.225-13 RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUL 2000)

(a) The Contractor shall not acquire, for use in the performance of this contract, any supplies or services originating from sources within, or that were located in or transported from or through, countries whose products are banned from importation into the United States under regulations of the Office of Foreign Assets Control, Department of the Treasury. Those countries are Cuba, Iran, Iraq, Libya, North Korea, Sudan, the territory of Afghanistan controlled by the Taliban, and Serbia (excluding the territory of Kosovo).

(b) The Contractor shall not acquire for use in the performance of this contract any supplies or services from entities controlled by the government of Iraq.

(c) The Contractor shall insert this clause, including this paragraph (c), in all subcontracts.

(End of clause)

52.225-15 SANCTIONED EUROPEAN UNION COUNTRY END PRODUCTS (FEB 2000)

(a) Definitions. As used in this clause--

Sanctioned European Union country end product means an article that--

(1) Is wholly the growth, product, or manufacture of a sanctioned European Union (EU) member state; or

(2) In the case of an article that consists in whole or in part of materials from another country, has been substantially transformed in a sanctioned EU member state into a new and different article of commerce with a name, character, or use distinct from that of the article or articles from which it was transformed. The term refers to a product offered for purchase under a supply contract, but for purposes of calculating the value of the end product includes services (except transportation services) incidental to the article, provided that the value of those incidental services does not exceed that of the article itself.

Sanctioned European Union member state means Austria, Belgium, Denmark, Finland, France, Ireland, Italy, Luxembourg, the Netherlands, Sweden, or the United Kingdom.

(b) The Contractor shall not deliver any sanctioned European Union country end products under this contract.

(End of clause)

52.228-1 BID GUARANTEE (SEP 1996)

(a) Failure to furnish a bid guarantee in the proper form and amount, by the time set for opening of bids, may be cause for rejection of the bid.

(b) The bidder shall furnish a bid guarantee in the form of a firm commitment, e.g., bid bond supported by good and sufficient surety or sureties acceptable to the Government, postal money order, certified check, cashier's check, irrevocable letter of credit, or, under Treasury Department regulations, certain bonds or notes of the United States. The Contracting Officer will return bid guarantees, other than bid bonds, (1) to unsuccessful bidders as soon as practicable after the opening of bids, and (2) to the successful bidder upon execution of contractual documents and bonds (including any necessary coinsurance or reinsurance agreements), as required by the bid as accepted.-

(c) The amount of the bid guarantee shall be 20 percent of the bid price or \$3,000,000.00, whichever is less.-

(d) If the successful bidder, upon acceptance of its bid by the Government within the period specified for acceptance, fails to execute all contractual documents or furnish executed bond(s) within 10 days after receipt of the forms by the bidder, the Contracting Officer may terminate the contract for default.-

(e) In the event the contract is terminated for default, the bidder is liable for any cost of acquiring the work that exceeds the amount of its bid, and the bid guarantee is available to offset the difference.

(End of clause)

52.228-4506 INDIVIDUAL SURETIES IN SUPPORT OF BID BONDS

Bidder/offerors utilizing individual sureties in support of a bid bond shall include a Standard Form (SF) 28 (Affidavit of Individual

Surety), accompanied by a pledge of acceptable assets from each person acting as an individual surety, and include these with the SF 24 (Bid Bond), and the bid itself (see clause titled "Pledges of Assets," FAR 52.228-11).

Pledges of acceptable assets shall be in the form of (1) evidence of an escrow account and/or (2) a recorded lien on real estate. If this is an RFP, failure to provide required documentation described herein may cause the offeror to be deemed "unacceptable".

#### 52.228-4507 BID GUARANTEE FORM AND AMOUNT

When bids/proposals exceed \$100,000, the offeror shall furnish a separated bid guarantee in accordance with the solicitation provision titled "Bid Guarantee", FAR 52.228-1. In accordance with FAR 28.101-2 the bid guarantee amount shall be a least 20 percent of the "bid price" but shall not exceed \$3 million. When the penal sum is expressed as a percentage, a maximum dollar limitation may be stated. If there are option line items on the Pricing Schedule (Schedule B), the term "bid price" is hereby defined as the total bid not to include any amount for line items designated as "options". In bids/proposals that contain "additives", the "bid price" is defined as the total of all bid items including additive line items. FAR 28.106-1 states that a Standard Form (SF) 24 shall be used for the bid bond. In accordance with FAR 28.202(a)(1), corporate sureties utilized must appear on the list contained in the Department of Treasury Circular 570 titled "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and Acceptable Reinsuring Companies."

#### 52.232-38 SUBMISSION OF ELECTRONIC FUNDS TRANSFER INFORMATION WITH OFFER (MAY 1999)

The offeror shall provide, with its offer, the following information that is required to make payment by electronic funds transfer (EFT) under any contract that results from this solicitation. This submission satisfies the requirement to provide EFT information under paragraphs (b)(1) and (j) of the clause at 52.232-34, Payment by Electronic Funds Transfer--Other than Central Contractor Registration.

- (1) The solicitation number (or other procurement identification number).
- (2) The offeror's name and remittance address, as stated in the offer.
- (3) The signature (manual or electronic, as appropriate), title, and telephone number of the offeror's official authorized to provide this information.
- (4) The name, address, and 9-digit Routing Transit Number of the offeror's financial agent.
- (5) The offeror's account number and the type of account (checking, savings, or lockbox).
- (6) If applicable, the Fedwire Transfer System telegraphic abbreviation of the offeror's financial agent.
- (7) If applicable, the offeror shall also provide the name, address, telegraphic abbreviation, and 9-digit Routing Transit Number of the correspondent financial institution receiving the wire transfer payment if the offeror's financial agent is not directly on-line to the Fedwire and, therefore, not the receiver of the wire transfer payment.  
(End of provision)

#### 52.233-2 SERVICE OF PROTEST (AUG 1996)

(a) Protests, as defined in section 33.101 of the Federal Acquisition Regulation, that are filed directly with an agency, and copies of any protests that are filed with the General Accounting Office (GAO), shall be served on the Contracting Officer (addressed as follows) by obtaining written and dated acknowledgment of receipt from Patricia B. Bonilla, C/O Mary Ann Powers, P. O. Box 532711, Los Angeles, CA 90053-2325

(b) The copy of any protest shall be received in the office designated above within one day of filing a protest with the GAO.

(End of provision)

52.236-27 SITE VISIT (CONSTRUCTION) (FEB 1995) – ALTERNATE I (FEB 1995)

(a) The clauses at 52.236-2, Differing Site Conditions, and 52.236-3, Site Investigations and Conditions Affecting the Work, will be included in any contract awarded as a result of this solicitation. Accordingly, offerors or quoters are urged and expected to inspect the site where the work will be performed.

(b) No organized site visit will be conducted for this project.

(End of provision)

52.252-1 SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es):

<http://www.anet.gov.far>  
<http://farsite.hill.af.mil>  
<http://www.dtic.mil.dfars>

(End of provision)



**Section 00600**  
**Representations & Certifications**

CLAUSES INCORPORATED BY FULL TEXT .....	2
52.203-2 CERTIFICATE OF INDEPENDENT PRICE DETERMINATION (APR 1985) .....	2
52.203-11 CERTIFICATION AND DISCLOSURE REGARDING PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (APR 1991) .....	3
52.204-3 TAXPAYER IDENTIFICATION (OCT 1998) .....	3
52.204-6 DATA UNIVERSAL NUMBERING SYSTEM (DUNS) NUMBER (JUN 99) .....	5
52.209-5 CERTIFICATION REGARDING DEBARMENT, SUSPENSION, PROPOSED DEBARMENT, AND OTHER RESPONSIBILITY MATTERS (DEC 2001) .....	6
52.219-1 SMALL BUSINESS PROGRAM REPRESENTATIONS (APR 2002) .....	7
52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000) .....	10
52.222-21 PROHIBITION OF SEGREGATED FACILITIES (FEB 1999) .....	11
52.222-22 PREVIOUS CONTRACTS AND COMPLIANCE REPORTS (FEB 1999) .....	12
52.223-13 CERTIFICATION OF TOXIC CHEMICAL RELEASE REPORTING (OCT 2000) .....	12
252.204-7001 COMMERCIAL AND GOVERNMENT ENTITY (CAGE) CODE REPORTING (AUG 1999) .....	13
252.204-7004 REQUIRED CENTRAL CONTRACTOR REGISTRATION (NOV 2001) .....	14
252.209-7001 DISCLOSURE OF OWNERSHIP OR CONTROL BY THE GOVERNMENT OF A TERRORIST COUNTRY (MAR 1998) .....	15
252.247-7022 REPRESENTATION OF EXTENT OF TRANSPORTATION BY SEA (AUG 1992) .....	16

CLAUSES INCORPORATED BY FULL TEXT

52.203-2 CERTIFICATE OF INDEPENDENT PRICE DETERMINATION (APR 1985)

(a) The offeror certifies that --

(1) The prices in this offer have been arrived at independently, without, for the purpose of restricting competition, any consultation, communication, or agreement with any other offeror or competitor relating to --

(i) Those prices,

(ii) The intention to submit an offer, or

(iii) The methods of factors used to calculate the prices offered:

(2) The prices in this offer have not been and will not be knowingly disclosed by the offeror, directly or indirectly, to any other offeror or competitor before bid opening (in the case of a sealed bid solicitation) or contract award (in the case of a negotiated solicitation) unless otherwise required by law; and

(3) No attempt has been made or will be made by the offeror to induce any other concern to submit or not to submit an offer for the purpose of restricting competition.

(b) Each signature on the offer is considered to be a certification by the signatory that the signatory --

(1) Is the person in the offeror's organization responsible for determining the prices offered in this bid or proposal, and that the signatory has not participated and will not participate in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision; or

(2) (i) Has been authorized, in writing, to act as agent for the following principals in certifying that those principals have not participated, and will not participate in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision

\_\_\_\_\_ (insert full name of person(s) in the offeror's organization responsible for determining the prices offered in this bid or proposal, and the title of his or her position in the offeror's organization);

(ii) As an authorized agent, does certify that the principals named in subdivision (b)(2)(i) above have not participated, and will not participate, in any action contrary to subparagraphs (a)(1) through (a)(3) above; and

(iii) As an agent, has not personally participated, and will not participate, in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision.

(c) If the offeror deletes or modifies subparagraph (a)(2) of this provision, the offeror must furnish with its offer a signed statement setting forth in detail the circumstances of the disclosure.

(End of clause)

#### 52.203-11 CERTIFICATION AND DISCLOSURE REGARDING PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (APR 1991)

(a) The definitions and prohibitions contained in the clause, at FAR 52.203-12, Limitation on Payments to Influence Certain Federal Transactions, included in this solicitation, are hereby incorporated by reference in paragraph (b) of this Certification.

(b) The offeror, by signing its offer, hereby certifies to the best of his or her knowledge and belief that on or after December 23, 1989,--

(1) No Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress on his or her behalf in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment or modification of any Federal contract, grant, loan, or cooperative agreement;

(2) If any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress or an employee of a Member of Congress on his or her behalf in connection with this solicitation, the offeror shall complete and submit, with its offer, OMB standard form LLL, Disclosure of Lobbying Activities, to the Contracting Officer; and

(3) He or she will include the language of this certification in all subcontract awards at any tier and require that all recipients of subcontract awards in excess of \$100,000 shall certify and disclose accordingly.

(c) Submission of this certification and disclosure is a prerequisite for making or entering into this contract imposed by section 1352, title 31, United States Code. Any person who makes an expenditure prohibited under this provision, shall be subject to a civil penalty of not less than \$10,000, and not more than \$100,000, for each such failure.

(End of provision)

#### 52.204-3 TAXPAYER IDENTIFICATION (OCT 1998)

(a) Definitions.

“Common parent,” as used in this provision, means that corporate entity that owns or controls an affiliated group of corporations that files its Federal income tax returns on a consolidated basis, and of which the offeror is a member.

“Taxpayer Identification Number (TIN),” as used in this provision, means the number required by the Internal Revenue Service (IRS) to be used by the offeror in reporting income tax and other returns. The TIN may be either a Social Security Number or an Employer Identification Number.

(b) All offerors must submit the information required in paragraphs (d) through (f) of this provision to comply with debt collection requirements of 31 U.S.C. 7701(c) and 3325(d), reporting requirements of 26 U.S.C. 6041, 6041A, and 6050M, and implementing regulations issued by the IRS. If the resulting contract is subject to the payment reporting requirements described in Federal Acquisition Regulation (FAR) 4.904, the failure or refusal by the offeror to furnish the information may result in a 31 percent reduction of payments otherwise due under the contract.

(c) The TIN may be used by the Government to collect and report on any delinquent amounts arising out of the offeror's relationship with the Government (31 U.S.C. 7701(c)(3)). If the resulting contract is subject to the payment reporting requirements described in FAR 4.904, the TIN provided hereunder may be matched with IRS records to verify the accuracy of the offeror's TIN.

(d) Taxpayer Identification Number (TIN).

\_\_\_ TIN: \_\_\_\_\_

\_\_\_ TIN has been applied for.

\_\_\_ TIN is not required because:

\_\_\_ Offeror is a nonresident alien, foreign corporation, or foreign partnership that does not have income effectively connected with the conduct of a trade or business in the United States and does not have an office or place of business or a fiscal paying agent in the United States;

\_\_\_ Offeror is an agency or instrumentality of a foreign government;

\_\_\_ Offeror is an agency or instrumentality of the Federal Government.

(e) Type of organization.

\_\_\_ Sole proprietorship;

\_\_\_ Partnership;

- \_\_\_ Corporate entity (not tax-exempt);
- \_\_\_ Corporate entity (tax-exempt);
- \_\_\_ Government entity (Federal, State, or local);
- \_\_\_ Foreign government;
- \_\_\_ International organization per 26 CFR 1.6049-4;
- \_\_\_ Other \_\_\_\_\_

(f) Common parent.

\_\_\_ Offeror is not owned or controlled by a common parent as defined in paragraph (a) of this provision.

\_\_\_ Name and TIN of common parent:

Name \_\_\_\_\_

TIN \_\_\_\_\_

(End of provision)

#### 52.204-6 DATA UNIVERSAL NUMBERING SYSTEM (DUNS) NUMBER (JUN 99)

(a) The offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation "DUNS" followed by the DUNS number that identifies the offeror's name and address exactly as stated in the offer.

(b) If the offeror does not have a DUNS number, it should contact Dun and Bradstreet directly to obtain one. A DUNS number will be provided immediately by telephone at no charge to the offeror. For information on obtaining a DUNS number, the offeror, if located within the United States, should call Dun and Bradstreet at 1-800-333-0505. The offeror should be prepared to provide the following information:

- (1) Company name.
- (2) Company address.
- (3) Company telephone number.
- (4) Line of business.

(5) Chief executive officer/key manager.

(6) Date the company was started.

(7) Number of people employed by the company.

(8) Company affiliation.

(c) Offerors located outside the United States may obtain the location and phone number of the local Dun and Bradstreet Information Services office from the Internet Home Page at <http://www.customerservice@dnb.com>. If an offeror is unable to locate a local service center, it may send an e-mail to Dun and Bradstreet at [globalinfo@mail.dnb.com](mailto:globalinfo@mail.dnb.com).

(End of provision)

52.209-5 CERTIFICATION REGARDING DEBARMENT, SUSPENSION, PROPOSED DEBARMENT, AND OTHER RESPONSIBILITY MATTERS (DEC 2001)

(a)(1) The Offeror certifies, to the best of its knowledge and belief, that--

(i) The Offeror and/or any of its Principals--

(A) Are ( ) are not ( ) presently debarred, suspended, proposed for debarment, or declared ineligible for the award of contracts by any Federal agency;

(B) Have ( ) have not ( ), within a three-year period preceding this offer, been convicted of or had a civil judgment rendered against them for: commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, state, or local) contract or subcontract; violation of Federal or state antitrust statutes relating to the submission of offers; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, tax evasion, or receiving stolen property; and

(C) Are ( ) are not ( ) presently indicted for, or otherwise criminally or civilly charged by a governmental entity with, commission of any of the offenses enumerated in subdivision (a)(1)(i)(B) of this provision.

(ii) The Offeror has ( ) has not ( ), within a three-year period preceding this offer, had one or more contracts terminated for default by any Federal agency.

(2) "Principals," for the purposes of this certification, means officers; directors; owners; partners; and, persons having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a subsidiary, division, or business segment, and similar positions).

THIS CERTIFICATION CONCERNS A MATTER WITHIN THE JURISDICTION OF AN AGENCY OF THE UNITED STATES AND THE MAKING OF A FALSE, FICTITIOUS, OR FRAUDULENT CERTIFICATION MAY RENDER THE MAKER SUBJECT TO PROSECUTION UNDER SECTION 1001, TITLE 18, UNITED STATES CODE.

(b) The Offeror shall provide immediate written notice to the Contracting Officer if, at any time prior to contract award, the Offeror learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

(c) A certification that any of the items in paragraph (a) of this provision exists will not necessarily result in withholding of an award under this solicitation. However, the certification will be considered in connection with a determination of the Offeror's responsibility. Failure of the Offeror to furnish a certification or provide such additional information as requested by the Contracting Officer may render the Offeror nonresponsible.

(d) Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by paragraph (a) of this provision. The knowledge and information of an Offeror is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

(e) The certification in paragraph (a) of this provision is a material representation of fact upon which reliance was placed when making award. If it is later determined that the Offeror knowingly rendered an erroneous certification, in addition to other remedies available to the Government, the Contracting Officer may terminate the contract resulting from this solicitation for default.

(End of provision)

#### 52.219-1 SMALL BUSINESS PROGRAM REPRESENTATIONS (APR 2002)

(a)(1) The North American Industry Classification System (NAICS) code for this acquisition is ( ) (insert NAICS code).

(2) The small business size standard is ( ) (insert size standard).

(3) The small business size standard for a concern which submits an offer in its own name, other than on a construction or service contract, but which proposes to furnish a product which it did not itself manufacture, is 500 employees.

(b) Representations. (1) The offeror represents as part of its offer that it ( ) is, ( ) is not a small business concern.

(2) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents, for general statistical purposes, that it ( ) is, ( ) is not a small disadvantaged business concern as defined in 13 CFR 124.1002.

(3) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents as part of its offer that it ( ) is, ( ) is not a women-owned small business concern.

(4) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents as part of its offer that it ( ) is, ( ) is not a veteran-owned small business concern.

(5) (Complete only if the offeror represented itself as a veteran-owned small business concern in paragraph (b)(4) of this provision.) The offeror represents as part of its offer that it ( ) is, ( ) is not a service-disabled veteran-owned small business concern.

(6) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents, as part of its offer, that--

(i) It ( ) is, ( ) is not a HUBZone small business concern listed, on the date of this representation, on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration, and no material change in ownership and control, principal office, or HUBZone employee percentage has occurred since it was certified by the Small Business Administration in accordance with 13 CFR part 126; and

(ii) It ( ) is, ( ) is not a joint venture that complies with the requirements of 13 CFR part 126, and the representation in paragraph (b)(6)(i) of this provision is accurate for the HUBZone small business concern or concerns that are participating in the joint venture. (The offeror shall enter the name or names of the HUBZone small business concern or concerns that are participating in the joint venture: \_\_\_\_\_.) Each HUBZone small business concern participating in the joint venture shall submit a separate signed copy of the HUBZone representation.

(c) Definitions. As used in this provision--

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and



(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

"Small business concern," means a concern, including its affiliates, that is independently owned and operated, not dominant in the field of operation in which it is bidding on Government contracts, and qualified as a small business under the criteria in 13 CFR Part 121 and the size standard in paragraph (a) of this provision.

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

"Women-owned small business concern," means a small business concern --

(1) That is at least 51 percent owned by one or more women; in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Notice.

(1) If this solicitation is for supplies and has been set aside, in whole or in part, for small business concerns, then the clause in this solicitation providing notice of the set-aside contains restrictions on the source of the end items to be furnished.

(2) Under 15 U.S.C. 645(d), any person who misrepresents a firm's status as a small, HUBZone small, small disadvantaged, or women-owned small business concern in order to obtain a contract to be awarded under the preference programs established pursuant to section 8(a), 8(d), 9, or 15 of the Small Business Act or any other provision of Federal law that specifically references section 8(d) for a definition of program eligibility, shall--

(i) Be punished by imposition of fine, imprisonment, or both;

(ii) Be subject to administrative remedies, including suspension and debarment; and

(iii) Be ineligible for participation in programs conducted under the authority of the Act.

(End of provision)

#### 52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000)

(a) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

(b) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.

Definitions. As used in this contract--

HUBZone small business concern means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

Small business concern means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

Small disadvantaged business concern means a small business concern that represents, as part of its offer that--

(1) It has received certification as a small disadvantaged business concern consistent with 13 CFR part 124, subpart B;

(2) No material change in disadvantaged ownership and control has occurred since its certification;

(3) Where the concern is owned by one or more individuals, the net worth of each individual upon whom the certification is based does not exceed \$750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and

(4) It is identified, on the date of its representation, as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net).

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

Women-owned small business concern means a small business concern--

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a HUBZone small business concern, a small disadvantaged business concern, or a women-owned small business concern.

(End of clause)

(a) Segregated facilities, as used in this clause, means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees, that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.

(b) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Opportunity clause in this contract.

(c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Opportunity clause of this contract.

(End of clause)

#### 52.222-22 PREVIOUS CONTRACTS AND COMPLIANCE REPORTS (FEB 1999)

The offeror represents that --

(a) ( ) It has, ( ) has not participated in a previous contract or subcontract subject to the Equal Opportunity clause of this solicitation;

(b) ( ) It has, ( ) has not, filed all required compliance reports; and

(c) Representations indicating submission of required compliance reports, signed by proposed subcontractors, will be obtained before subcontract awards.

(End of provision)

#### 52.223-13 CERTIFICATION OF TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)

(a) Submission of this certification is a prerequisite for making or entering into this contract imposed by Executive Order 12969, August 8, 1995.

(b) By signing this offer, the offeror certifies that--

(1) As the owner or operator of facilities that will be used in the performance of this contract that are subject to the filing and reporting requirements described in section 313 of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42

U.S.C. 11023) and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106), the offeror will file and continue to file for such facilities for the life of the contract the Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of EPCRA and section 6607 of PPA; or

(2) None of its owned or operated facilities to be used in the performance of this contract is subject to the Form R filing and reporting requirements because each such facility is exempt for at least one of the following reasons: (Check each block that is applicable.)

☐ (i) The facility does not manufacture, process or otherwise use any toxic chemicals listed under section 313(c) of EPCRA, 42 U.S.C. 11023(c);

☐ (ii) The facility does not have 10 or more full-time employees as specified in section 313.(b)(1)(A) of EPCRA 42 U.S.C. 11023(b)(1)(A);

☐ (iii) The facility does not meet the reporting thresholds of toxic chemicals established under section 313(f) of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

☐ (iv) The facility does not fall within Standard Industrial Classification Code (SIC) major groups 20 through 39 or their corresponding North American Industry Classification System (NAICS) sectors 31 through 33; or

☐ (v) The facility is not located within any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, Guam, American Samoa, the United States Virgin Islands, the Northern Mariana Islands, or any other territory or possession over which the United States has jurisdiction.

(End of clause)

#### 252.204-7001 COMMERCIAL AND GOVERNMENT ENTITY (CAGE) CODE REPORTING (AUG 1999)

(a) The offeror is requested to enter its CAGE code on its offer in the block with its name and address. The CAGE code entered must be for that name and address. Enter "CAGE" before the number.

(b) If the offeror does not have a CAGE code, it may ask the Contracting Officer to request one from the Defense Logistics Information Service (DLIS). The Contracting Officer will--

(1) Ask the Contractor to complete section B of a DD Form 2051, Request for Assignment of a Commercial and Government Entity (CAGE) Code;

(2) Complete section A and forward the form to DLIS; and

(3) Notify the Contractor of its assigned CAGE code.

(c) Do not delay submission of the offer pending receipt of a CAGE code.

(End of provision)

252.204-7004 REQUIRED CENTRAL CONTRACTOR REGISTRATION (NOV 2001)

(a) Definitions.

As used in this clause--

(1) Central Contractor Registration (CCR) database means the primary DoD repository for contractor information required for the conduct of business with DoD.

(2) Data Universal Numbering System (DUNS) number means the 9-digit number assigned by Dun and Bradstreet Information Services to identify unique business entities.

(3) Data Universal Numbering System +4 (DUNS+4) number means the DUNS number assigned by Dun and Bradstreet plus a 4-digit suffix that may be assigned by a parent (controlling) business concern. This 4-digit suffix may be assigned at the discretion of the parent business concern for such purposes as identifying subunits or affiliates of the parent business concern.

(4) Registered in the CCR database means that all mandatory information, including the DUNS number or the DUNS+4 number, if applicable, and the corresponding Commercial and Government Entity (CAGE) code, is in the CCR database; the DUNS number and the CAGE code have been validated; and all edits have been successfully completed.

(b)(1) By submission of an offer, the offeror acknowledges the requirement that a prospective awardee must be registered in the CCR database prior to award, during performance, and through final payment of any contract resulting from this solicitation, except for awards to foreign vendors for work to be performed outside the United States.

(2) The offeror shall provide its DUNS or, if applicable, its DUNS+4 number with its offer, which will be used by the Contracting Officer to verify that the offeror is registered in the CCR database.

(3) Lack of registration in the CCR database will make an offeror ineligible for award.

(4) DoD has established a goal of registering an applicant in the CCR database within 48 hours after receipt of a complete and accurate application via the Internet. However, registration of an applicant submitting an application through a method other than the Internet may take up to 30 days. Therefore, offerors that are not registered should consider applying for registration immediately upon receipt of this solicitation.

(c) The Contractor is responsible for the accuracy and completeness of the data within the CCR, and for any liability resulting from the Government's reliance on inaccurate or incomplete data. To remain registered in the CCR database after the initial registration, the Contractor is required to confirm on an annual basis that its information in the CCR database is accurate and complete.

(d) Offerors and contractors may obtain information on registration and annual confirmation requirements by calling 1-888-227-2423, or via the Internet at <http://www.ccr.gov>.

(End of clause)

#### 252.209-7001 DISCLOSURE OF OWNERSHIP OR CONTROL BY THE GOVERNMENT OF A TERRORIST COUNTRY (MAR 1998)

(a) "Definitions."

As used in this provision --

(a) "Government of a terrorist country" includes the state and the government of a terrorist country, as well as any political subdivision, agency, or instrumentality thereof.

(2) "Terrorist country" means a country determined by the Secretary of State, under section 6(j)(1)(A) of the Export Administration Act of 1979 (50 U.S.C. App. 2405(j)(i)(A)), to be a country the government of which has repeatedly provided support for such acts of international terrorism. As of the date of this provision, terrorist countries include: Cuba, Iran, Iraq, Libya, North Korea, Sudan, and Syria.

(3) "Significant interest" means --

(i) Ownership of or beneficial interest in 5 percent or more of the firm's or subsidiary's securities. Beneficial interest includes holding 5 percent or more of any class of the firm's securities in "nominee shares," "street names," or some other method of holding securities that does not disclose the beneficial owner;

(ii) Holding a management position in the firm, such as a director or officer;

(iii) Ability to control or influence the election, appointment, or tenure of directors or officers in the firm;

(iv) Ownership of 10 percent or more of the assets of a firm such as equipment, buildings, real estate, or other tangible assets of the firm; or

(v) Holding 50 percent or more of the indebtedness of a firm.

(b) "Prohibition on award."

In accordance with 10 U.S.C. 2327, no contract may be awarded to a firm or a subsidiary of a firm if the government of a terrorist country has a significant interest in the firm or subsidiary or, in the case of a subsidiary, the firm that owns the subsidiary, unless a waiver is granted by the Secretary of Defense.

(c) "Disclosure."

If the government of a terrorist country has a significant interest in the Offeror or a subsidiary of the Offeror, the Offeror shall disclose such interest in an attachment to its offer. If the Offeror is a subsidiary, it shall also disclose any significant interest the government of a terrorist country has in any firm that owns or controls the subsidiary. The disclosure shall include --

(1) Identification of each government holding a significant interest; and

(2) A description of the significant interest held by each government.

(End of provision)

252.247-7022 REPRESENTATION OF EXTENT OF TRANSPORTATION BY SEA  
(AUG 1992)

(a) The Offeror shall indicate by checking the appropriate blank in paragraph (b) of this provision whether transportation of supplies by sea is anticipated under the resultant contract. The term supplies is defined in the Transportation of Supplies by Sea clause of this solicitation.

(b) Representation. The Offeror represents that it:

\_\_\_\_ (1) Does anticipate that supplies will be transported by sea in the performance of any contract or subcontract resulting from this solicitation.

\_\_\_\_ (2) Does not anticipate that supplies will be transported by sea in the performance of any contract or subcontract resulting from this solicitation.

(c) Any contract resulting from this solicitation will include the Transportation of Supplies by Sea clause. If the Offeror represents that it will not use ocean transportation, the resulting contract will also include the Defense FAR Supplement clause at 252.247-7024, Notification of Transportation of Supplies by Sea.

(End of provision)



**Section 00700**  
**Contract Clauses**

52.202-1	DEFINITIONS (DEC 2001).....	4
52.203-3	GRATUITIES (APR 1984) .....	6
52.203-5	COVENANT AGAINST CONTINGENT FEES (APR 1984).....	7
52.203-7	ANTI-KICKBACK PROCEDURES. (JUL 1995).....	7
52.203-8	CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997).....	9
52.203-10	PRICE OR FEE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997).....	9
52.203-12	LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (JUN 1997) .....	11
52.204-4	PRINTED OR COPIED DOUBLE-SIDED ON RECYCLED PAPER (AUG 2000) .....	16
52.214-26	Audit and Records--Sealed Bidding. (OCT 1997) .....	17
52.214-27	Price Reduction for Defective Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 1997).....	18
52.214-28	Subcontractor Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 1997) .....	20
52.219-8	UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000) .....	21
52.219-14	LIMITATIONS ON SUBCONTRACTING (DEC 1996).....	23
52.222-3	Convict Labor (Aug 1996) .....	23
52.222-4	Contract Work Hours and Safety Standards Act - Overtime Compensation. (SEP 2000) .....	24
52.222-6	DAVIS-BACON ACT (FEB 1995).....	25
52.222-7	WITHHOLDING OF FUNDS (FEB 1988) .....	27
52.222-8	PAYROLLS AND BASIC RECORDS (FEB 1988).....	27
52.222-9	APPRENTICES AND TRAINEES (FEB 1988).....	28
52.222-10	COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988).....	30
52.222-11	SUBCONTRACTS (LABOR STANDARDS (FEB 1988).....	30
52.222-12	CONTRACT TERMINATION--DEBARMENT (FEB 1988) .....	31
52.222-13	COMPLIANCE WITH DAVIS-BACON AND RELATED ACT REGULATIONS (FEB 1988).....	31
52.222-14	DISPUTES CONCERNING LABOR STANDARDS (FEB 1988).....	31
52.222-15	CERTIFICATION OF ELIGIBILITY (FEB 1988) .....	31
52.222-26	EQUAL OPPORTUNITY (APR 2002) .....	32
52.222-27	AFFIRMATIVE ACTION COMPLIANCE REQUIREMENTS FOR CONSTRUCTION (FEB 1999).....	33
52.222-35	AFFIRMATIVE ACTION FOR DISABLED VETERANS AND VETERANS OF THE VIETNAM ERA (APR 1998).....	38
52.222-36	AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998).....	41
52.222-37	EMPLOYMENT REPORTS ON DISABLED VETERANS AND VETERANS OF THE VIETNAM ERA (JAN 1999) .....	42
52.222-38	COMPLIANCE WITH VETERANS' EMPLOYMENT REPORTING REQUIREMENTS (DEC 2001).....	43

52.223-5	POLLUTION PREVENTION AND RIGHT-TO-KNOW INFORMATION (APR 1998)	43
52.223-6	DRUG-FREE WORKPLACE (MAY 2001)	44
52.223-14	TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)	46
52.225-13	RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUL 2000)	47
52.225-14	INCONSISTENCY BETWEEN ENGLISH VERSION AND TRANSLATION OF CONTRACT (FEB 2000)	47
52.227-1	AUTHORIZATION AND CONSENT (JUL 1995)	47
52.227-2	NOTICE AND ASSISTANCE REGARDING PATENT AND COPYRIGHT INFRINGEMENT (AUG 1996)	48
52.227-4	PATENT INDEMNITY--CONSTRUCTION CONTRACTS (APR 1984)	48
52.228-2	ADDITIONAL BOND SECURITY (OCT 1997)	49
52.228-11	PLEDGES OF ASSETS (FEB 1992)	49
52.229-3	FEDERAL, STATE, AND LOCAL TAXES (JAN 1991)	50
52.232-5	PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (MAY 1997)	51
52.232-17	INTEREST (JUNE 1996)	54
52.232-23	ASSIGNMENT OF CLAIMS (JAN 1986)	55
52.232-27	PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (FEB 2002)	55
52.233-1	Disputes. (JUL 2002)	63
52.233-3	PROTEST AFTER AWARD (AUG. 1996)	64
52.236-2	DIFFERING SITE CONDITIONS (APR 1984)	66
52.236-3	SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)	66
52.236-5	MATERIAL AND WORKMANSHIP (APR 1984)	67
52.236-6	SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)	68
52.236-7	PERMITS AND RESPONSIBILITIES (NOV 1991)	68
52.236-8	OTHER CONTRACTS (APR 1984)	68
52.236-9	PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984)	68
52.236-10	OPERATIONS AND STORAGE AREAS (APR 1984)	69
52.236-11	USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)	69
52.236-12	CLEANING UP (APR 1984)	70
52.236-13	ACCIDENT PREVENTION (NOV 1991)	70
52.236-15	SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)	71
52.236-17	LAYOUT OF WORK (APR 1984)	72
52.236-21	SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)	72
52.236-26	PRECONSTRUCTION CONFERENCE (FEB 1995)	73
52.242-13	BANKRUPTCY (JUL 1995)	74
52.242-14	SUSPENSION OF WORK (APR 1984)	74
52.243-3	CHANGES--TIME-AND-MATERIALS OR LABOR-HOURS (SEP 2000)	74
52.246-12	INSPECTION OF CONSTRUCTION (AUG 1996)	75
52.246-21	WARRANTY OF CONSTRUCTION (MAR 1994)	77
52.248-3	VALUE ENGINEERING--CONSTRUCTION (FEB 2000)	78
52.249-2	TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (SEP 1996)	81

52.249-10	DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984) .....	85
52.252-2	CLAUSES INCORPORATED BY REFERENCE (FEB 1998) .....	86
52.252-4	ALTERATIONS IN CONTRACT (APR 1984) .....	87
52.252-6	AUTHORIZED DEVIATIONS IN CLAUSES (APR 1984) .....	87
52.253-1	COMPUTER GENERATED FORMS (JAN 1991) .....	87
252.201-7000	CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991) .....	87
252.203-7001	PROHIBITION ON PERSONS CONVICTED OF FRAUD OR OTHER DEFENSE-CONTRACT-RELATED FELONIES (MAR 1999) .....	88
252.203-7002	DISPLAY OF DOD HOTLINE POSTER (DEC 1991) .....	89
252.204-7000	DISCLOSURE OF INFORMATION (DEC 1991) .....	89
252.204-7003	CONTROL OF GOVERNMENT PERSONNEL WORK PRODUCT (APR 1992) .....	90
252.205-7000	PROVISION OF INFORMATION TO COOPERATIVE AGREEMENT HOLDERS (DEC 1991) .....	90
252.209-7000	ACQUISITION FROM SUBCONTRACTORS SUBJECT TO ONSITE INSPECTION UNDER THE INTERMEDIATE-RANGE NUCLEAR FORCES (INF) TREATY (NOV 1995) .....	91
252.223-7004	DRUG-FREE WORK FORCE (SEP 1988) .....	91
252.225-7012	Preference for Certain Domestic Commodities (APR 2002) .....	93
252.225-7031	SECONDARY ARAB BOYCOTT OF ISRAEL (JUN 1992) .....	94
252.227-7000	Non-estoppel. (OCT 1966) .....	95
252.227-7022	GOVERNMENT RIGHTS (UNLIMITED) (MAR 1979) .....	95
252.227-7023	DRAWINGS AND OTHER DATA TO BECOME PROPERTY OF GOVERNMENT. (MAR 1979) .....	95
252.227-7033	RIGHTS IN SHOP DRAWINGS (APR 1966) .....	96
252.231-7000	SUPPLEMENTAL COST PRINCIPLES (DEC 1991) .....	96
252.236-7000	MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991) .....	96
252.236-7008	CONTRACT PRICES - BIDDING SCHEDULES. (DEC 1991) .....	97
252.242-7000	POSTAWARD CONFERENCE (DEC 1991) .....	97
252.243-7001	PRICING OF CONTRACT MODIFICATIONS (DEC 1991) .....	97
252.243-7002	REQUESTS FOR EQUITABLE ADJUSTMENT (MAR 1998) .....	97
252.247-7024	Notification of Transportation of Supplies by Sea (MAR 2000) .....	98

## CLAUSES INCORPORATED BY FULL TEXT

## 52.202-1 DEFINITIONS (DEC 2001)

(a) Agency head or head of the agency means the Secretary (Attorney General, Administrator, Governor, Chairperson, or other chief official, as appropriate) of the agency, unless otherwise indicated, including any deputy or assistant chief official of the executive agency.

(b) Commercial component means any component that is a commercial item.

(c) Commercial item means--

(1) Any item, other than real property, that is of a type customarily used by the general public or by non-governmental entities for purposes other than governmental purposes, and that--

(i) Has been sold, leased, or licensed to the general public; or

(ii) Has been offered for sale, lease, or license to the general public;

(2) Any item that evolved from an item described in paragraph (c)(1) of this clause through advances in technology or performance and that is not yet available in the commercial marketplace, but will be available in the commercial marketplace in time to satisfy the delivery requirements under a Government solicitation;

(3) Any item that would satisfy a criterion expressed in paragraphs (c)(1) or (c)(2) of this clause, but for--

(i) Modifications of a type customarily available in the commercial marketplace; or

(ii) Minor modifications of a type not customarily available in the commercial marketplace made to meet Federal Government requirements. "Minor" modifications means modifications that do not significantly alter the nongovernmental function or essential physical characteristics of an item or component, or change the purpose of a process. Factors to be considered in determining whether a modification is minor include the value and size of the modification and the comparative value and size of the final product. Dollar values and percentages may be used as guideposts, but are not conclusive evidence that a modification is minor;

(4) Any combination of items meeting the requirements of paragraphs (c)(1), (2), (3), or (5) of this clause that are of a type customarily combined and sold in combination to the general public;

(5) Installation services, maintenance services, repair services, training services, and other services if--

(i) Such services are procured for support of an item referred to in paragraph (c)(1), (2), (3), or (4) of this definition, regardless of whether such services are provided by the same source or at the same time as the item; and

(ii) The source of such services provides similar services contemporaneously to the general public under terms and conditions similar to those offered to the Federal Government;

(6) Services of a type offered and sold competitively in substantial quantities in the commercial marketplace based on established catalog or market prices for specific tasks performed under standard commercial terms and conditions. This does not include services that are sold based on hourly rates without an established catalog or market price for a specific service performed. For purposes of these services--

(i) Catalog price means a price included in a catalog, price list, schedule, or other form that is regularly maintained by the manufacturer or vendor, is either published or otherwise available for inspection by customers, and states prices at which sales are currently, or were last, made to a significant number of buyers constituting the general public; and

(ii) Market prices means current prices that are established in the course of ordinary trade between buyers and sellers free to bargain and that can be substantiated through competition or from sources independent of the offerors.

(7) Any item, combination of items, or service referred to in subparagraphs (c)(1) through (c)(6), notwithstanding the fact that the item, combination of items, or service is transferred between or among separate divisions, subsidiaries, or affiliates of a Contractor; or

(8) A nondevelopmental item, if the procuring agency determines the item was developed exclusively at private expense and sold in substantial quantities, on a competitive basis, to multiple State and local Governments.

(d) Component means any item supplied to the Government as part of an end item or of another component, except that for use in 52.225-9, and 52.225-11 see the definitions in 52.225-9(a) and 52.225-11(a).

(e) Contracting Officer means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.

(f) Nondevelopmental item means--

(1) Any previously developed item of supply used exclusively for governmental purposes by a Federal agency, a State or local government, or a foreign government with which the United States has a mutual defense cooperation agreement;

(2) Any item described in paragraph (f)(1) of this definition that requires only minor modification or modifications of a type customarily available in the commercial marketplace in order to meet the requirements of the procuring department or agency; or

(3) Any item of supply being produced that does not meet the requirements of paragraph (f)(1) or (f)(2) solely because the item is not yet in use.

(g) "Contracting Officer" means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.

(h) Except as otherwise provided in this contract, the term "subcontracts" includes, but is not limited to, purchase orders and changes and modifications to purchase orders under this contract.

(End of clause)

#### 52.203-3 GRATUITIES (APR 1984)

(a) The right of the Contractor to proceed may be terminated by written notice if, after notice and hearing, the agency head or a designee determines that the Contractor, its agent, or another representative--

(1) Offered or gave a gratuity (e.g., an entertainment or gift) to an officer, official, or employee of the Government; and

(2) Intended, by the gratuity, to obtain a contract or favorable treatment under a contract.

(b) The facts supporting this determination may be reviewed by any court having lawful jurisdiction.

(c) If this contract is terminated under paragraph (a) of this clause, the Government is entitled--

(1) To pursue the same remedies as in a breach of the contract; and

(2) In addition to any other damages provided by law, to exemplary damages of not less than 3 nor more than 10 times the cost incurred by the Contractor in giving gratuities to the person concerned, as determined by the agency head or a designee. (This subparagraph (c)(2) is applicable only if this contract uses money appropriated to the Department of Defense.)

(d) The rights and remedies of the Government provided in this clause shall not be exclusive and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

## 52.203-5 COVENANT AGAINST CONTINGENT FEES (APR 1984)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise recover, the full amount of the contingent fee.

(b) "Bona fide agency," as used in this clause, means an established commercial or selling agency, maintained by a contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

"Bona fide employee," as used in this clause, means a person, employed by a contractor and subject to the contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

"Contingent fee," as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

"Improper influence," as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

(End of clause)

## 52.203-7 ANTI-KICKBACK PROCEDURES. (JUL 1995)

(a) Definitions.

"Kickback," as used in this clause, means any money, fee, commission, credit, gift, gratuity, thing of value, or compensation of any kind which is provided, directly or indirectly, to any prime Contractor, prime Contractor employee, subcontractor, or subcontractor employee for the purpose of improperly obtaining or rewarding favorable treatment in connection with a prime contract or in connection with a subcontract relating to a prime contract.

"Person," as used in this clause, means a corporation, partnership, business association of any kind, trust, joint-stock company, or individual.

"Prime contract," as used in this clause, means a contract or contractual action entered into by the United States for the purpose of obtaining supplies, materials, equipment, or services of any kind.

"Prime Contractor," as used in this clause, means a person who has entered into a prime contract with the United States.

"Prime Contractor employee," as used in this clause, means any officer, partner, employee, or agent of a prime Contractor.

"Subcontract," as used in this clause, means a contract or contractual action entered into by a prime Contractor or subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind under a prime contract.

"Subcontractor," as used in this clause, (1) means any person, other than the prime Contractor, who offers to furnish or furnishes any supplies, materials, equipment, or services of any kind under a prime contract or a subcontract entered into in connection with such prime contract, and (2) includes any person who offers to furnish or furnishes general supplies to the prime Contractor or a higher tier subcontractor.

"Subcontractor employee," as used in this clause, means any officer, partner, employee, or agent of a subcontractor.

(b) The Anti-Kickback Act of 1986 (41 U.S.C. 51-58) (the Act), prohibits any person from -

(1) Providing or attempting to provide or offering to provide any kickback;

(2) Soliciting, accepting, or attempting to accept any kickback; or

(3) Including, directly or indirectly, the amount of any kickback in the contract price charged by a prime Contractor to the United States or in the contract price charged by a subcontractor to a prime Contractor or higher tier subcontractor.

(c)(1) The Contractor shall have in place and follow reasonable procedures designed to prevent and detect possible violations described in paragraph (b) of this clause in its own operations and direct business relationships.

(2) When the Contractor has reasonable grounds to believe that a violation described in paragraph (b) of this clause may have occurred, the Contractor shall promptly report in writing the possible violation. Such reports shall be made to the inspector general of the contracting agency, the head of the contracting agency if the agency does not have an inspector general, or the Department of Justice.

(3) The Contractor shall cooperate fully with any Federal agency investigating a possible violation described in paragraph (b) of this clause.

(4) The Contracting Officer may (i) offset the amount of the kickback against any monies owed by the United States under the prime contract and/or (ii) direct that the Prime Contractor withhold, from sums owed a subcontractor under the prime contract, the amount of any kickback. The Contracting Officer may order the monies withheld under subdivision (c)(4)(ii) of



this clause be paid over to the Government unless the Government has already offset those monies under subdivision (c)(4)(i) of this clause. In either case, the Prime Contractor shall notify the Contracting Officer when the monies are withheld.

(5) The Contractor agrees to incorporate the substance of this clause, including this subparagraph (c)(5) but excepting subparagraph (c)(1), in all subcontracts under this contract which exceed \$100,000

#### 52.203-8 CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) If the Government receives information that a contractor or a person has engaged in conduct constituting a violation of subsection (a), (b), (c), or (d) of Section 27 of the Office of Federal Procurement Policy Act (41 U.S.C. 423) (the Act), as amended by section 4304 of the 1996 National Defense Authorization Act for Fiscal Year 1996 (Pub. L. 104-106), the Government may--

(1) Cancel the solicitation, if the contract has not yet been awarded or issued; or

(2) Rescind the contract with respect to which--

(i) The Contractor or someone acting for the Contractor has been convicted for an offense where the conduct constitutes a violation of subsection 27(a) or (b) of the Act for the purpose of either--

(A) Exchanging the information covered by such subsections for anything of value; or

(B) Obtaining or giving anyone a competitive advantage in the award of a Federal agency procurement contract; or

(ii) The head of the contracting activity has determined, based upon a preponderance of the evidence, that the Contractor or someone acting for the Contractor has engaged in conduct constituting an offense punishable under subsections 27(e)(1) of the Act.

(b) If the Government rescinds the contract under paragraph (a) of this clause, the Government is entitled to recover, in addition to any penalty prescribed by law, the amount expended under the contract.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law, regulation, or under this contract.

(End of clause)

#### 52.203-10 PRICE OR FEE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) The Government, at its election, may reduce the price of a fixed-price type contract and the

total cost and fee under a cost-type contract by the amount of profit or fee determined as set forth in paragraph (b) of this clause if the head of the contracting activity or designee determines that there was a violation of subsection 27 (a), (b), or (c) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in section 3.104 of the Federal Acquisition Regulation.

(b) The price or fee reduction referred to in paragraph (a) of this clause shall be--

(1) For cost-plus-fixed-fee contracts, the amount of the fee specified in the contract at the time of award;

(2) For cost-plus-incentive-fee contracts, the target fee specified in the contract at the time of award, notwithstanding any minimum fee or "fee floor" specified in the contract;

(3) For cost-plus-award-fee contracts--

(i) The base fee established in the contract at the time of contract award;

(ii) If no base fee is specified in the contract, 30 percent of the amount of each award fee otherwise payable to the Contractor for each award fee evaluation period or at each award fee determination point.

(4) For fixed-price-incentive contracts, the Government may--

(i) Reduce the contract target price and contract target profit both by an amount equal to the initial target profit specified in the contract at the time of contract award; or

(ii) If an immediate adjustment to the contract target price and contract target profit would have a significant adverse impact on the incentive price revision relationship under the contract, or adversely affect the contract financing provisions, the Contracting Officer may defer such adjustment until establishment of the total final price of the contract. The total final price established in accordance with the incentive price revision provisions of the contract shall be reduced by an amount equal to the initial target profit specified in the contract at the time of contract award and such reduced price shall be the total final contract price.

(5) For firm-fixed-price contracts, by 10 percent of the initial contract price or a profit amount determined by the Contracting Officer from records or documents in existence prior to the date of the contract award.

(c) The Government may, at its election, reduce a prime contractor's price or fee in accordance with the procedures of paragraph (b) of this clause for violations of the Act by its subcontractors by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was first definitively priced.

(d) In addition to the remedies in paragraphs (a) and (c) of this clause, the Government may terminate this contract for default. The rights and remedies of the Government specified herein

are not exclusive, and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

## 52.203-12 LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (JUN 1997)

### (a) Definitions.

"Agency," as used in this clause, means executive agency as defined in 2.101.

"Covered Federal action," as used in this clause, means any of the following Federal actions:

- (1) The awarding of any Federal contract.
- (2) The making of any Federal grant.
- (3) The making of any Federal loan.
- (4) The entering into of any cooperative agreement.
- (5) The extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

"Indian tribe" and "tribal organization," as used in this clause, have the meaning provided in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450B) and include Alaskan Natives.

"Influencing or attempting to influence," as used in this clause, means making, with the intent to influence, any communication to or appearance before an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any covered Federal action.

"Local government," as used in this clause, means a unit of government in a State and, if chartered, established, or otherwise recognized by a State for the performance of a governmental duty, including a local public authority, a special district, an intrastate district, a council of governments, a sponsor group representative organization, and any other instrumentality of a local government.

"Officer or employee of an agency," as used in this clause, includes the following individuals who are employed by an agency:

- (1) An individual who is appointed to a position in the Government under Title 5, United States Code, including a position under a temporary appointment.

(2) A member of the uniformed services, as defined in subsection 101(3), Title 37, United States Code.

(3) A special Government employee, as defined in section 202, Title 18, United States Code.

(4) An individual who is a member of a Federal advisory committee, as defined by the Federal Advisory Committee Act, Title 5, United States Code, appendix 2.

"Person," as used in this clause, means an individual, corporation, company, association, authority, firm, partnership, society, State, and local government, regardless of whether such entity is operated for profit, or not for profit. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Reasonable compensation," as used in this clause, means, with respect to a regularly employed officer or employee of any person, compensation that is consistent with the normal compensation for such officer or employee for work that is not furnished to, not funded by, or not furnished in cooperation with the Federal Government.

"Reasonable payment," as used in this clause, means, with respect to professional and other technical services, a payment in an amount that is consistent with the amount normally paid for such services in the private sector.

"Recipient," as used in this clause, includes the Contractor and all subcontractors. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Regularly employed," as used in this clause, means, with respect to an officer or employee of a person requesting or receiving a Federal contract, an officer or employee who is employed by such person for at least 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person for receipt of such contract. An officer or employee who is employed by such person for less than 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person shall be considered to be regularly employed as soon as he or she is employed by such person for 130 working days.

"State," as used in this clause, means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, a territory or possession of the United States, an agency or instrumentality of a State, and multi-State, regional, or interstate entity having governmental duties and powers.

(b) Prohibitions.

(1) Section 1352 of Title 31, United States Code, among other things, prohibits a recipient of a Federal contract, grant, loan, or cooperative agreement from using appropriated funds to pay any person for influencing or attempting to influence an officer or employee of any agency, a

Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any of the following covered Federal actions: the awarding of any Federal contract; the making of any Federal grant; the making of any Federal loan; the entering into of any cooperative agreement; or the modification of any Federal contract, grant, loan, or cooperative agreement.

(2) The Act also requires Contractors to furnish a disclosure if any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with a Federal contract, grant, loan, or cooperative agreement.

(3) The prohibitions of the Act do not apply under the following conditions:

(i) Agency and legislative liaison by own employees.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of a payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action if the payment is for agency and legislative liaison activities not directly related to a covered Federal action.

(B) For purposes of subdivision (b)(3)(i)(A) of this clause, providing any information specifically requested by an agency or Congress is permitted at any time.

(C) The following agency and legislative liaison activities are permitted at any time where they are not related to a specific solicitation for any covered Federal action:

(1) Discussing with an agency the qualities and characteristics (including individual demonstrations) of the person's products or services, conditions or terms of sale, and service capabilities.

(2) Technical discussions and other activities regarding the application or adaptation of the person's products or services for an agency's use.

(D) The following agency and legislative liaison activities are permitted where they are prior to formal solicitation of any covered Federal action--

(1) Providing any information not specifically requested but necessary for an agency to make an informed decision about initiation of a covered Federal action;

(2) Technical discussions regarding the preparation of an unsolicited proposal prior to its official submission; and

(3) Capability presentations by persons seeking awards from an agency pursuant to the provisions of the Small Business Act, as amended by Pub. L. 95-507, and subsequent amendments.

(E) Only those services expressly authorized by subdivision (b)(3)(i)(A) of this clause are permitted under this clause.

(ii) Professional and technical services.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of--

(1) A payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action, if payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action.

(2) Any reasonable payment to a person, other than an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action if the payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action. Persons other than officers or employees of a person requesting or receiving a covered Federal action include consultants and trade associations.

(B) For purposes of subdivision (b)(3)(ii)(A) of this clause, "professional and technical services" shall be limited to advice and analysis directly applying any professional or technical discipline. For example, drafting of a legal document accompanying a bid or proposal by a lawyer is allowable. Similarly, technical advice provided by an engineer on the performance or operational capability of a piece of equipment rendered directly in the negotiation of a contract is allowable. However, communications with the intent to influence made by a professional (such as a licensed lawyer) or a technical person (such as a licensed accountant) are not allowable under this section unless they provide advice and analysis directly applying their professional or technical expertise and unless the advice or analysis is rendered directly and solely in the preparation, submission or negotiation of a covered Federal action. Thus, for example, communications with the intent to influence made by a lawyer that do not provide legal advice or analysis directly and solely related to the legal aspects of his or her client's proposal, but generally advocate one proposal over another are not allowable under this section because the lawyer is not providing professional legal services. Similarly, communications with the intent to influence made by an engineer providing an engineering analysis prior to the preparation or submission of a bid or proposal are not allowable under this section since the engineer is providing technical services but not directly in the preparation, submission or negotiation of a covered Federal action.

(C) Requirements imposed by or pursuant to law as a condition for receiving a covered Federal award include those required by law or regulation and any other requirements in the actual award documents.

(D) Only those services expressly authorized by subdivisions (b)(3)(ii)(A)(1) and (2) of this clause are permitted under this clause.

(E) The reporting requirements of FAR 3.803(a) shall not apply with respect to payments of reasonable compensation made to regularly employed officers or employees of a person.

(c) Disclosure.

(1) The Contractor who requests or receives from an agency a Federal contract shall file with that agency a disclosure form, OMB standard form LLL, Disclosure of Lobbying Activities, if such person has made or has agreed to make any payment using nonappropriated funds (to include profits from any covered Federal action), which would be prohibited under subparagraph (b)(1) of this clause, if paid for with appropriated funds.

(2) The Contractor shall file a disclosure form at the end of each calendar quarter in which there occurs any event that materially affects the accuracy of the information contained in any disclosure form previously filed by such person under subparagraph (c)(1) of this clause. An event that materially affects the accuracy of the information reported includes--

(i) A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or

(ii) A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or

(iii) A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

(3) The Contractor shall require the submittal of a certification, and if required, a disclosure form by any person who requests or receives any subcontract exceeding \$100,000 under the Federal contract.

(4) All subcontractor disclosure forms (but not certifications) shall be forwarded from tier to tier until received by the prime Contractor. The prime Contractor shall submit all disclosures to the Contracting Officer at the end of the calendar quarter in which the disclosure form is submitted by the subcontractor. Each subcontractor certification shall be retained in the subcontract file of the awarding Contractor.

(d) Agreement. The Contractor agrees not to make any payment prohibited by this clause.

(e) Penalties.

(1) Any person who makes an expenditure prohibited under paragraph (a) of this clause or who fails to file or amend the disclosure form to be filed or amended by paragraph (b) of this clause shall be subject to civil penalties as provided for by 31 U.S.C. 1352. An imposition of a civil penalty does not prevent the Government from seeking any other remedy that may be applicable.

(2) Contractors may rely without liability on the representation made by their subcontractors in the certification and disclosure form.

(f) Cost allowability. Nothing in this clause makes allowable or reasonable any costs which would otherwise be unallowable or unreasonable. Conversely, costs made specifically unallowable by the requirements in this clause will not be made allowable under any other provision.

(End of clause)

#### 52.204-4 PRINTED OR COPIED DOUBLE-SIDED ON RECYCLED PAPER (AUG 2000)

(a) Definitions. As used in this clause--

“Postconsumer material” means a material or finished product that has served its intended use and has been discarded for disposal or recovery, having completed its life as a consumer item. Postconsumer material is a part of the broader category of “recovered material.” For paper and paper products, postconsumer material means “postconsumer fiber” defined by the U.S. Environmental Protection Agency (EPA) as--

(1) Paper, paperboard, and fibrous materials from retail stores, office buildings, homes, and so forth, after they have passed through their end-usage as a consumer item, including: used corrugated boxes; old newspapers; old magazines; mixed waste paper; tabulating cards; and used cordage; or

(2) All paper, paperboard, and fibrous materials that enter and are collected from municipal solid waste; but not

(3) Fiber derived from printers' over-runs, converters' scrap, and over-issue publications.

“Printed or copied double-sided” means printing or reproducing a document so that information is on both sides of a sheet of paper.

“Recovered material,” for paper and paper products, is defined by EPA in its Comprehensive Procurement Guideline as “recovered fiber” and means the following materials:

(1) Postconsumer fiber; and

(2) Manufacturing wastes such as--



(i) Dry paper and paperboard waste generated after completion of the papermaking process (that is, those manufacturing operations up to and including the cutting and trimming of the paper machine reel into smaller rolls or rough sheets) including: envelope cuttings, bindery trimmings, and other paper and paperboard waste resulting from printing, cutting, forming, and other converting operations; bag, box, and carton manufacturing wastes; and butt rolls, mill wrappers, and rejected unused stock; and

(ii) Repulped finished paper and paperboard from obsolete inventories of paper and paperboard manufacturers, merchants, wholesalers, dealers, printers, converters, or others.

(b) In accordance with Section 101 of Executive Order 13101 of September 14, 1998, Greening the Government through Waste Prevention, Recycling, and Federal Acquisition, the Contractor is encouraged to submit paper documents, such as offers, letters, or reports, that are printed or copied double-sided on recycled paper that meet minimum content standards specified in Section 505 of Executive Order 13101, when not using electronic commerce methods to submit information or data to the Government.

(c) If the Contractor cannot purchase high-speed copier paper, offset paper, forms bond, computer printout paper, carbonless paper, file folders, white wove envelopes, writing and office paper, book paper, cotton fiber paper, and cover stock meeting the 30 percent postconsumer material standard for use in submitting paper documents to the Government, it should use paper containing no less than 20 percent postconsumer material. This lesser standard should be used only when paper meeting the 30 percent postconsumer material standard is not obtainable at a reasonable price or does not meet reasonable performance standards.

(End of clause)

#### 52.214-26 Audit and Records--Sealed Bidding. (OCT 1997)

(a) As used in this clause, records includes books, documents, accounting procedures and practices, and other data, regardless of type and regardless of whether such items are in written form, in the form of computer data, or in any other form.

(b) Cost or pricing data. If the Contractor has been required to submit cost or pricing data in connection with the pricing of any modification to this contract, the Contracting Officer, or an authorized representative of the Contracting Officer, in order to evaluate the accuracy, completeness, and currency of the cost or pricing data, shall have the right to examine and audit all of the Contractor's records, including computations and projections, related to--

(1) The proposal for the modification;

(2) The discussions conducted on the proposal(s), including those related to negotiating;

(3) Pricing of the modification; or

(4) Performance of the modification.

(c) Comptroller General. In the case of pricing any modification, the Comptroller General of the United States, or an authorized representative, shall have the same rights as specified in paragraph (b) of this clause.

(d) Availability. The Contractor shall make available at its office at all reasonable times the materials described in reproduction, until 3 years after final payment under this contract, or for any other period specified in Subpart 4.7 of the Federal Acquisition Regulation (FAR). FAR Subpart 4.7, Contractor Records Retention, in effect on the date of this contract, is incorporated by reference in its entirety and made a part of this contract.

(1) If this contract is completely or partially terminated, the records relating to the work terminated shall be made available for 3 years after any resulting final termination settlement.

(2) Records pertaining to appeals under the Disputes clause or to litigation or the settlement of claims arising under or relating to the performance of this contract shall be made available until disposition of such appeals, litigation, or claims.

(e) The Contractor shall insert a clause containing all the provisions of this clause, including this paragraph (e), in all subcontracts expected to exceed the threshold in FAR 15.403-4(a)(1) for submission of cost or pricing data.

(End of clause)

52.214-27 Price Reduction for Defective Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 1997)

(a) This clause shall become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for the submission of cost or pricing data at FAR 15.403-4(a)(1), except that this clause does not apply to a modification if an exception under FAR 15.403-1(b) applies.

(1) Based on adequate price competition;

(2) Based on established catalog or market prices of commercial items sold in substantial quantities to the general public; or

(3) Set by law or regulation.

(b) If any price, including profit, negotiated in connection with any modification under this clause, was increased by any significant amount because

(1) the Contractor or a subcontractor furnished cost or pricing data that were not complete, accurate, and current as certified in its Certificate of Current Cost or Pricing Data;

(2) a subcontractor or prospective subcontractor furnished the Contractor cost or pricing data that were not complete, accurate, and current as certified in the Contractor's Certificate of Current Cost or Pricing Data; or

(3) any of these parties furnished data of any description that were not accurate, the price shall be reduced accordingly and the contract shall be modified to reflect the reduction. This right to a price reduction is limited to that resulting from defects in data relating to modifications for which this clause becomes operative under paragraph (a) above.

(c) Any reduction in the contract price under paragraph (b) above due to defective data from a prospective subcontractor that was not subsequently awarded the subcontract shall be limited to the amount, plus applicable overhead and profit markup, by which:

(1) the actual subcontract; or

(2) the actual cost to the Contractor, if there was no subcontract, was less than the prospective subcontract cost estimate submitted by the Contractor; provided, that the actual subcontract price was not itself affected by defective cost or pricing data.

(d) If the Contracting Officer determines under paragraph (b) of this clause that a price or cost reduction should be made:

(1) the Contractor agrees not to raise the following matters as a defense:

(i) The Contractor or subcontractor was a sole source supplier or otherwise was in a superior bargaining position and thus the price of the contract would not have been modified even if accurate, complete, and current cost or pricing data had been submitted;

(ii) The Contracting Officer should have known that the cost or pricing data in issue were defective even though the Contractor or subcontractor took no affirmative action to bring the character of the data to the attention of the Contracting Officer;

(iii) The contract was based on an agreement about the total cost of the contract and there was no agreement about the cost of each item procured under the contract; or

(iv) The Contractor or subcontractor did not submit a Certificate of Current Cost or Pricing Data.

(2) Except as prohibited by subdivision (d)(2)(ii) of this clause:

(i) an offset in an amount determined appropriate by the Contracting Officer based upon the facts shall be allowed against the amount of a contract price reduction if:

(A) The Contractor certifies to the Contracting Officer that, to the best of the Contractor's knowledge and belief, the Contractor is entitled to the offset in the amount requested; and

(B) The Contractor proves that the cost or pricing data were available before the date of agreement on the price of the contract (or price of the modification) and that the data were not submitted before such date.

(ii) An offset shall not be allowed if:

(A) The understated data was known by the Contractor to be understated when the Certificate of Current Cost or Pricing Data was signed; or (B) The Government proves that the facts demonstrate that the contract price would not have increased in the amount to be offset even if the available data had been submitted before the date of agreement on price.

(e) If any reduction in the contract price under this clause reduces the price of items for which payment was made prior to the date of the modification reflecting the price reduction, the Contractor shall be liable to and shall pay the United States at the time such overpayment is repaid:

(1) Simple interest on the amount of such overpayment to be computed from the date(s) of overpayment to the Contractor to the date the Government is repaid by the Contractor at the applicable underpayment rate effective for each quarter prescribed by the Secretary of the Treasury under 26 U.S.C. 6621(a)(2); and

(2) A penalty equal to the amount of the overpayment, if the Contractor or subcontractor knowingly submitted cost or pricing data which were incomplete, inaccurate, or noncurrent.

(End of clause)

#### 52.214-28 Subcontractor Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 1997)

(a) The requirements of paragraphs (b) and (c) of this clause shall:

(1) become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of cost or pricing data at (FAR) 48 CFR 15.403-4(a)(1); and

(2) be limited to such modifications.

(b) Before awarding any subcontract expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1), on the date of agreement on price or the date of award, whichever is later; or before pricing any subcontract modifications involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1), the Contractor shall require the subcontractor to submit cost or pricing data (actually or by specific identification in writing), unless an exception under FAR 15.403-1(b) applies.

(1) Based on adequate price competition;

(2) Based on established catalog or market prices of commercial items sold in substantial quantities to the general public; or

(3) Set by law or regulation.

(c) The Contractor shall require the subcontractor to certify in substantially the form prescribed in subsection 15.406-2 of the Federal Acquisition Regulation that, to the best of its knowledge and belief, the data submitted under paragraph (b) above were accurate, complete, and current as of the date of agreement on the negotiated price of the subcontract or subcontract modification.

(d) The Contractor shall insert the substance of this clause, including this paragraph (d), in each subcontract that, when entered into, exceeds the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1).

(End of clause)

#### 52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000)

(a) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

(b) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.

Definitions. As used in this contract--

HUBZone small business concern means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

Small business concern means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

Small disadvantaged business concern means a small business concern that represents, as part of its offer that--

(1) It has received certification as a small disadvantaged business concern consistent with 13 CFR part 124, subpart B;

(2) No material change in disadvantaged ownership and control has occurred since its certification;

(3) Where the concern is owned by one or more individuals, the net worth of each individual upon whom the certification is based does not exceed \$750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and

(4) It is identified, on the date of its representation, as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net).

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

Women-owned small business concern means a small business concern--

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a HUBZone small business concern, a small disadvantaged business concern, or a women-owned small business concern.

(End of clause)

#### 52.219-14 LIMITATIONS ON SUBCONTRACTING (DEC 1996)

(a) This clause does not apply to the unrestricted portion of a partial set-aside.

(b) By submission of an offer and execution of a contract, the Offeror/Contractor agrees that in performance of the contract in the case of a contract for--

(1) Services (except construction). At least 50 percent of the cost of contract performance incurred for personnel shall be expended for employees of the concern.

(2) Supplies (other than procurement from a nonmanufacturer of such supplies). The concern shall perform work for at least 50 percent of the cost of manufacturing the supplies, not including the cost of materials.

(3) General construction. The concern will perform at least 15 percent of the cost of the contract, not including the cost of materials, with its own employees.

(4) Construction by special trade contractors. The concern will perform at least 25 percent of the cost of the contract, not including the cost of materials, with its own employees.

#### 52.222-3 Convict Labor (Aug 1996)

The Contractor agrees not to employ in the performance of this contract any person undergoing a sentence of imprisonment which has been imposed by any court of a State, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, or the Trust Territory of the Pacific Islands. This limitation, however, shall not prohibit the employment by the Contractor in the performance of this contract of persons on parole or probation to work at paid employment during the term of their sentence or persons who have been pardoned or who have served their terms. Nor shall it prohibit the employment by the Contractor in the performance of this contract of persons confined for violation of the laws of any of the States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, or the Trust Territory of the Pacific Islands who are authorized to work at paid employment in the community under the laws of such jurisdiction, if--

(a)(1) The worker is paid or is in an approved work training program on a voluntary basis;

(2) Representatives of local union central bodies or similar labor union organizations have been consulted;

(3) Such paid employment will not result in the displacement of employed workers, or be applied in skills, crafts, or trades in which there is a surplus of available gainful labor in the locality, or impair existing contracts for services; and

(4) The rates of pay and other conditions of employment will not be less than those paid or provided for work of a similar nature in the locality in which the work is being performed; and

(b) The Attorney General of the United States has certified that the work-release laws or regulations of the jurisdiction involved are in conformity with the requirements of Executive Order 11755, as amended by Executive Orders 12608 and 12943.

(End of clause)

52.222-4 Contract Work Hours and Safety Standards Act - Overtime Compensation. (SEP 2000)

(a) Overtime requirements. No Contractor or subcontractor employing laborers or mechanics (see Federal Acquisition Regulation 22.300) shall require or permit them to work over 40 hours in any workweek unless they are paid at least 1 and 1/2 times the basic rate of pay for each hour worked over 40 hours.

(b) Violation; liability for unpaid wages; liquidated damages. The responsible Contractor and subcontractor are liable for unpaid wages if they violate the terms in paragraph (a) of this clause. In addition, the Contractor and subcontractor are liable for liquidated damages payable to the Government. The Contracting Officer will assess liquidated damages at the rate of \$10 per affected employee for each calendar day on which the employer required or permitted the employee to work in excess of the standard workweek of 40 hours without paying overtime wages required by the Contract Work Hours and Safety Standards Act.

(c) Withholding for unpaid wages and liquidated damages. The Contracting Officer will withhold from payments due under the contract sufficient funds required to satisfy any Contractor or subcontractor liabilities for unpaid wages and liquidated damages. If amounts withheld under the contract are insufficient to satisfy Contractor or subcontractor liabilities, the Contracting Officer will withhold payments from other Federal or Federally assisted contracts held by the same Contractor that are subject to the Contract Work Hours and Safety Standards Act.

(d) Payrolls and basic records.

(1) The Contractor and its subcontractors shall maintain payrolls and basic payroll records for all laborers and mechanics working on the contract during the contract and shall make them available to the Government until 3 years after contract completion. The records shall contain the name and address of each employee, social security number, labor classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid.



The records need not duplicate those required for construction work by Department of Labor regulations at 29 CFR 5.5(a)(3) implementing the Davis-Bacon Act.

(2) The Contractor and its subcontractors shall allow authorized representatives of the Contracting Officer or the Department of Labor to inspect, copy, or transcribe records maintained under paragraph (d)(1) of this clause. The Contractor or subcontractor also shall allow authorized representatives of the Contracting Officer or Department of Labor to interview employees in the workplace during working hours.

(e) Subcontracts. The Contractor shall insert the provisions set forth in paragraphs (a) through (d) of this clause in subcontracts exceeding \$100,000 and require subcontractors to include these provisions in any lower tier subcontracts. The Contractor shall be responsible for compliance by any subcontractor or lower-tier subcontractor with the provisions set forth in paragraphs (a) through (d) of this clause.

(End of clause)

#### 52.222-6 DAVIS-BACON ACT (FEB 1995)

(a) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics. Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (d) of this clause; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such period. Such laborers and mechanics shall be paid not less than the appropriate wage rate and fringe benefits in the wage determination for the classification of work actually performed, without regard to skill, except as provided in the clause entitled Apprentices and Trainees. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein; provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph (b) of this clause) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

(b)(1) The Contracting Officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be

classified in conformance with the wage determination. The Contracting Officer shall approve an additional classification and wage rate and fringe benefits therefor only when all the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination.

(ii) The classification is utilized in the area by the construction industry.

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the Contracting Officer agree on the classification and wage rate (including the amount designated for fringe benefits, where appropriate), a report of the action taken shall be sent by the Contracting Officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator or an authorized representative will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(3) In the event the Contractor, the laborers or mechanics to be employed in the classification, or their representatives, and the Contracting Officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the Contracting Officer shall refer the questions, including the views of all interested parties and the recommendation of the Contracting Officer, to the Administrator of the Wage and Hour Division for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits, where appropriate) determined pursuant to subparagraphs (b)(2) and (b)(3) of this clause shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

(c) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

(c) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program; provided, That the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the

Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

(End of clause)

#### 52.222-7 WITHHOLDING OF FUNDS (FEB 1988)

The Contracting Officer shall, upon his or her own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same Prime Contractor, or any other Federally assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same Prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

(End of clause)

#### 52.222-8 PAYROLLS AND BASIC RECORDS (FEB 1988)

(a) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of 3 years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made, and actual wages paid. Whenever the Secretary of Labor has found, under paragraph (d) of the clause entitled Davis-Bacon Act, that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

(b)(1) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Contracting Officer. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph (a) of

this clause. This information may be submitted in any form desired. Optional Form WH-347 (Federal Stock Number 029-005-00014-1) is available for this purpose and may be purchased from the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402. The Prime Contractor is responsible for the submission of copies of payrolls by all subcontractors.

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify--

(i) That the payroll for the payroll period contains the information required to be maintained under paragraph (a) of this clause and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR Part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by subparagraph (b)(2) of this clause.

(4) The falsification of any of the certifications in this clause may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 3729 of Title 31 of the United States Code.

(c) The Contractor or subcontractor shall make the records required under paragraph (a) of this clause available for inspection, copying, or transcription by the Contracting Officer or authorized representatives of the Contracting Officer or the Department of Labor. The Contractor or subcontractor shall permit the Contracting Officer or representatives of the Contracting Officer or the Department of Labor to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit required records or to make them available, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

(End of clause)

52.222-9 APPRENTICES AND TRAINEES (FEB 1988)

(a) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State Apprenticeship Agency recognized by the Bureau, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in this paragraph, shall be paid not less than the applicable wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Bureau of Apprenticeship and Training, or a State Apprenticeship Agency recognized by the Bureau, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(b) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed in the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate in the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and

participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate in the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate in the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the Contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(c) Equal employment opportunity. The utilization of apprentices, trainees, and journeymen under this clause shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.

(End of clause)

#### 52.222-10 COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988)

The Contractor shall comply with the requirements of 29 CFR Part 3, which are hereby incorporated by reference in this contract.

(End of clause)

#### 52.222-11 SUBCONTRACTS (LABOR STANDARDS (FEB 1988)

(a) The Contractor or subcontractor shall insert in any subcontracts the clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act-Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Withholding of Funds, Subcontracts (Labor Standards), Contract Termination-Debarment, Disputes Concerning Labor Standards, Compliance with Davis-Bacon and Related Act Regulations, and Certification of Eligibility, and such other clauses as the Contracting Officer may, by appropriate instructions, require, and also a clause requiring subcontractors to include these clauses in any lower tier subcontracts. The Prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with all the contract clauses cited in this paragraph.

(b)(1) Within 14 days after award of the contract, the Contractor shall deliver to the Contracting Officer a completed Statement and Acknowledgment Form (SF 1413) for each subcontract, including the subcontractor's signed and dated acknowledgment that the clauses set forth in paragraph (a) of this clause have been included in the subcontract.

(2) Within 14 days after the award of any subsequently awarded subcontract the Contractor shall deliver to the Contracting Officer an updated completed SF 1413 for such additional subcontract.

(End of clause)

**52.222-12 CONTRACT TERMINATION--DEBARMENT (FEB 1988)**

A breach of the contract clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act--Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Subcontracts (Labor Standards), Compliance with Davis-Bacon and Related Act Regulations, or Certification of Eligibility may be grounds for termination of the contract, and for debarment as a Contractor and subcontractor as provided in 29 CFR 5.12.

(End of clause)

**52.222-13 COMPLIANCE WITH DAVIS-BACON AND RELATED ACT REGULATIONS (FEB 1988)**

All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are hereby incorporated by reference in this contract.

(End of clause)

**52.222-14 DISPUTES CONCERNING LABOR STANDARDS (FEB 1988)**

The United States Department of Labor has set forth in 29 CFR Parts 5, 6, and 7 procedures for resolving disputes concerning labor standards requirements. Such disputes shall be resolved in accordance with those procedures and not the Disputes clause of this contract. Disputes within the meaning of this clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

(End of clause)

**52.222-15 CERTIFICATION OF ELIGIBILITY (FEB 1988)**

(a) By entering into this contract, the Contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

(b) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

(c) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

(End of clause)

## 52.222-26 EQUAL OPPORTUNITY (APR 2002)

(a) Definition. United States, as used in this clause, means the 50 States, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, the U.S. Virgin Islands, and Wake Island.

(b) If, during any 12-month period (including the 12 months preceding the award of this contract), the Contractor has been or is awarded nonexempt Federal contracts and/or subcontracts that have an aggregate value in excess of \$10,000, the Contractor shall comply with paragraphs (b)(1) through (b)(11) of this clause, except for work performed outside the United States by employees who were not recruited within the United States. Upon request, the Contractor shall provide information necessary to determine the applicability of this clause.

(1) The Contractor shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. However, it shall not be a violation of this clause for the Contractor to extend a publicly announced preference in employment to Indians living on or near an Indian reservation, in connection with employment opportunities on or near an Indian reservation, as permitted by 41 CFR 60-1.5.

(2) The Contractor shall take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, or national origin. This shall include, but not be limited to, (i) employment, (ii) upgrading, (iii) demotion, (iv) transfer, (v) recruitment or recruitment advertising, (vi) layoff or termination, (vii) rates of pay or other forms of compensation, and (viii) selection for training, including apprenticeship.

(3) The Contractor shall post in conspicuous places available to employees and applicants for employment the notices to be provided by the Contracting Officer that explain this clause.

(4) The Contractor shall, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, or national origin.

(5) The Contractor shall send, to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, the notice to be provided by the Contracting Officer advising the labor union or workers' representative of the Contractor's commitments under this clause, and post copies of the notice in conspicuous places available to employees and applicants for employment.

(6) The Contractor shall comply with Executive Order 11246, as amended, and the rules, regulations, and orders of the Secretary of Labor.

(7) The Contractor shall furnish to the contracting agency all information required by Executive Order 11246, as amended, and by the rules, regulations, and orders of the Secretary of Labor. The Contractor shall also file Standard Form 100 (EEO-1), or any successor form, as prescribed in 41 CFR part 60-1. Unless the Contractor has filed within the 12 months preceding the date of



contract award, the Contractor shall, within 30 days after contract award, apply to either the regional Office of Federal Contract Compliance Programs (OFCCP) or the local office of the Equal Employment Opportunity Commission for the necessary forms.

(8) The Contractor shall permit access to its premises, during normal business hours, by the contracting agency or the OFCCP for the purpose of conducting on-site compliance evaluations and complaint investigations. The Contractor shall permit the Government to inspect and copy any books, accounts, records (including computerized records), and other material that may be relevant to the matter under investigation and pertinent to compliance with Executive Order 11246, as amended, and rules and regulations that implement the Executive Order.

(9) If the OFCCP determines that the Contractor is not in compliance with this clause or any rule, regulation, or order of the Secretary of Labor, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts, under the procedures authorized in Executive Order 11246, as amended. In addition, sanctions may be imposed and remedies invoked against the Contractor as provided in Executive Order 11246, as amended; in the rules, regulations, and orders of the Secretary of Labor; or as otherwise provided by law.

(10) The Contractor shall include the terms and conditions of subparagraphs (b)(1) through (11) of this clause in every subcontract or purchase order that is not exempted by the rules, regulations, or orders of the Secretary of Labor issued under Executive Order 11246, as amended, so that these terms and conditions will be binding upon each subcontractor or vendor.

(11) The Contractor shall take such action with respect to any subcontract or purchase order as the contracting officer may direct as a means of enforcing these terms and conditions, including sanctions for noncompliance; provided, that if the Contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of any direction, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

(c) Notwithstanding any other clause in this contract, disputes relative to this clause will be governed by the procedures in 41 CFR 60-1.1.

(End of clause)

#### 52.222-27 AFFIRMATIVE ACTION COMPLIANCE REQUIREMENTS FOR CONSTRUCTION (FEB 1999)

(a) Definitions. "Covered area," as used in this clause, means the geographical area described in the solicitation for this contract.

"Deputy Assistant Secretary," as used in this clause, means Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, or a designee.

"Employer's identification number," as used in this clause, means the Federal Social Security

number used on the employer's quarterly federal tax return, U.S. Treasury Department Form 941.

"Minority," as used in this clause, means--

- (1) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).
  - (2) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands);
  - (3) Black (all persons having origins in any of the black African racial groups not of Hispanic origin); and
  - (4) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin, regardless of race).
- (b) If the Contractor, or a subcontractor at any tier, subcontracts a portion of the work involving any construction trade, each such subcontract in excess of \$10,000 shall include this clause and the Notice containing the goals for minority and female participation stated in the solicitation for this contract.
- (c) If the Contractor is participating in a Hometown Plan (41 CFR 60-4) approved by the U.S. Department of Labor in a covered area, either individually or through an association, its affirmative action obligations on all work in the plan area (including goals) shall comply with the plan for those trades that have unions participating in the plan. Contractors must be able to demonstrate participation in, and compliance with, the provisions of the plan. Each Contractor or subcontractor participating in an approved plan is also required to comply with its obligations under the Equal Opportunity clause, and to make a good faith effort to achieve each goal under the plan in each trade in which it has employees. The overall good-faith performance by other Contractors or subcontractors toward a goal in an approved plan does not excuse any Contractor's or subcontractor's failure to make good-faith efforts to achieve the plan's goals.
- (d) The Contractor shall implement the affirmative action procedures in subparagraphs (g)(1) through (16) of this clause. The goals stated in the solicitation for this contract are expressed as percentages of the total hours of employment and training of minority and female utilization that the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for the geographical area where that work is actually performed. The Contractor is expected to make substantially uniform progress toward its goals in each craft.
- (e) Neither the terms and conditions of any collective bargaining agreement, nor the failure by a union with which the Contractor has a collective bargaining agreement, to refer minorities or women shall excuse the Contractor's obligations under this clause, Executive Order 11246, as amended, or the regulations thereunder.

(f) In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.

(g) The Contractor shall take affirmative action to ensure equal employment opportunity. The evaluation of the Contractor's compliance with this clause shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully and implement affirmative action steps at least as extensive as the following:

(1) Ensure a working environment free of harassment, intimidation, and coercion at all sites and in all facilities where the Contractor's employees are assigned to work. The Contractor, if possible, will assign two or more women to each construction project. The Contractor shall ensure that foremen, superintendents, and other onsite supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at these sites or facilities.

(2) Establish and maintain a current list of sources for minority and female recruitment. Provide written notification to minority and female recruitment sources and community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

(3) Establish and maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant, referrals of minorities or females from unions, recruitment sources, or community organizations, and the action taken with respect to each individual. If an individual was sent to the union hiring hall for referral and not referred back to the Contractor by the union or, if referred back, not employed by the Contractor, this shall be documented in the file, along with whatever additional actions the Contractor may have taken.

(4) Immediately notify the Deputy Assistant Secretary when the union or unions with which the Contractor has a collective bargaining agreement has not referred back to the Contractor a minority or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

(5) Develop on-the-job training opportunities and/or participate in training programs for the area that expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under subparagraph (g)(2) of this clause.

(6) Disseminate the Contractor's equal employment policy by--

(i) Providing notice of the policy to unions and to training, recruitment, and outreach programs, and requesting their cooperation in assisting the Contractor in meeting its contract obligations;

(ii) Including the policy in any policy manual and in collective bargaining agreements;

(iii) Publicizing the policy in the company newspaper, annual report, etc.;

(iv) Reviewing the policy with all management personnel and with all minority and female employees at least once a year; and

(v) Posting the policy on bulletin boards accessible to employees at each location where construction work is performed.

(7) Review, at least annually, the Contractor's equal employment policy and affirmative action obligations with all employees having responsibility for hiring, assignment, layoff, termination, or other employment decisions. Conduct review of this policy with all on-site supervisory personnel before initiating construction work at a job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

(8) Disseminate the Contractor's equal employment policy externally by including it in any advertising in the news media, specifically including minority and female news media. Provide written notification to, and discuss this policy with, other Contractors and subcontractors with which the Contractor does or anticipates doing business.

(9) Direct recruitment efforts, both oral and written, to minority, female, and community organizations, to schools with minority and female students, and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than 1 month before the date for acceptance of applications for apprenticeship or training by any recruitment source, send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

(10) Encourage present minority and female employees to recruit minority persons and women. Where reasonable, provide after-school, summer, and vacation employment to minority and female youth both on the site and in other areas of the Contractor's workforce.

(11) Validate all tests and other selection requirements where required under 41 CFR 60-3.

(12) Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities. Encourage these employees to seek or to prepare for, through appropriate training, etc., opportunities for promotion.

(13) Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring all personnel and employment-related activities to ensure that the Contractor's obligations under this contract are being carried out.

(14) Ensure that all facilities and company activities are nonsegregated except that separate or single-user rest rooms and necessary dressing or sleeping areas shall be provided to assure privacy between the sexes.

(15) Maintain a record of solicitations for subcontracts for minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.

(16) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's equal employment policy and affirmative action obligations.

(h) The Contractor is encouraged to participate in voluntary associations that may assist in fulfilling one or more of the affirmative action obligations contained in subparagraphs (g)(1) through (16) of this clause. The efforts of a contractor association, joint contractor-union, contractor-community, or similar group of which the contractor is a member and participant may be asserted as fulfilling one or more of its obligations under subparagraphs (g)(1) through (16) of this clause, provided the Contractor--

(1) Actively participates in the group;

(2) Makes every effort to ensure that the group has a positive impact on the employment of minorities and women in the industry;

(3) Ensures that concrete benefits of the program are reflected in the Contractor's minority and female workforce participation;

(4) Makes a good-faith effort to meet its individual goals and timetables; and

(5) Can provide access to documentation that demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply is the Contractor's, and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

(i) A single goal for minorities and a separate single goal for women shall be established. The Contractor is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and nonminority. Consequently, the Contractor may be in violation of Executive Order 11246, as amended, if a particular group is employed in a substantially disparate manner.

(j) The Contractor shall not use goals or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

(k) The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts under Executive Order 11246, as amended.

(l) The Contractor shall carry out such sanctions and penalties for violation of this clause and of

the Equal Opportunity clause, including suspension, termination, and cancellation of existing subcontracts, as may be imposed or ordered under Executive Order 11246, as amended, and its implementing regulations, by the OFCCP. Any failure to carry out these sanctions and penalties as ordered shall be a violation of this clause and Executive Order 11246, as amended.

(m) The Contractor in fulfilling its obligations under this clause shall implement affirmative action procedures at least as extensive as those prescribed in paragraph (g) of this clause, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of Executive Order 11246, as amended, the implementing regulations, or this clause, the Deputy Assistant Secretary shall take action as prescribed in 41 CFR 60-4.8.

(n) The Contractor shall designate a responsible official to--

(1) Monitor all employment-related activity to ensure that the Contractor's equal employment policy is being carried out;

(2) Submit reports as may be required by the Government; and

(3) Keep records that shall at least include for each employee the name, address, telephone number, construction trade, union affiliation (if any), employee identification number, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, separate records are not required to be maintained.

Nothing contained herein shall be construed as a limitation upon the application of other laws that establish different standards of compliance or upon the requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

(End of clause)

#### 52.222-35 AFFIRMATIVE ACTION FOR DISABLED VETERANS AND VETERANS OF THE VIETNAM ERA (APR 1998)

(a) ) Definitions. As used in this clause--

All employment openings includes all positions except executive and top management, those positions that will be filled from within the contractor's organization, and positions lasting 3 days or less. This term includes full-time employment, temporary employment of more than 3 days' duration, and part-time employment.

Appropriate office of the State employment service system means the local office of the Federal-State national system of public employment offices with assigned responsibility to serve the area

where the employment opening is to be filled, including the District of Columbia, Guam, the Commonwealth of Puerto Rico, and the Virgin Islands.

Positions that will be filled from within the Contractor's organization means employment openings for which no consideration will be given to persons outside the Contractor's organization (including any affiliates, subsidiaries, and parent companies) and includes any openings that the Contractor proposes to fill from regularly established "recall" lists. The exception does not apply to a particular opening once an employer decides to consider applicants outside of its organization.

Veteran of the Vietnam era means a person who--

(1) Served on active duty for a period of more than 180 days, any part of which occurred between August 5, 1964, and May 7, 1975, and was discharged or released therefrom with other than a dishonorable discharge; or

(2) Was discharged or released from active duty for a service-connected disability if any part of such active duty was performed between August 5, 1964, and May 7, 1975.

(b) General. (1) Regarding any position for which the employee or applicant for employment is qualified, the Contractor shall not discriminate against the individual because the individual is a disabled veteran or a veteran of the Vietnam era. The Contractor agrees to take affirmative action to employ, advance in employment, and otherwise treat qualified disabled veterans and veterans of the Vietnam era without discrimination based upon their disability or veterans' status in all employment practices such as--

(i) Employment;

(ii) Upgrading;

(iii) Demotion or transfer;

(iv) Recruitment;

(v) Advertising;

(vi) Layoff or termination;

(vii) Rates of pay or other forms of compensation; and

(viii) Selection for training, including apprenticeship.

(2) The Contractor agrees to comply with the rules, regulations, and relevant orders of the Secretary of Labor (Secretary) issued under the Vietnam Era Veterans' Readjustment Assistance Act of 1972 (the Act), as amended.

(c) Listing openings. (1) The Contractor agrees to list all employment openings existing at contract award or occurring during contract performance, at an appropriate office of the State employment service system in the locality where the opening occurs. These openings include those occurring at any Contractor facility, including one not connected with performing this contract. An independent corporate affiliate is exempt from this requirement.

(2) State and local government agencies holding Federal contracts of \$10,000 or more shall also list all their employment openings with the appropriate office of the State employment service.

(3) The listing of employment openings with the State employment service system is required at least concurrently with using any other recruitment source or effort and involves the obligations of placing a bona fide job order, including accepting referrals of veterans and nonveterans. This listing does not require hiring any particular job applicant or hiring from any particular group of job applicants and is not intended to relieve the Contractor from any requirements of Executive orders or regulations concerning nondiscrimination in employment.

(4) Whenever the Contractor becomes contractually bound to the listing terms of this clause, it shall advise the State employment service system, in each State where it has establishments, of the name and location of each hiring location in the State. As long as the Contractor is contractually bound to these terms and has so advised the State system, it need not advise the State system of subsequent contracts. The Contractor may advise the State system when it is no longer bound by this contract clause.

(d) Applicability. This clause does not apply to the listing of employment openings that occur and are filled outside the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, Guam, and the Virgin Islands.

(e) Postings. (1) The Contractor agrees to post employment notices stating (i) the Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified disabled veterans and veterans of the Vietnam era, and (ii) the rights of applicants and employees.

(2) These notices shall be posted in conspicuous places that are available to employees and applicants for employment. They shall be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance Programs, Department of Labor (Deputy Assistant Secretary), and provided by or through the Contracting Officer.

(3) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding, that the Contractor is bound by the terms of the Act, and is committed to take affirmative action to employ, and advance in employment, qualified disabled veterans and veterans of the Vietnam Era.

(f) Noncompliance. If the Contractor does not comply with the requirements of this clause, appropriate actions may be taken under the rules, regulations, and relevant orders of the Secretary issued pursuant to the Act.



(g) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order of \$10,000 or more unless exempted by rules, regulations, or orders of the Secretary. The Contractor shall act as specified by the Deputy Assistant Secretary to enforce the terms, including action for noncompliance.

(End of clause)

#### 52.222-36 AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998)

(a) General. (1) Regarding any position for which the employee or applicant for employment is qualified, the Contractor shall not discriminate against any employee or applicant because of physical or mental disability. The Contractor agrees to take affirmative action to employ, advance in employment, and otherwise treat qualified individuals with disabilities without discrimination based upon their physical or mental disability in all employment practices such as--

- (i) Recruitment, advertising, and job application procedures;
  - (ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff, and rehiring;
  - (iii) Rates of pay or any other form of compensation and changes in compensation;
  - (iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;
  - (v) Leaves of absence, sick leave, or any other leave;
  - (vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;
  - (vii) Selection and financial support for training, including apprenticeships, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;
  - (viii) Activities sponsored by the Contractor, including social or recreational programs; and
  - (ix) Any other term, condition, or privilege of employment.
- (2) The Contractor agrees to comply with the rules, regulations, and relevant orders of the Secretary of Labor (Secretary) issued under the Rehabilitation Act of 1973 (29 U.S.C. 793) (the Act), as amended.
- (b) Postings. (1) The Contractor agrees to post employment notices stating--

(i) The Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified individuals with disabilities; and

(ii) The rights of applicants and employees.

(2) These notices shall be posted in conspicuous places that are available to employees and applicants for employment. The Contractor shall ensure that applicants and employees with disabilities are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled individual, or may lower the posted notice so that it might be read by a person in a wheelchair). The notices shall be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance of the U.S. Department of Labor (Deputy Assistant Secretary) and shall be provided by or through the Contracting Officer.

(3) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding, that the Contractor is bound by the terms of Section 503 of the Act and is committed to take affirmative action to employ, and advance in employment, qualified individuals with physical or mental disabilities.

(c) Noncompliance. If the Contractor does not comply with the requirements of this clause, appropriate actions may be taken under the rules, regulations, and relevant orders of the Secretary issued pursuant to the Act.

(d) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of \$10,000 unless exempted by rules, regulations, or orders of the Secretary. The Contractor shall act as specified by the Deputy Assistant Secretary to enforce the terms, including action for noncompliance.

(End of clause)

#### 52.222-37 EMPLOYMENT REPORTS ON DISABLED VETERANS AND VETERANS OF THE VIETNAM ERA (JAN 1999)

(a) Unless the Contractor is a State or local government agency, the Contractor shall report at least annually, as required by the Secretary of Labor, on--

(1) The number of disabled veterans and the number of veterans of the Vietnam era in the workforce of the contractor by job category and hiring location; and

(2) The total number of new employees hired during the period covered by the report, and of that total, the number of disabled veterans, and the number of veterans of the Vietnam era.

(b) The above items shall be reported by completing the form entitled "Federal Contractor Veterans' Employment Report VETS-100."

(c) Reports shall be submitted no later than September 30 of each year beginning September 30, 1988.

(d) The employment activity report required by paragraph (a)(2) of this clause shall reflect total hires during the most recent 12-month period as of the ending date selected for the employment profile report required by paragraph (a)(1) of this clause. Contractors may select an ending date: (1) As of the end of any pay period during the period January through March 1st of the year the report is due, or (2) as of December 31, if the contractor has previous written approval from the Equal Employment Opportunity Commission to do so for purposes of submitting the Employer Information Report EEO-1 (Standard Form 100).

(e) The count of veterans reported according to paragraph (a) of this clause shall be based on voluntary disclosure. Each Contractor subject to the reporting requirements at 38 U.S.C. 4212 shall invite all disabled veterans and veterans of the Vietnam era who wish to benefit under the affirmative action program at 38 U.S.C. 4212 to identify themselves to the Contractor. The invitation shall state that the information is voluntarily provided; that the information will be kept confidential; that disclosure or refusal to provide the information will not subject the applicant or employee to any adverse treatment; and that the information will be used only in accordance with the regulations promulgated under 38 U.S.C. 4212.

(f) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order of \$10,000 or more unless exempted by rules, regulations, or orders of the Secretary.

(End of clause)

#### 52.222-38 COMPLIANCE WITH VETERANS' EMPLOYMENT REPORTING REQUIREMENTS (DEC 2001)

By submission of its offer, the offeror represents that, if it is subject to the reporting requirements of 38 U.S.C. 4212(d) (i.e., if it has any contract containing Federal Acquisition Regulation clause 52.222-37, Employment Reports on Special Disabled Veterans, Veterans of the Vietnam Era, and Other Eligible Veterans), it has submitted the most recent VETS-100 Report required by that clause.

(End of provision)

#### 52.223-5 POLLUTION PREVENTION AND RIGHT-TO-KNOW INFORMATION (APR 1998)

(a) Executive Order 12856 of August 3, 1993, requires Federal facilities to comply with the provisions of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA)(42 U.S.C. 11001-11050) and the Pollution Prevention Act of 1990 (PPA)(42 U.S.C. 13101-13109).

(b) The Contractor shall provide all information needed by the Federal facility to comply with the emergency planning reporting requirements of Section 302 of EPCRA; the emergency notice requirements of Section 304 of EPCRA; the list of Material Safety Data Sheets required by Section 311 of EPCRA; the emergency and hazardous chemical inventory forms of Section 312

of EPCRA; the toxic chemical release inventory of Section 313 of EPCRA, which includes the reduction and recycling information required by Section 6607 of PPA; and the toxic chemical reduction goals requirements of Section 3-302 of Executive Order 12856.

(End of clause)

#### 52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(a) Definitions. As used in this clause --

"Controlled substance" means a controlled substance in schedules I through V of section 202 of the Controlled Substances Act (21 U.S.C. 812) and as further defined in regulation at 21 CFR 1308.11 - 1308.15.

"Conviction" means a finding of guilt (including a plea of nolo contendere) or imposition of sentence, or both, by any judicial body charged with the responsibility to determine violations of the Federal or State criminal drug statutes.

"Criminal drug statute" means a Federal or non-Federal criminal statute involving the manufacture, distribution, dispensing, possession, or use of any controlled substance.

"Drug-free workplace" means the site(s) for the performance of work done by the Contractor in connection with a specific contract at which employees of the Contractor are prohibited from engaging in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance.

"Employee" means an employee of a Contractor directly engaged in the performance of work under a Government contract. "Directly engaged" is defined to include all direct cost employees and any other Contractor employee who has other than a minimal impact or involvement in contract performance.

"Individual" means an offeror/contractor that has no more than one employee including the offeror/contractor.

(b) The Contractor, if other than an individual, shall-- within 30 days after award (unless a longer period is agreed to in writing for contracts of 30 days or more performance duration), or as soon as possible for contracts of less than 30 days performance duration--

(1) Publish a statement notifying its employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such prohibition;

(2) Establish an ongoing drug-free awareness program to inform such employees about--

(i) The dangers of drug abuse in the workplace;

- (ii) The Contractor's policy of maintaining a drug-free workplace;
  - (iii) Any available drug counseling, rehabilitation, and employee assistance programs; and
  - (iv) The penalties that may be imposed upon employees for drug abuse violations occurring in the workplace;
- (3) Provide all employees engaged in performance of the contract with a copy of the statement required by subparagraph (b)(1) of this clause;
- (4) Notify such employees in writing in the statement required by subparagraph (b)(1) of this clause that, as a condition of continued employment on this contract, the employee will--
- (i) Abide by the terms of the statement; and
  - (ii) Notify the employer in writing of the employee's conviction under a criminal drug statute for a violation occurring in the workplace no later than 5 days after such conviction.
- (5) Notify the Contracting Officer in writing within 10 days after receiving notice under subdivision (b)(4)(ii) of this clause, from an employee or otherwise receiving actual notice of such conviction. The notice shall include the position title of the employee;
- (6) Within 30 days after receiving notice under subdivision (b)(4)(ii) of this clause of a conviction, take one of the following actions with respect to any employee who is convicted of a drug abuse violation occurring in the workplace:
- (i) Taking appropriate personnel action against such employee, up to and including termination; or
  - (ii) Require such employee to satisfactorily participate in a drug abuse assistance or rehabilitation program approved for such purposes by a Federal, State, or local health, law enforcement, or other appropriate agency; and
- (7) Make a good faith effort to maintain a drug-free workplace through implementation of subparagraphs (b)(1) through (b)(6) of this clause.
- (c) The Contractor, if an individual, agrees by award of the contract or acceptance of a purchase order, not to engage in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance while performing this contract.
- (d) In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraph (b) or (c) of this clause may, pursuant to FAR 23.506, render the Contractor subject to suspension of contract payments, termination of the contract for default, and suspension or debarment.
- (End of clause)

## 52.223-14 TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)

(a) Unless otherwise exempt, the Contractor, as owner or operator of a facility used in the performance of this contract, shall file by July 1 for the prior calendar year an annual Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11023(a) and (g)), and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106). The Contractor shall file, for each facility subject to the Form R filing and reporting requirements, the annual Form R throughout the life of the contract.

(b) A Contractor owned or operated facility used in the performance of this contract is exempt from the requirement to file an annual Form R if--

(1) The facility does not manufacture, process, or otherwise use any toxic chemicals listed under section 313(c) of EPCRA, 42 U.S.C. 11023(c);

(2) The facility does not have 10 or more full-time employees as specified in section 313(b)(1)(A) of EPCRA, 42 U.S.C. 11023(b)(1)(A);

(3) The facility does not meet the reporting thresholds of toxic chemicals established under of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

(4) The facility does not fall within Standard Industrial Classification Code (SIC) major groups 20 through 39 or their corresponding North American Industry Classification System (NAICS) sectors 31 through 33; or

(5) The facility is not located within any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, Guam, American Samoa, the United States Virgin Islands, the Northern Mariana Islands, or any other territory or possession over which the United States has jurisdiction.

(c) If the Contractor has certified to an exemption in accordance with one or more of the criteria in paragraph (b) of this clause, and after award of the contract circumstances change so that any of its owned or operated facilities used in the performance of this contract is no longer exempt--

(1) The Contractor shall notify the Contracting Officer; and

(2) The Contractor, as owner or operator of a facility used in the performance of this contract that is no longer exempt, shall (i) submit a Toxic Chemical Release Inventory Form (Form R) on or before July 1 for the prior calendar year during which the facility becomes eligible; and (ii) continue to file the annual Form R for the life of the contract for such facility.

(d) The Contracting Officer may terminate this contract or take other action as appropriate, if the Contractor fails to comply accurately and fully with the EPCRA and PPA toxic chemical release filing and reporting requirements.

(e) Except for acquisitions of commercial items, as defined in FAR Part 2, the Contractor shall--

(1) For competitive subcontracts expected to exceed \$100,000 (including all options), include a solicitation provision substantially the same as the provision at FAR 52.223-13, Certification of Toxic Chemical Release Reporting; and

(2) Include in any resultant subcontract exceeding \$100,000 (including all options), the substance of this clause, except this paragraph (e).

(End of clause)

#### 52.225-13 RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUL 2000)

(a) The Contractor shall not acquire, for use in the performance of this contract, any supplies or services originating from sources within, or that were located in or transported from or through, countries whose products are banned from importation into the United States under regulations of the Office of Foreign Assets Control, Department of the Treasury. Those countries are Cuba, Iran, Iraq, Libya, North Korea, Sudan, the territory of Afghanistan controlled by the Taliban, and Serbia (excluding the territory of Kosovo).

(b) The Contractor shall not acquire for use in the performance of this contract any supplies or services from entities controlled by the government of Iraq.

(c) The Contractor shall insert this clause, including this paragraph (c), in all subcontracts.

(End of clause)

#### 52.225-14 INCONSISTENCY BETWEEN ENGLISH VERSION AND TRANSLATION OF CONTRACT (FEB 2000)

In the event of inconsistency between any terms of this contract and any translation into another language, the English language meaning shall control.

(End of clause)

#### 52.227-1 AUTHORIZATION AND CONSENT (JUL 1995)

(a) The Government authorizes and consents to all use and manufacture, in performing this contract or any subcontract at any tier, of any invention described in and covered by a United States patent (1) embodied in the structure or composition of any article the delivery of which is accepted by the Government under this contract or (2) used in machinery, tools, or methods whose use necessarily results from compliance by the Contractor or a subcontractor with (i)

specifications or written provisions forming a part of this contract or (ii) specific written instructions given by the Contracting Officer directing the manner of performance. The entire liability to the Government for infringement of a patent of the United States shall be determined solely by the provisions of the indemnity clause, if any, included in this contract or any subcontract hereunder (including any lower-tier subcontract), and the Government assumes liability for all other infringement to the extent of the authorization and consent hereinabove granted.

(b) The Contractor agrees to include, and require inclusion of, this clause, suitably modified to identify the parties, in all subcontracts at any tier for supplies or services (including construction, architect-engineer services, and materials, supplies, models, samples, and design or testing services expected to exceed the simplified acquisition threshold (however, omission of this clause from any subcontract, including those at or below the simplified acquisition threshold, does not affect this authorization and consent.)

(End of clause)

#### 52.227-2 NOTICE AND ASSISTANCE REGARDING PATENT AND COPYRIGHT INFRINGEMENT (AUG 1996)

(a) The Contractor shall report to the Contracting Officer, promptly and in reasonable written detail, each notice or claim of patent or copyright infringement based on the performance of this contract of which the Contractor has knowledge.

(b) In the event of any claim or suit against the Government on account of any alleged patent or copyright infringement arising out of the performance of this contract or out of the use of any supplies furnished or work or services performed under this contract, the Contractor shall furnish to the Government, when requested by the Contracting Officer, all evidence and information in possession of the Contractor pertaining to such suit or claim. Such evidence and information shall be furnished at the expense of the Government except where the Contractor has agreed to indemnify the Government.

(d) The Contractor agrees to include, and require inclusion of, this clause in all subcontracts at any tier for supplies or services (including construction and architect-engineer subcontracts and those for material, supplies, models, samples, or design or testing services) expected to exceed the simplified acquisition threshold at (FAR) 2.101 to exceed the dollar amount set forth in 13.000 of the Federal Acquisition Regulation (FAR).

(End of clause)

#### 52.227-4 PATENT INDEMNITY--CONSTRUCTION CONTRACTS (APR 1984)

Except as otherwise provided, the Contractor agrees to indemnify the Government and its officers, agents, and employees against liability, including costs and expenses, for infringement upon any United States patent (except a patent issued upon an application that is now or may hereafter be withheld from issue pursuant to a Secrecy Order under 35 U.S.C. 181) arising out of



performing this contract or out of the use or disposal by or for the account of the Government of supplies furnished or work performed under this contract.

(End of clause)

#### 52.228-2 ADDITIONAL BOND SECURITY (OCT 1997)

The Contractor shall promptly furnish additional security required to protect the Government and persons supplying labor or materials under this contract if--

- (a) Any surety upon any bond, or issuing financial institution for other security, furnished with this contract becomes unacceptable to the Government.
- (b) Any surety fails to furnish reports on its financial condition as required by the Government;
- (c) The contract price is increased so that the penal sum of any bond becomes inadequate in the opinion of the Contracting Officer; or
- (d) An irrevocable letter of credit (ILC) used as security will expire before the end of the period of required security. If the Contractor does not furnish an acceptable extension or replacement ILC, or other acceptable substitute, at least 30 days before an ILC's scheduled expiration, the Contracting officer has the right to immediately draw on the ILC.

(End of clause)

#### 52.228-11 PLEDGES OF ASSETS (FEB 1992)

(a) Offerors shall obtain from each person acting as an individual surety on a bid guarantee, a performance bond, or a payment bond--

(1) Pledge of assets; and

(2) Standard Form 28, Affidavit of Individual Surety.

(b) Pledges of assets from each person acting as an individual surety shall be in the form of--

(1) Evidence of an escrow account containing cash, certificates of deposit, commercial or Government securities, or other assets described in FAR 28.203-2 (except see 28.203-2(b)(2) with respect to Government securities held in book entry form) and/or;

(2) A recorded lien on real estate. The offeror will be required to provide--

(i) Evidence of title in the form of a certificate of title prepared by a title insurance company approved by the United States Department of Justice. This title evidence must show fee simple title vested in the surety along with any concurrent owners; whether any real estate taxes are due and payable; and any recorded encumbrances against the property, including the lien filed in

favor of the Government as required by FAR 28.203-3(d);

(ii) Evidence of the amount due under any encumbrance shown in the evidence of title;

(iii) A copy of the current real estate tax assessment of the property or a current appraisal dated no earlier than 6 months prior to the date of the bond, prepared by a professional appraiser who certifies that the appraisal has been conducted in accordance with the generally accepted appraisal standards as reflected in the Uniform Standards of Professional Appraisal Practice, as promulgated by the Appraisal Foundation.

(End of clause)

#### 52.229-3 FEDERAL, STATE, AND LOCAL TAXES (JAN 1991)

(a) "Contract date," as used in this clause, means the date set for bid opening or, if this is a negotiated contract or a modification, the effective date of this contract or modification.

"All applicable Federal, State, and local taxes and duties," as used in this clause, means all taxes and duties, in effect on the contract date, that the taxing authority is imposing and collecting on the transactions or property covered by this contract.

"After-imposed Federal tax," as used in this clause, means any new or increased Federal excise tax or duty, or tax that was exempted or excluded on the contract date but whose exemption was later revoked or reduced during the contract period, on the transactions or property covered by this contract that the Contractor is required to pay or bear as the result of legislative, judicial, or administrative action taking effect after the contract date. It does not include social security tax or other employment taxes.

"After-relieved Federal tax," as used in this clause, means any amount of Federal excise tax or duty, except social security or other employment taxes, that would otherwise have been payable on the transactions or property covered by this contract, but which the Contractor is not required to pay or bear, or for which the Contractor obtains a refund or drawback, as the result of legislative, judicial, or administrative action taking effect after the contract date.

(b) The contract price includes all applicable Federal, State, and local taxes and duties.

(c) The contract price shall be increased by the amount of any after-imposed Federal tax, provided the Contractor warrants in writing that no amount for such newly imposed Federal excise tax or duty or rate increase was included in the contract price, as a contingency reserve or otherwise.

(d) The contract price shall be decreased by the amount of any after-relieved Federal tax.

(e) The contract price shall be decreased by the amount of any Federal excise tax or duty, except social security or other employment taxes, that the Contractor is required to pay or bear, or does not obtain a refund of, through the Contractor's fault, negligence, or failure to follow instructions of the Contracting Officer.

(f) No adjustment shall be made in the contract price under this clause unless the amount of the adjustment exceeds \$250.

(g) The Contractor shall promptly notify the Contracting Officer of all matters relating to any Federal excise tax or duty that reasonably may be expected to result in either an increase or decrease in the contract price and shall take appropriate action as the Contracting Officer directs.

(h) The Government shall, without liability, furnish evidence appropriate to establish exemption from any Federal, State, or local tax when the Contractor requests such evidence and a reasonable basis exists to sustain the exemption.

(End of clause)

52.232-5 PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (MAY 1997)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

(i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.

(ii) A listing of the amount included for work performed by each subcontractor under the contract.

(iii) A listing of the total amount of each subcontract under the contract.

(iv) A listing of the amounts previously paid to each such subcontractor under the contract.

(v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the Contractor at locations other than the site also may be taken into consideration if--

(i) Consideration is specifically authorized by this contract; and

(ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and

that the material will be used to perform this contract.

(c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that--

(1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;

(2) Payments to subcontractors and suppliers have been made from previous payments received under the contract, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of chapter 39 of Title 31, United States Code;

(3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and

(4) This certification is not to be construed as final acceptance of a subcontractor's performance.

---

(Name)

---

(Title)

---

(Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the Contractor shall--

(1) Notify the Contracting Officer of such performance deficiency; and

(2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8th day after the date of receipt of the unearned amount until--

(i) The date the Contractor notifies the Contracting Officer that the performance deficiency has

been corrected; or

(ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.

(e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.

(f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as--

(1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or

(2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.

(g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion of progress payments attributable to bond premiums.

(h) Final payment. The Government shall pay the amount due the Contractor under this contract after--

(1) Completion and acceptance of all work;

(2) Presentation of a properly executed voucher; and

(3) Presentation of release of all claims against the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of 1940 (31 U.S.C. 3727 and 41 U.S.C. 15).

(i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in FAR Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.

(j) Interest computation on unearned amounts. In accordance with 31 U.S.C. 3903(c)(1), the amount payable under subparagraph (d)(2) of this clause shall be--

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

(End of clause)

#### 52.232-17 INTEREST (JUNE 1996)

(a) Except as otherwise provided in this contract under a Price Reduction for Defective Cost or Pricing Data clause or a Cost Accounting Standards clause, all amounts that become payable by the Contractor to the Government under this contract (net of any applicable tax credit under the Internal Revenue Code (26 U.S.C. 1481)) shall bear simple interest from the date due until paid unless paid within 30 days of becoming due. The interest rate shall be the interest rate established by the Secretary of the Treasury as provided in Section 12 of the Contract Disputes Act of 1978 (Public Law 95-563), which is applicable to the period in which the amount becomes due, as provided in paragraph (b) of this clause, and then at the rate applicable for each six-month period as fixed by the Secretary until the amount is paid. reproduce, prepare derivative works, distribute copies to the public, and (b) Amounts shall be due at the earliest of the following dates:

(1) The date fixed under this contract.

(2) The date of the first written demand for payment consistent with this contract, including any demand resulting from a default termination.

(3) The date the Government transmits to the Contractor a proposed supplemental agreement to confirm completed negotiations establishing the amount of debt.

(4) If this contract provides for revision of prices, the date of written notice to the Contractor stating the amount of refund payable in connection with a pricing proposal or a negotiated pricing agreement not confirmed by contract modification.

(c) The interest charge made under this clause may be reduced under the procedures prescribed

in 32.614-2 of the Federal Acquisition Regulation in effect on the date of this contract.

(End of clause)

#### 52.232-23 ASSIGNMENT OF CLAIMS (JAN 1986)

(a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 15 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

(End of clause)

#### 52.232-27 PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (FEB 2002)

Notwithstanding any other payment terms in this contract, the Government will make invoice payments under the terms and conditions specified in this clause. The Government considers payment as being made on the day a check is dated or the date of an electronic funds transfer. Definitions of pertinent terms are set forth in sections 2.101, 32.001, and 32.902 of the Federal Acquisition Regulation. All days referred to in this clause are calendar days, unless otherwise specified. (However, see paragraph (a)(3) concerning payments due on Saturdays, Sundays, and legal holidays.)

(a) Invoice payments--(1) Types of invoice payments. For purposes of this clause, there are several types of invoice payments that may occur under this contract, as follows:

(i) Progress payments, if provided for elsewhere in this contract, based on Contracting Officer approval of the estimated amount and value of work or services performed, including payments for reaching milestones in any project.

(A) The due date for making such payments is 14 days after the designated billing office receives a proper payment request. If the designated billing office fails to annotate the payment request with the actual date of receipt at the time of receipt, the payment due date is the 14th day after the date of the Contractor's payment request, provided the designated billing office receives a

proper payment request and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(B) The due date for payment of any amounts retained by the Contracting Officer in accordance with the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts, is as specified in the contract or, if not specified, 30 days after approval by the Contracting Officer for release to the Contractor.

(ii) Final payments based on completion and acceptance of all work and presentation of release of all claims against the Government arising by virtue of the contract, and payments for partial deliveries that have been accepted by the Government (e.g., each separate building, public work, or other division of the contract for which the price is stated separately in the contract).

(A) The due date for making such payments is the later of the following two events:

(1) The 30th day after the designated billing office receives a proper invoice from the Contractor.

(2) The 30th day after Government acceptance of the work or services completed by the Contractor. For a final invoice when the payment amount is subject to contract settlement actions (e.g., release of claims), acceptance is deemed to occur on the effective date of the contract settlement.

(B) If the designated billing office fails to annotate the invoice with the date of actual receipt at the time of receipt, the invoice payment due date is the 30th day after the date of the Contractor's invoice, provided the designated billing office receives a proper invoice and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(2) Contractor's invoice. The Contractor shall prepare and submit invoices to the designated billing office specified in the contract. A proper invoice must include the items listed in paragraphs (a)(2)(i) through (a)(2)(xi) of this clause. If the invoice does not comply with these requirements, the designated billing office must return it within 7 days after receipt, with the reasons why it is not a proper invoice. When computing any interest penalty owed the Contractor, the Government will take into account if the Government notifies the Contractor of an improper invoice in an untimely manner.

(i) Name and address of the Contractor.

(ii) Invoice date and invoice number. (The Contractor should date invoices as close as possible to the date of mailing or transmission.)

(iii) Contract number or other authorization for work or services performed (including order number and contract line item number).

(iv) Description of work or services performed.

(v) Delivery and payment terms (e.g., discount for prompt payment terms).



(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the contract or in a proper notice of assignment).

(vii) Name (where practicable), title, phone number, and mailing address of person to notify in the event of a defective invoice.

(viii) For payments described in paragraph (a)(1)(i) of this clause, substantiation of the amounts requested and certification in accordance with the requirements of the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts.

(ix) Taxpayer Identification Number (TIN). The Contractor shall include its TIN on the invoice only if required elsewhere in this contract.

(x) Electronic funds transfer (EFT) banking information.

(A) The Contractor shall include EFT banking information on the invoice only if required elsewhere in this contract.

(B) If EFT banking information is not required to be on the invoice, in order for the invoice to be a proper invoice, the Contractor shall have submitted correct EFT banking information in accordance with the applicable solicitation provision (e.g., 52.232-38, Submission of Electronic Funds Transfer Information with Offer), contract clause (e.g., 52.232-33, Payment by Electronic Funds Transfer--Central Contractor Registration, or 52.232-34, Payment by Electronic Funds Transfer--Other Than Central Contractor Registration), or applicable agency procedures.

(C) EFT banking information is not required if the Government waived the requirement to pay by EFT.

(xi) Any other information or documentation required by the contract.

(3) Interest penalty. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if payment is not made by the due date and the conditions listed in paragraphs (a)(3)(i) through (a)(3)(iii) of this clause are met, if applicable. However, when the due date falls on a Saturday, Sunday, or legal holiday, the designated payment office may make payment on the following working day without incurring a late payment interest penalty.

(i) The designated billing office received a proper invoice.

(ii) The Government processed a receiving report or other Government documentation authorizing payment and there was no disagreement over quantity, quality, Contractor compliance with any contract term or condition, or requested progress payment amount.

(iii) In the case of a final invoice for any balance of funds due the Contractor for work or services performed, the amount was not subject to further contract settlement actions between the Government and the Contractor.

(4) Computing penalty amount. The Government will compute the interest penalty in accordance with the Office of Management and Budget prompt payment regulations at 5 CFR part 1315.

(i) For the sole purpose of computing an interest penalty that might be due the Contractor for payments described in paragraph (a)(1)(ii) of this clause, Government acceptance or approval is deemed to occur constructively on the 7th day after the Contractor has completed the work or services in accordance with the terms and conditions of the contract. If actual acceptance or approval occurs within the constructive acceptance or approval period, the Government will base the determination of an interest penalty on the actual date of acceptance or approval. Constructive acceptance or constructive approval requirements do not apply if there is a disagreement over quantity, quality, or Contractor compliance with a contract provision. These requirements also do not compel Government officials to accept work or services, approve Contractor estimates, perform contract administration functions, or make payment prior to fulfilling their responsibilities.

(ii) The prompt payment regulations at 5 CFR 1315.10(c) do not require the Government to pay interest penalties if payment delays are due to disagreement between the Government and the Contractor over the payment amount or other issues involving contract compliance, or on amounts temporarily withheld or retained in accordance with the terms of the contract. The Government and the Contractor shall resolve claims involving disputes, and any interest that may be payable in accordance with the clause at FAR 52.233-1, Disputes.

(5) Discounts for prompt payment. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if the Government takes a discount for prompt payment improperly. The Government will calculate the interest penalty in accordance with the prompt payment regulations at 5 CFR part 1315.

(6) Additional interest penalty. (i) The designated payment office will pay a penalty amount, calculated in accordance with the prompt payment regulations at 5 CFR part 1315 in addition to the interest penalty amount only if--

(A) The Government owes an interest penalty of \$1 or more;

(B) The designated payment office does not pay the interest penalty within 10 days after the date the invoice amount is paid; and

(C) The Contractor makes a written demand to the designated payment office for additional penalty payment, in accordance with paragraph (a)(6)(ii) of this clause, postmarked not later than 40 days after the date the invoice amount is paid.

(ii)(A) The Contractor shall support written demands for additional penalty payments with the following data. The Government will not request any additional data. The Contractor shall--

(1) Specifically assert that late payment interest is due under a specific invoice, and request payment of all overdue late payment interest penalty and such additional penalty as may be required;

(2) Attach a copy of the invoice on which the unpaid late payment interest was due; and

(3) State that payment of the principal has been received, including the date of receipt.

(B) If there is no postmark or the postmark is illegible--

(1) The designated payment office that receives the demand will annotate it with the date of receipt provided the demand is received on or before the 40th day after payment was made; or

(2) If the designated payment office fails to make the required annotation, the Government will determine the demand's validity based on the date the Contractor has placed on the demand, provided such date is no later than the 40th day after payment was made.

(b) Contract financing payments. If this contract provides for contract financing, the Government will make contract financing payments in accordance with the applicable contract financing clause.

(c) Subcontract clause requirements. The Contractor shall include in each subcontract for property or services (including a material supplier) for the purpose of performing this contract the following:

(1) Prompt payment for subcontractors. A payment clause that obligates the Contractor to pay the subcontractor for satisfactory performance under its subcontract not later than 7 days from receipt of payment out of such amounts as are paid to the Contractor under this contract.

(2) Interest for subcontractors. An interest penalty clause that obligates the Contractor to pay to the subcontractor an interest penalty for each payment not made in accordance with the payment clause--

(i) For the period beginning on the day after the required payment date and ending on the date on which payment of the amount due is made; and

(ii) Computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(3) Subcontractor clause flowdown. A clause requiring each subcontractor to use:

(i) Include a payment clause and an interest penalty clause conforming to the standards set forth in paragraphs (c)(1) and (c)(2) of this clause in each of its subcontracts; and

(ii) Require each of its subcontractors to include such clauses in their subcontracts with each lower-tier subcontractor or supplier.

(d) Subcontract clause interpretation. The clauses required by paragraph (c) of this clause shall not be construed to impair the right of the Contractor or a subcontractor at any tier to negotiate, and to include in their subcontract, provisions that--

(1) Retainage permitted. Permit the Contractor or a subcontractor to retain (without cause) a specified percentage of each progress payment otherwise due to a subcontractor for satisfactory performance under the subcontract without incurring any obligation to pay a late payment interest penalty, in accordance with terms and conditions agreed to by the parties to the subcontract, giving such recognition as the parties deem appropriate to the ability of a subcontractor to furnish a performance bond and a payment bond;

(2) Withholding permitted. Permit the Contractor or subcontractor to make a determination that part or all of the subcontractor's request for payment may be withheld in accordance with the subcontract agreement; and

(3) Withholding requirements. Permit such withholding without incurring any obligation to pay a late payment penalty if--

(i) A notice conforming to the standards of paragraph (g) of this clause previously has been furnished to the subcontractor; and

(ii) The Contractor furnishes to the Contracting Officer a copy of any notice issued by a Contractor pursuant to paragraph (d)(3)(i) of this clause.

(e) Subcontractor withholding procedures. If a Contractor, after making a request for payment to the Government but before making a payment to a subcontractor for the subcontractor's performance covered by the payment request, discovers that all or a portion of the payment otherwise due such subcontractor is subject to withholding from the subcontractor in accordance with the subcontract agreement, then the Contractor shall--

(1) Subcontractor notice. Furnish to the subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon ascertaining the cause giving rise to a withholding, but prior to the due date for subcontractor payment;

(2) Contracting Officer notice. Furnish to the Contracting Officer, as soon as practicable, a copy of the notice furnished to the subcontractor pursuant to paragraph (e)(1) of this clause;

(3) Subcontractor progress payment reduction. Reduce the subcontractor's progress payment by an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (e)(1) of this clause;

(4) Subsequent subcontractor payment. Pay the subcontractor as soon as practicable after the correction of the identified subcontract performance deficiency, and--

(i) Make such payment within--

(A) Seven days after correction of the identified subcontract performance deficiency (unless the funds therefor must be recovered from the Government because of a reduction under paragraph (e)(5)(i)) of this clause; or

(B) Seven days after the Contractor recovers such funds from the Government; or

(ii) Incur an obligation to pay a late payment interest penalty computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty;

(5) Notice to Contracting Officer. Notify the Contracting Officer upon--

(i) Reduction of the amount of any subsequent certified application for payment; or

(ii) Payment to the subcontractor of any withheld amounts of a progress payment, specifying--

(A) The amounts withheld under paragraph (e)(1) of this clause; and

(B) The dates that such withholding began and ended; and

(6) Interest to Government. Be obligated to pay to the Government an amount equal to interest on the withheld payments (computed in the manner provided in 31 U.S.C. 3903(c)(1)), from the 8th day after receipt of the withheld amounts from the Government until--

(i) The day the identified subcontractor performance deficiency is corrected; or

(ii) The date that any subsequent payment is reduced under paragraph (e)(5)(i) of this clause.

(f) Third-party deficiency reports--(1) Withholding from subcontractor. If a Contractor, after making payment to a first-tier subcontractor, receives from a supplier or subcontractor of the first-tier subcontractor (hereafter referred to as a "second-tier subcontractor") a written notice in accordance with section 2 of the Act of August 24, 1935 (40 U.S.C. 270b, Miller Act), asserting a deficiency in such first-tier subcontractor's performance under the contract for which the Contractor may be ultimately liable, and the Contractor determines that all or a portion of future payments otherwise due such first-tier subcontractor is subject to withholding in accordance with the subcontract agreement, the Contractor may, without incurring an obligation to pay an interest penalty under paragraph (e)(6) of this clause--

(i) Furnish to the first-tier subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon making such determination; and

(ii) Withhold from the first-tier subcontractor's next available progress payment or payments an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (f)(1)(i) of this clause.

(2) Subsequent payment or interest charge. As soon as practicable, but not later than 7 days after receipt of satisfactory written notification that the identified subcontract performance deficiency has been corrected, the Contractor shall--

(i) Pay the amount withheld under paragraph (f)(1)(ii) of this clause to such first-tier subcontractor; or

(ii) Incur an obligation to pay a late payment interest penalty to such first-tier subcontractor computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(g) Written notice of subcontractor withholding. The Contractor shall issue a written notice of any withholding to a subcontractor (with a copy furnished to the Contracting Officer), specifying--

(1) The amount to be withheld;

(2) The specific causes for the withholding under the terms of the subcontract; and

(3) The remedial actions to be taken by the subcontractor in order to receive payment of the amounts withheld.

(h) Subcontractor payment entitlement. The Contractor may not request payment from the Government of any amount withheld or retained in accordance with paragraph (d) of this clause until such time as the Contractor has determined and certified to the Contracting Officer that the subcontractor is entitled to the payment of such amount.

(i) Prime-subcontractor disputes. A dispute between the Contractor and subcontractor relating to the amount or entitlement of a subcontractor to a payment or a late payment interest penalty under a clause included in the subcontract pursuant to paragraph (c) of this clause does not constitute a dispute to which the Government is a party. The Government may not be interpleaded in any judicial or administrative proceeding involving such a dispute.

(j) Preservation of prime-subcontractor rights. Except as provided in paragraph (i) of this clause, this clause shall not limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or a subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or nonperformance by a subcontractor.

(k) Non-recourse for prime contractor interest penalty. The Contractor's obligation to pay an interest penalty to a subcontractor pursuant to the clauses included in a subcontract under paragraph (c) of this clause shall not be construed to be an obligation of the Government for such interest penalty. A cost-reimbursement claim may not include any amount for reimbursement of such interest penalty.

(l) Overpayments. If the Contractor becomes aware of a duplicate payment or that the Government has otherwise overpaid on an invoice payment, the Contractor shall immediately notify the Contracting Officer and request instructions for disposition of the overpayment.

(End of clause)

#### 52.233-1 Disputes. (JUL 2002)

(a) This contract is subject to the Contract Disputes Act of 1978, as amended (41 U.S.C. 601-613).

(b) Except as provided in the Act, all disputes arising under or relating to this contract shall be resolved under this clause.

(c) Claim, as used in this clause, means a written demand or written assertion by one of the contracting parties seeking, as a matter of right, the payment of money in a sum certain, the adjustment or interpretation of contract terms, or other relief arising under or relating to this contract. However, a written demand or written assertion by the Contractor seeking the payment of money exceeding \$100,000 is not a claim under the Act until certified. A voucher, invoice, or other routine request for payment that is not in dispute when submitted is not a claim under the Act. The submission may be converted to a claim under the Act, by complying with the submission and certification requirements of this clause, if it is disputed either as to liability or amount or is not acted upon in a reasonable time.

(d)(1) A claim by the Contractor shall be made in writing and, unless otherwise stated in this contract, submitted within 6 years after accrual of the claim to the Contracting Officer for a written decision. A claim by the Government against the Contractor shall be subject to a written decision by the Contracting Officer.

(2)(i) The contractors shall provide the certification specified in subparagraph (d)(2)(iii) of this clause when submitting any claim -

(A) Exceeding \$100,000; or

(B) Regardless of the amount claimed, when using -

(1) Arbitration conducted pursuant to 5 U.S.C. 575-580; or

(2) Any other alternative means of dispute resolution (ADR) technique that the agency elects to handle in accordance with the Administrative Dispute Resolution Act (ADRA).

(ii) The certification requirement does not apply to issues in controversy that have not been submitted as all or part of a claim.

(iii) The certification shall state as follows: "I certify that the claim is made in good faith; that the supporting data are accurate and complete to the best of my knowledge and belief; that the amount requested accurately reflects the contract adjustment for which the Contractor believes the Government is liable; and that I am duly authorized to certify the claim on behalf of the Contractor.

(3) The certification may be executed by any person duly authorized to bind the Contractor with respect to the claim.

(e) For Contractor claims of \$100,000 or less, the Contracting Officer must, if requested in writing by the Contractor, render a decision within 60 days of the request. For Contractor-certified claims over \$100,000, the Contracting Officer must, within 60 days, decide the claim or notify the Contractor of the date by which the decision will be made.

(f) The Contracting Officer's decision shall be final unless the Contractor appeals or files a suit as provided in the Act.

(g) If the claim by the Contractor is submitted to the Contracting Officer or a claim by the Government is presented to the Contractor, the parties, by mutual consent, may agree to use alternative dispute resolution (ADR). If the Contractor refuses an offer for ADR, the Contractor shall inform the Contracting Officer, in writing, of the Contractor's specific reasons for rejecting the request.

(h) The Government shall pay interest on the amount found due and unpaid from (1) the date the Contracting Officer receives the claim (certified, if required); or (2) the date that payment otherwise would be due, if that date is later, until the date of payment. With regard to claims having defective certifications, as defined in (FAR) 48 CFR 33.201, interest shall be paid from the date that the Contracting Officer initially receives the claim. Simple interest on claims shall be paid at the rate, fixed by the Secretary of the Treasury as provided in the Act, which is applicable to the period during which the Contracting Officer receives the claim and then at the rate applicable for each 6-month period as fixed by the Treasury Secretary during the pendency of the claim.

(i) The Contractor shall proceed diligently with performance of this contract, pending final resolution of any request for relief, claim, appeal, or action arising under the contract, and comply with any decision of the Contracting Officer.

(End of clause)

#### 52.233-3 PROTEST AFTER AWARD (AUG. 1996)

(a) Upon receipt of a notice of protest (as defined in FAR 33.101) or a determination that a



protest is likely (see FAR 33.102(d)), the Contracting Officer may, by written order to the Contractor, direct the Contractor to stop performance of the work called for by this contract. The order shall be specifically identified as a stop-work order issued under this clause. Upon receipt of the order, the Contractor shall immediately comply with its terms and take all reasonable steps to minimize the incurrence of costs allocable to the work covered by the order during the period of work stoppage. Upon receipt of the final decision in the protest, the Contracting Officer shall either--

(1) Cancel the stop-work order; or

(2) Terminate the work covered by the order as provided in the Default, or the Termination for Convenience of the Government, clause of this contract.

(b) If a stop-work order issued under this clause is canceled either before or after a final decision in the protest, the Contractor shall resume work. The Contracting Officer shall make an equitable adjustment in the delivery schedule or contract price, or both, and the contract shall be modified, in writing, accordingly, if--

(1) The stop-work order results in an increase in the time required for, or in the Contractor's cost properly allocable to, the performance of any part of this contract; and

(2) The Contractor asserts its right to an adjustment within 30 days after the end of the period of work stoppage; provided, that if the Contracting Officer decides the facts justify the action, the Contracting Officer may receive and act upon a proposal at any time before final payment under this contract.

(c) If a stop-work order is not canceled and the work covered by the order is terminated for the convenience of the Government, the Contracting Officer shall allow reasonable costs resulting from the stop-work order in arriving at the termination settlement.

(d) If a stop-work order is not canceled and the work covered by the order is terminated for default, the Contracting Officer shall allow, by equitable adjustment or otherwise, reasonable costs resulting from the stop-work order.

(e) The Government's rights to terminate this contract at any time are not affected by action taken under this clause.

(f) If, as the result of the Contractor's intentional or negligent misstatement, misrepresentation, or miscertification, a protest related to this contract is sustained, and the Government pays costs, as provided in FAR 33.102(b)(2) or 33.104(h)(1), the Government may require the Contractor to reimburse the Government the amount of such costs. In addition to any other remedy available, and pursuant to the requirements of Subpart 32.6, the Government may collect this debt by offsetting the amount against any payment due the Contractor under any contract between the Contractor and the Government.

(End of clause)

## 52.236-2 DIFFERING SITE CONDITIONS (APR 1984)

As prescribed in 36.502, insert the following clause in solicitations and contracts when a fixed-price construction contract or a fixed-price dismantling, demolition, or removal of improvements contract is contemplated and the contract amount is expected to exceed the small purchase limitation. The Contracting Officer may insert the clause in solicitations and contracts when a fixed-price construction or a fixed-price contract for dismantling, demolition, or removal of improvements is contemplated and the contract amount is expected to be within the small purchase limitation.

(a) The Contractor shall promptly, and before the conditions are disturbed, give a written notice to the Contracting Officer of

(1) subsurface or latent physical conditions at the site which differ materially from those indicated in this contract, or

(2) unknown physical conditions at the site, of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the contract.

(b) The Contracting Officer shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the Contractor's cost of, or the time required for, performing any part of the work under this contract, whether or not changed as a result of the conditions, an equitable adjustment shall be made under this clause and the contract modified in writing accordingly.

(c) No request by the Contractor for an equitable adjustment to the contract under this clause shall be allowed, unless the Contractor has given the written notice required; provided, that the time prescribed in (a) above for giving written notice may be extended by the Contracting Officer.

(d) No request by the Contractor for an equitable adjustment to the contract for differing site conditions shall be allowed if made after final payment under this contract.

(End of clause)

## 52.236-3 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)

(a) The Contractor acknowledges that it has taken steps reasonably necessary to ascertain the nature and location of the work, and that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to

(1) conditions bearing upon transportation, disposal, handling, and storage of materials;

- (2) the availability of labor, water, electric power, and roads;
- (3) uncertainties of weather, river stages, tides, or similar physical conditions at the site;
- (4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Government, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Government.

(b) The Government assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Government. Nor does the Government assume responsibility for any understanding reached or representation made concerning conditions which can affect the work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

(End of clause)

#### 52.236-5 MATERIAL AND WORKMANSHIP (APR 1984)

(a) All equipment, material, and articles incorporated into the work covered by this contract shall be new and of the most suitable grade for the purpose intended, unless otherwise specifically provided in this contract. References in the specifications to equipment, material, articles, or patented processes by trade name, make, or catalog number, shall be regarded as establishing a standard of quality and shall not be construed as limiting competition. The Contractor may, at its option, use any equipment, material, article, or process that, in the judgment of the Contracting Officer, is equal to that named in the specifications, unless otherwise specifically provided in this contract.

(b) The Contractor shall obtain the Contracting Officer's approval of the machinery and mechanical and other equipment to be incorporated into the work. When requesting approval, the Contractor shall furnish to the Contracting Officer the name of the manufacturer, the model number, and other information concerning the performance, capacity, nature, and rating of the machinery and mechanical and other equipment. When required by this contract or by the Contracting Officer, the Contractor shall also obtain the Contracting Officer's approval of the material or articles which the Contractor contemplates incorporating into the work. When requesting approval, the Contractor shall provide full information concerning the material or articles. When directed to do so, the Contractor shall submit samples for approval at the Contractor's expense, with all shipping charges prepaid. Machinery, equipment, material, and articles that do not have the required approval shall be installed or used at the risk of subsequent

rejection.

(c) All work under this contract shall be performed in a skillful and workmanlike manner. The Contracting Officer may require, in writing, that the Contractor remove from the work any employee the Contracting Officer deems incompetent, careless, or otherwise objectionable.

(End of clause)

#### 52.236-6 SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)

At all times during performance of this contract and until the work is completed and accepted, the Contractor shall directly superintend the work or assign and have on the worksite a competent superintendent who is satisfactory to the Contracting Officer and has authority to act for the Contractor.

(End of clause)

#### 52.236-7 PERMITS AND RESPONSIBILITIES (NOV 1991)

The Contractor shall, without additional expense to the Government, be responsible for obtaining any necessary licenses and permits, and for complying with any Federal, State, and municipal laws, codes, and regulations applicable to the performance of the work. The Contractor shall also be responsible for all damages to persons or property that occur as a result of the Contractor's fault or negligence. The Contractor shall also be responsible for all materials delivered and work performed until completion and acceptance of the entire work, except for any completed unit of work which may have been accepted under the contract.

(End of clause)

#### 52.236-8 OTHER CONTRACTS (APR 1984)

The Government may undertake or award other contracts for additional work at or near the site of the work under this contract. The Contractor shall fully cooperate with the other contractors and with Government employees and shall carefully adapt scheduling and performing the work under this contract to accommodate the additional work, heeding any direction that may be provided by the Contracting Officer. The Contractor shall not commit or permit any act that will interfere with the performance of work by any other contractor or by Government employees.

(End of clause)

#### 52.236-9 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984)

(a) The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall

only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the Contracting Officer.

(b) The Contractor shall protect from damage all existing improvements and utilities

(1) at or near the work site, and

(2) on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

(End of clause)

#### 52.236-10 OPERATIONS AND STORAGE AREAS (APR 1984)

(a) The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.

(b) Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with the approval of the Contracting Officer and shall be built with labor and materials furnished by the Contractor without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.

(c) The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

(End of clause)

#### 52.236-11 USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)

(a) The Government shall have the right to take possession of or use any completed or partially

completed part of the work. Before taking possession of or using any work, the Contracting Officer shall furnish the Contractor a list of items of work remaining to be performed or corrected on those portions of the work that the Government intends to take possession of or use. However, failure of the Contracting Officer to list any item of work shall not relieve the Contractor of responsibility for complying with the terms of the contract. The Government's possession or use shall not be deemed an acceptance of any work under the contract.

(b) While the Government has such possession or use, the Contractor shall be relieved of the responsibility for the loss of or damage to the work resulting from the Government's possession or use, notwithstanding the terms of the clause in this contract entitled "Permits and Responsibilities." If prior possession or use by the Government delays the progress of the work or causes additional expense to the Contractor, an equitable adjustment shall be made in the contract price or the time of completion, and the contract shall be modified in writing accordingly.

(End of clause)

#### 52.236-12 CLEANING UP (APR 1984)

The Contractor shall at all times keep the work area, including storage areas, free from accumulations of waste materials. Before completing the work, the Contractor shall remove from the work and premises any rubbish, tools, scaffolding, equipment, and materials that are not the property of the Government. Upon completing the work, the Contractor shall leave the work area in a clean, neat, and orderly condition satisfactory to the Contracting Officer.

(End of clause)

#### 52.236-13 ACCIDENT PREVENTION (NOV 1991)

(a) The Contractor shall provide and maintain work environments and procedures which will

(1) safeguard the public and Government personnel, property, materials, supplies, and equipment exposed to Contractor operations and activities;

(2) avoid interruptions of Government operations and delays in project completion dates; and

(3) control costs in the performance of this contract.

(b) For these purposes on contracts for construction or dismantling, demolition, or removal of improvements, the Contractor shall-

(1) Provide appropriate safety barricades, signs, and signal lights;

(2) Comply with the standards issued by the Secretary of Labor at 29 CFR Part 1926 and 29 CFR Part 1910; and

(3) Ensure that any additional measures the Contracting Officer determines to be reasonably necessary for the purposes are taken.

(c) If this contract is for construction or dismantling, demolition or removal of improvements with any Department of Defense agency or component, the Contractor shall comply with all pertinent provisions of the latest version of U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, in effect on the date of the solicitation.

(d) Whenever the Contracting Officer becomes aware of any noncompliance with these requirements or any condition which poses a serious or imminent danger to the health or safety of the public or Government personnel, the Contracting Officer shall notify the Contractor orally, with written confirmation, and request immediate initiation of corrective action. This notice, when delivered to the Contractor or the Contractor's representative at the work site, shall be deemed sufficient notice of the noncompliance and that corrective action is required. After receiving the notice, the Contractor shall immediately take corrective action. If the Contractor fails or refuses to promptly take corrective action, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall not be entitled to any equitable adjustment of the contract price or extension of the performance schedule on any stop work order issued under this clause.

(e) The Contractor shall insert this clause, including this paragraph (e), with appropriate changes in the designation of the parties, in subcontracts.

(End of clause)

#### 52.236-15 SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)

(a) The Contractor shall, within five days after the work commences on the contract or another period of time determined by the Contracting Officer, prepare and submit to the Contracting Officer for approval three copies of a practicable schedule showing the order in which the Contractor proposes to perform the work, and the dates on which the Contractor contemplates starting and completing the several salient features of the work (including acquiring materials, plant, and equipment). The schedule shall be in the form of a progress chart of suitable scale to indicate appropriately the percentage of work scheduled for completion by any given date during the period. If the Contractor fails to submit a schedule within the time prescribed, the Contracting Officer may withhold approval of progress payments until the Contractor submits the required schedule.

(b) The Contractor shall enter the actual progress on the chart as directed by the Contracting Officer, and upon doing so shall immediately deliver three copies of the annotated schedule to the Contracting Officer. If, in the opinion of the Contracting Officer, the Contractor falls behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer, without additional cost to the Government. In this circumstance, the Contracting Officer may require the Contractor to increase the number of shifts, overtime operations, days of work, and/or the amount of construction plant, and to submit for approval any supplementary schedule or schedules in chart form as the

Contracting Officer deems necessary to demonstrate how the approved rate of progress will be regained.

(c) Failure of the Contractor to comply with the requirements of the Contracting Officer under this clause shall be grounds for a determination by the Contracting Officer that the Contractor is not prosecuting the work with sufficient diligence to ensure completion within the time specified in the contract. Upon making this determination, the Contracting Officer may terminate the Contractor's right to proceed with the work, or any separable part of it, in accordance with the default terms of this contract.

(End of clause)

#### 52.236-17 LAYOUT OF WORK (APR 1984)

The Contractor shall lay out its work from Government established base lines and bench marks indicated on the drawings, and shall be responsible for all measurements in connection with the layout. The Contractor shall furnish, at its own expense, all stakes, templates, platforms, equipment, tools, materials, and labor required to lay out any part of the work. The Contractor shall be responsible for executing the work to the lines and grades that may be established or indicated by the Contracting Officer. The Contractor shall also be responsible for maintaining and preserving all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through its negligence before their removal is authorized, the Contracting Officer may replace them and deduct the expense of the replacement from any amounts due or to become due to the Contractor.

(End of clause)

#### 52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or "acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.



(c) Where "as shown," as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

(End of clause)

#### 52.236-26 PRECONSTRUCTION CONFERENCE (FEB 1995)

If the Contracting Officer decides to conduct a preconstruction conference, the successful offeror will be notified and will be required to attend. The Contracting Officer's notification will include specific details regarding the date, time, and location of the conference, any need for attendance by subcontractors, and information regarding the items to be discussed.

(End of clause)

## 52.242-13 BANKRUPTCY (JUL 1995)

In the event the Contractor enters into proceedings relating to bankruptcy, whether voluntary or involuntary, the Contractor agrees to furnish, by certified mail or electronic commerce method authorized by the contract, written notification of the bankruptcy to the Contracting Officer responsible for administering the contract. This notification shall be furnished within five days of the initiation of the proceedings relating to bankruptcy filing. This notification shall include the date on which the bankruptcy petition was filed, the identity of the court in which the bankruptcy petition was filed, and a listing of Government contract numbers and contracting offices for all Government contracts against which final payment has not been made. This obligation remains in effect until final payment under this contract.

(End of clause)

## 52.242-14 SUSPENSION OF WORK (APR 1984)

(a) The Contracting Officer may order the Contractor, in writing, to suspend, delay, or interrupt all or any part of the work of this contract for the period of time that the Contracting Officer determines appropriate for the convenience of the Government.

(b) If the performance of all or any part of the work is, for an unreasonable period of time, suspended, delayed, or interrupted (1) by an act of the Contracting Officer in the administration of this contract, or (2) by the Contracting Officer's failure to act within the time specified in this contract (or within a reasonable time if not specified), an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) necessarily caused by the unreasonable suspension, delay, or interruption, and the contract modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay, or interruption to the extent that performance would have been so suspended, delayed, or interrupted by any other cause, including the fault or negligence of the Contractor, or for which an equitable adjustment is provided for or excluded under any other term or condition of this contract. (c) A claim under this clause shall not be allowed (1) for any costs incurred more than 20 days before the Contractor shall have notified the Contracting Officer in writing of the act or failure to act involved (but this requirement shall not apply as to a claim resulting from a suspension order), and (2) unless the claim, in an amount stated, is asserted in writing as soon as practicable after the termination of the suspension, delay, or interruption, but not later than the date of final payment under the contract.

(End of clause)

## 52.243-3 CHANGES--TIME-AND-MATERIALS OR LABOR-HOURS (SEP 2000)

(a) The Contracting Officer may at any time, by written order, and without notice to the sureties, if any, make changes within the general scope of this contract in any one or more of the following:

- (1) Description of services to be performed.
  - (2) Time of performance (i.e., hours of the day, days of the week, etc.).
  - (3) Place of performance of the services.
  - (4) Drawings, designs, or specifications when the supplies to be furnished are to be specially manufactured for the Government in accordance with the drawings, designs, or specifications.
  - (5) Method of shipment or packing of supplies.
  - (6) Place of delivery.
  - (7) Amount of Government-furnished property.
- (b) If any change causes an increase or decrease in any hourly rate, the ceiling price, or the time required for performance of any part of the work under this contract, whether or not changed by the order, or otherwise affects any other terms and conditions of this contract, the Contracting Officer will make an equitable adjustment in any one or more of the following and will modify the contract accordingly:
- (1) Ceiling price.
  - (2) Hourly rates.
  - (3) Delivery schedule.
  - (4) Other affected terms.
- (c) The Contractor shall assert its right to an adjustment under this clause within 30 days from the date of receipt of the written order. However, if the Contracting Officer decides that the facts justify it, the Contracting Officer may receive and act upon a proposal submitted before final payment of the contract.
- (d) Failure to agree to any adjustment will be a dispute under the Disputes clause. However, nothing in this clause excuses the Contractor from proceeding with the contract as changed.
- (End of clause)

#### 52.246-12 INSPECTION OF CONSTRUCTION (AUG 1996)

- (a) Definition. "Work" includes, but is not limited to, materials, workmanship, and manufacture and fabrication of components.
- (b) The Contractor shall maintain an adequate inspection system and perform such inspections as will ensure that the work performed under the contract conforms to contract requirements. The

Contractor shall maintain complete inspection records and make them available to the Government. All work shall be conducted under the general direction of the Contracting Officer and is subject to Government inspection and test at all places and at all reasonable times before acceptance to ensure strict compliance with the terms of the contract.

(c) Government inspections and tests are for the sole benefit of the Government and do not--

(1) Relieve the Contractor of responsibility for providing adequate quality control measures;

(2) Relieve the Contractor of responsibility for damage to or loss of the material before acceptance;

(3) Constitute or imply acceptance; or

(4) Affect the continuing rights of the Government after acceptance of the completed work under paragraph (i) of this section.

(d) The presence or absence of a Government inspector does not relieve the Contractor from any contract requirement, nor is the inspector authorized to change any term or condition of the specification without the Contracting Officer's written authorization.

(e) The Contractor shall promptly furnish, at no increase in contract price, all facilities, labor, and material reasonably needed for performing such safe and convenient inspections and tests as may be required by the Contracting Officer. The Government may charge to the Contractor any additional cost of inspection or test when work is not ready at the time specified by the Contractor for inspection or test, or when prior rejection makes reinspection or retest necessary. The Government shall perform all inspections and tests in a manner that will not unnecessarily delay the work. Special, full size, and performance tests shall be performed as described in the contract.

(f) The Contractor shall, without charge, replace or correct work found by the Government not to conform to contract requirements, unless in the public interest the Government consents to accept the work with an appropriate adjustment in contract price. The Contractor shall promptly segregate and remove rejected material from the premises.

(g) If the Contractor does not promptly replace or correct rejected work, the Government may (1) by contract or otherwise, replace or correct the work and charge the cost to the Contractor or (2) terminate for default the Contractor's right to proceed.

(h) If, before acceptance of the entire work, the Government decides to examine already completed work by removing it or tearing it out, the Contractor, on request, shall promptly furnish all necessary facilities, labor, and material. If the work is found to be defective or nonconforming in any material respect due to the fault of the Contractor or its subcontractors, the Contractor shall defray the expenses of the examination and of satisfactory reconstruction. However, if the work is found to meet contract requirements, the Contracting Officer shall make an equitable adjustment for the additional services involved in the examination and

reconstruction, including, if completion of the work was thereby delayed, an extension of time.

(i) Unless otherwise specified in the contract, the Government shall accept, as promptly as practicable after completion and inspection, all work required by the contract or that portion of the work the Contracting Officer determines can be accepted separately. Acceptance shall be final and conclusive except for latent defects, fraud, gross mistakes amounting to fraud, or the Government's rights under any warranty or guarantee.

(End of clause)

#### 52.246-21 WARRANTY OF CONSTRUCTION (MAR 1994)

(a) In addition to any other warranties in this contract, the Contractor warrants, except as provided in paragraph (i) of this clause, that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, or design furnished, or workmanship performed by the Contractor or any subcontractor or supplier at any tier.

(b) This warranty shall continue for a period of 1 year from the date of final acceptance of the work. If the Government takes possession of any part of the work before final acceptance, this warranty shall continue for a period of 1 year from the date the Government takes possession.

(c) The Contractor shall remedy at the Contractor's expense any failure to conform, or any defect. In addition, the Contractor shall remedy at the Contractor's expense any damage to Government-owned or controlled real or personal property, when that damage is the result of--

(1) The Contractor's failure to conform to contract requirements; or

(2) Any defect of equipment, material, workmanship, or design furnished.

(d) The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for 1 year from the date of repair or replacement.

(e) The Contracting Officer shall notify the Contractor, in writing, within a reasonable time after the discovery of any failure, defect, or damage.

(f) If the Contractor fails to remedy any failure, defect, or damage within a reasonable time after receipt of notice, the Government shall have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.

(g) With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall--

(1) Obtain all warranties that would be given in normal commercial practice;

(2) Require all warranties to be executed, in writing, for the benefit of the Government, if directed by the Contracting Officer; and

(3) Enforce all warranties for the benefit of the Government, if directed by the Contracting Officer.

(h) In the event the Contractor's warranty under paragraph (b) of this clause has expired, the Government may bring suit at its expense to enforce a subcontractor's, manufacturer's, or supplier's warranty.

(i) Unless a defect is caused by the negligence of the Contractor or subcontractor or supplier at any tier, the Contractor shall not be liable for the repair of any defects of material or design furnished by the Government nor for the repair of any damage that results from any defect in Government-furnished material or design.

(j) This warranty shall not limit the Government's rights under the Inspection and Acceptance clause of this contract with respect to latent defects, gross mistakes, or fraud.

(End of clause)

#### 52.248-3 VALUE ENGINEERING--CONSTRUCTION (FEB 2000)

(a) General. The Contractor is encouraged to develop, prepare, and submit value engineering change proposals (VECP's) voluntarily. The Contractor shall share in any instant contract savings realized from accepted VECP's, in accordance with paragraph (f) below.

(b) Definitions. "Collateral costs," as used in this clause, means agency costs of operation, maintenance, logistic support, or Government-furnished property.

"Collateral savings," as used in this clause, means those measurable net reductions resulting from a VECP in the agency's overall projected collateral costs, exclusive of acquisition savings, whether or not the acquisition cost changes.

"Contractor's development and implementation costs," as used in this clause, means those costs the Contractor incurs on a VECP specifically in developing, testing, preparing, and submitting the VECP, as well as those costs the Contractor incurs to make the contractual changes required by Government acceptance of a VECP.

"Government costs," as used in this clause, means those agency costs that result directly from developing and implementing the VECP, such as any net increases in the cost of testing, operations, maintenance, and logistic support. The term does not include the normal administrative costs of processing the VECP.

"Instant contract savings," as used in this clause, means the estimated reduction in Contractor cost of performance resulting from acceptance of the VECP, minus allowable Contractor's development and implementation costs, including subcontractors' development and implementation costs (see paragraph (h) below).

"Value engineering change proposal (VECP)" means a proposal that--

- (1) Requires a change to this, the instant contract, to implement; and
- (2) Results in reducing the contract price or estimated cost without impairing essential functions or characteristics; provided, that it does not involve a change--

- (i) In deliverable end item quantities only; or

- (ii) To the contract type only.

(c) VECP preparation. As a minimum, the Contractor shall include in each VECP the information described in subparagraphs (1) through (7) below. If the proposed change is affected by contractually required configuration management or similar procedures, the instructions in those procedures relating to format, identification, and priority assignment shall govern VECP preparation. The VECP shall include the following:

- (1) A description of the difference between the existing contract requirement and that proposed, the comparative advantages and disadvantages of each, a justification when an item's function or characteristics are being altered, and the effect of the change on the end item's performance.

- (2) A list and analysis of the contract requirements that must be changed if the VECP is accepted, including any suggested specification revisions.

- (3) A separate, detailed cost estimate for

- (i) the affected portions of the existing contract requirement and

- (ii) the VECP. The cost reduction associated with the VECP shall take into account the Contractor's allowable development and implementation costs, including any amount attributable to subcontracts under paragraph (h) below.

- (4) A description and estimate of costs the Government may incur in implementing the VECP, such as test and evaluation and operating and support costs.

- (5) A prediction of any effects the proposed change would have on collateral costs to the agency.

- (6) A statement of the time by which a contract modification accepting the VECP must be issued in order to achieve the maximum cost reduction, noting any effect on the contract completion time or delivery schedule.

- (7) Identification of any previous submissions of the VECP, including the dates submitted, the agencies and contract numbers involved, and previous Government actions, if known.

(d) Submission. The Contractor shall submit VECP's to the Resident Engineer at the worksite, with a copy to the Contracting Officer.

(e) Government action.

(1) The Contracting Officer will notify the Contractor of the status of the VECP within 45 calendar days after the contracting office receives it. If additional time is required, the Contracting Officer will notify the Contractor within the 45-day period and provide the reason for the delay and the expected date of the decision. The Government will process VECP's expeditiously; however, it shall not be liable for any delay in acting upon a VECP.

If the VECP is not accepted, the Contracting Officer will notify the Contractor in writing, explaining the reasons for rejection. The Contractor may withdraw any VECP, in whole or in part, at any time before it is accepted by the Government. The Contracting Officer may require that the Contractor provide written notification before undertaking significant expenditures for VECP effort.

Any VECP may be accepted, in whole or in part, by the Contracting Officer's award of a modification to this contract citing this clause. The Contracting Officer may accept the VECP, even though an agreement on price reduction has not been reached, by issuing the Contractor a notice to proceed with the change. Until a notice to proceed is issued or a contract modification applies a VECP to this contract, the Contractor shall perform in accordance with the existing contract. The decision to accept or reject all or part of any VECP is a unilateral decision made solely at the discretion of the Contracting Officer.

(f) Sharing.

(1) Rates. The Government's share of savings is determined by subtracting Government costs from instant contract savings and multiplying the result by

(i) 45 percent for fixed-price contracts or

(ii) 75 percent for cost-reimbursement contracts.

(2) Payment. Payment of any share due the Contractor for use of a VECP on this contract shall be authorized by a modification to this contract to--

(i) Accept the VECP;

(ii) Reduce the contract price or estimated cost by the amount of instant contract savings; and

(iii) Provide the Contractor's share of savings by adding the amount calculated to the contract price or fee.

(g) Collateral savings. If a VECP is accepted, the Contracting Officer will increase the instant contract amount by 20 percent of any projected collateral savings determined to be realized in a typical year of use after subtracting any Government costs not previously offset. However, the Contractor's share of collateral savings will not exceed the contract's firm-fixed-price or



estimated cost, at the time the VECP is accepted, or \$100,000, whichever is greater. The Contracting Officer is the sole determiner of the amount of collateral savings.

(h) Subcontracts. The Contractor shall include an appropriate value engineering clause in any subcontract of \$50,000 or more and may include one in subcontracts of lesser value. In computing any adjustment in this contract's price under paragraph (f) above, the Contractor's allowable development and implementation costs shall include any subcontractor's allowable development and implementation costs clearly resulting from a VECP accepted by the Government under this contract, but shall exclude any value engineering incentive payments to a subcontractor. The Contractor may choose any arrangement for subcontractor value engineering incentive payments; provided, that these payments shall not reduce the Government's share of the savings resulting from the VECP.

(i) Data. The Contractor may restrict the Government's right to use any part of a VECP or the supporting data by marking the following legend on the affected parts:

"These data, furnished under the Value Engineering-- Construction clause of contract . . . . . , shall not be disclosed outside the Government or duplicated, used, or disclosed, in whole or in part, for any purpose other than to evaluate a value engineering change proposal submitted under the clause. This restriction does not limit the Government's right to use information contained in these data if it has been obtained or is otherwise available from the Contractor or from another source without limitations." If a VECP is accepted, the Contractor hereby grants the Government unlimited rights in the VECP and supporting data, except that, with respect to data qualifying and submitted as limited rights technical data, the Government shall have the rights specified in the contract modification implementing the VECP and shall appropriately mark the data. (The terms "unlimited rights" and "limited rights" are defined in Part 27 of the Federal Acquisition Regulation.)

(End of clause)

#### 52.249-2 TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (SEP 1996)

(a) The Government may terminate performance of work under this contract in whole or, from time to time, in part if the Contracting Officer determines that a termination is in the Government's interest. The Contracting Officer shall terminate by delivering to the Contractor a Notice of Termination specifying the extent of termination and the effective date.

(b) After receipt of a Notice of Termination, and except as directed by the Contracting Officer, the Contractor shall immediately proceed with the following obligations, regardless of any delay in determining or adjusting any amounts due under this clause:

(1) Stop work as specified in the notice.

- (2) Place no further subcontracts or orders (referred to as subcontracts in this clause) for materials, services, or facilities, except as necessary to complete the continued portion of the contract.
- (3) Terminate all subcontracts to the extent they relate to the work terminated.
- (4) Assign to the Government, as directed by the Contracting Officer, all right, title, and interest of the Contractor under the subcontracts terminated, in which case the Government shall have the right to settle or to pay any termination settlement proposal arising out of those terminations.
- (5) With approval or ratification to the extent required by the Contracting Officer, settle all outstanding liabilities and termination settlement proposals arising from the termination of subcontracts; the approval or ratification will be final for purposes of this clause.
- (6) As directed by the Contracting Officer, transfer title and deliver to the Government (i) the fabricated or unfabricated parts, work in process, completed work, supplies, and other material produced or acquired for the work terminated, and (ii) the completed or partially completed plans, drawings, information, and other property that, if the contract had been completed, would be required to be furnished to the Government.
- (7) Complete performance of the work not terminated.
- (8) Take any action that may be necessary, or that the Contracting Officer may direct, for the protection and preservation of the property related to this contract that is in the possession of the Contractor and in which the Government has or may acquire an interest.
- (9) Use its best efforts to sell, as directed or authorized by the Contracting Officer, any property of the types referred to in subparagraph (b)(6) of this clause; provided, however, that the Contractor (i) is not required to extend credit to any purchaser and (ii) may acquire the property under the conditions prescribed by, and at prices approved by, the Contracting Officer. The proceeds of any transfer or disposition will be applied to reduce any payments to be made by the Government under this contract, credited to the price or cost of the work, or paid in any other manner directed by the Contracting Officer.
- (c) The Contractor shall submit complete termination inventory schedules no later than 120 days from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 120-day period.
- (d) After expiration of the plant clearance period as defined in Subpart 45.6 of the Federal Acquisition Regulation, the Contractor may submit to the Contracting Officer a list, certified as to quantity and quality, of termination inventory not previously disposed of, excluding items authorized for disposition by the Contracting Officer. The Contractor may request the Government to remove those items or enter into an agreement for their storage. Within 15 days, the Government will accept title to those items and remove them or enter into a storage agreement. The Contracting Officer may verify the list upon removal of the items, or if stored,

within 45 days from submission of the list, and shall correct the list, as necessary, before final settlement.

(e) After termination, the Contractor shall submit a final termination settlement proposal to the Contracting Officer in the form and with the certification prescribed by the Contracting Officer. The Contractor shall submit the proposal promptly, but no later than 1 year from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 1-year period. However, if the Contracting Officer determines that the facts justify it, a termination settlement proposal may be received and acted on after 1 year or any extension. If the Contractor fails to submit the proposal within the time allowed, the Contracting Officer may determine, on the basis of information available, the amount, if any, due the Contractor because of the termination and shall pay the amount determined.

(f) Subject to paragraph (e) of this clause, the Contractor and the Contracting Officer may agree upon the whole or any part of the amount to be paid or remaining to be paid because of the termination. The amount may include a reasonable allowance for profit on work done. However, the agreed amount, whether under this paragraph (g) or paragraph (g) of this clause, exclusive of costs shown in subparagraph (g)(3) of this clause, may not exceed the total contract price as reduced by (1) the amount of payments previously made and (2) the contract price of work not terminated. The contract shall be modified, and the Contractor paid the agreed amount. Paragraph (g) of this clause shall not limit, restrict, or affect the amount that may be agreed upon to be paid under this paragraph.

(g) If the Contractor and the Contracting Officer fail to agree on the whole amount to be paid because of the termination of work, the Contracting Officer shall pay the Contractor the amounts determined by the Contracting Officer as follows, but without duplication of any amounts agreed on under paragraph (f) of this clause:

(1) The contract price for completed supplies or services accepted by the Government (or sold or acquired under subparagraph (b)(9) of this clause) not previously paid for, adjusted for any saving of freight and other charges.

(2) The total of--

(i) The costs incurred in the performance of the work terminated, including initial costs and preparatory expense allocable thereto, but excluding any costs attributable to supplies or services paid or to be paid under subparagraph (f)(1) of this clause;

(ii) The cost of settling and paying termination settlement proposals under terminated subcontracts that are properly chargeable to the terminated portion of the contract if not included in subdivision (g)(2)(i) of this clause; and

(iii) A sum, as profit on subdivision (g)(2)(i) of this clause, determined by the Contracting Officer under 49.202 of the Federal Acquisition Regulation, in effect on the date of this contract, to be fair and reasonable; however, if it appears that the Contractor would have sustained a loss

on the entire contract had it been completed, the Contracting Officer shall allow no profit under this subdivision (iii) and shall reduce the settlement to reflect the indicated rate of loss.

(3) The reasonable costs of settlement of the work terminated, including--

(i) Accounting, legal, clerical, and other expenses reasonably necessary for the preparation of termination settlement proposals and supporting data;

(ii) The termination and settlement of subcontracts (excluding the amounts of such settlements); and

(iii) Storage, transportation, and other costs incurred, reasonably necessary for the preservation, protection, or disposition of the termination inventory.

(h) Except for normal spoilage, and except to the extent that the Government expressly assumed the risk of loss, the Contracting Officer shall exclude from the amounts payable to the Contractor under paragraph (g) of this clause, the fair value, as determined by the Contracting Officer, of property that is destroyed, lost, stolen, or damaged so as to become undeliverable to the Government or to a buyer.

(i) The cost principles and procedures of Part 31 of the Federal Acquisition Regulation, in effect on the date of this contract, shall govern all costs claimed, agreed to, or determined under this clause.

(j) The Contractor shall have the right of appeal, under the Disputes clause, from any determination made by the Contracting Officer under paragraph (e), (g), or (l) of this clause, except that if the Contractor failed to submit the termination settlement proposal or request for equitable adjustment within the time provided in paragraph (e) or (l), respectively, and failed to request a time extension, there is no right of appeal.

(k) In arriving at the amount due the Contractor under this clause, there shall be deducted--

(1) All unliquidated advance or other payments to the Contractor under the terminated portion of this contract;

(2) Any claim which the Government has against the Contractor under this contract; and

(3) The agreed price for, or the proceeds of sale of, materials, supplies, or other things acquired by the Contractor or sold under the provisions of this clause and not recovered by or credited to the Government.

(l) If the termination is partial, the Contractor may file a proposal with the Contracting Officer for an equitable adjustment of the price(s) of the continued portion of the contract. The Contracting Officer shall make any equitable adjustment agreed upon. Any proposal by the Contractor for an equitable adjustment under this clause shall be requested within 90 days from the effective date of termination unless extended in writing by the Contracting Officer.

(m)(1) The Government may, under the terms and conditions it prescribes, make partial payments and payments against costs incurred by the Contractor for the terminated portion of the contract, if the Contracting Officer believes the total of these payments will not exceed the amount to which the Contractor will be entitled.

(2) If the total payments exceed the amount finally determined to be due, the Contractor shall repay the excess to the Government upon demand, together with interest computed at the rate established by the Secretary of the Treasury under 50 U.S.C. App. 1215(b)(2). Interest shall be computed for the period from the date the excess payment is received by the Contractor to the date the excess is repaid. Interest shall not be charged on any excess payment due to a reduction in the Contractor's termination settlement proposal because of retention or other disposition of termination inventory until 10 days after the date of the retention or disposition, or a later date determined by the Contracting Officer because of the circumstances.

(n) Unless otherwise provided in this contract or by statute, the Contractor shall maintain all records and documents relating to the terminated portion of this contract for 3 years after final settlement. This includes all books and other evidence bearing on the Contractor's costs and expenses under this contract. The Contractor shall make these records and documents available to the Government, at the Contractor's office, at all reasonable times, without any direct charge. If approved by the Contracting Officer, photographs, microphotographs, or other authentic reproductions may be maintained instead of original records and documents.

(End of clause)

#### 52.249-10 DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)

(a) If the Contractor refuses or fails to prosecute the work or any separable part, with the diligence that will insure its completion within the time specified in this contract including any extension, or fails to complete the work within this time, the Government may, by written notice to the Contractor, terminate the right to proceed with the work (or the separable part of the work) that has been delayed. In this event, the Government may take over the work and complete it by contract or otherwise, and may take possession of and use any materials, appliances, and plant on the work site necessary for completing the work. The Contractor and its sureties shall be liable for any damage to the Government resulting from the Contractor's refusal or failure to complete the work within the specified time, whether or not the Contractor's right to proceed with the work is terminated. This liability includes any increased costs incurred by the Government in completing the work.

(b) The Contractor's right to proceed shall not be terminated nor the Contractor charged with damages under this clause, if--

(1) The delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such causes include

(i) acts of God or of the public enemy,

- (ii) acts of the Government in either its sovereign or contractual capacity,
- (iii) acts of another Contractor in the performance of a contract with the Government,
- (iv) fires,
- (v) floods,
- (vi) epidemics,
- (vii) quarantine restrictions,
- (viii) strikes,
- (ix) freight embargoes,
- (x) unusually severe weather, or delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Contractor and the subcontractors or suppliers; and

(2) The Contractor, within 10 days from the beginning of any delay (unless extended by the Contracting Officer), notifies the Contracting Officer in writing of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If, in the judgment of the Contracting Officer, the findings of fact warrant such action, the time for completing the work shall be extended. The findings of the Contracting Officer shall be final and conclusive on the parties, but subject to appeal under the Disputes clause.

(c) If, after termination of the Contractor's right to proceed, it is determined that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the termination had been issued for the convenience of the Government.

The rights and remedies of the Government in this clause are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

#### 52.252-2 CLAUSES INCORPORATED BY REFERENCE (FEB 1998)

This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):

<http://www.arnet.gov/far/>

(End of clause)

#### 52.252-4 ALTERATIONS IN CONTRACT (APR 1984)

Portions of this contract are altered as follows:

(End of clause)

#### 52.252-6 AUTHORIZED DEVIATIONS IN CLAUSES (APR 1984)

(a) The use in this solicitation or contract of any Federal Acquisition Regulation (48 CFR Chapter 1) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the clause.

(f) The use in this solicitation or contract of any \_\_\_\_\_ (48 CFR \_\_\_\_\_) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

#### 52.253-1 COMPUTER GENERATED FORMS (JAN 1991)

(a) Any data required to be submitted on a Standard or Optional Form prescribed by the Federal Acquisition Regulation (FAR) may be submitted on a computer generated version of the form, provided there is no change to the name, content, or sequence of the data elements on the form, and provided the form carries the Standard or Optional Form number and edition date.

(b) Unless prohibited by agency regulations, any data required to be submitted on an agency unique form prescribed by an agency supplement to the FAR may be submitted on a computer generated version of the form provided there is no change to the name, content, or sequence of the data elements on the form and provided the form carries the agency form number and edition date.

(g) If the Contractor submits a computer generated version of a form that is different than the required form, then the rights and obligations of the parties will be determined based on the content of the required form.

(End of clause)

#### 252.201-7000 CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991)

(a) "Definition. Contracting officer's representative" means an individual designated in accordance with subsection 201.602-2 of the Defense Federal Acquisition Regulation Supplement and authorized in writing by the contracting officer to perform specific technical or administrative functions.

(b) If the Contracting Officer designates a contracting officer's representative (COR), the Contractor will receive a copy of the written designation. It will specify the extent of the COR's

authority to act on behalf of the contracting officer. The COR is not authorized to make any commitments or changes that will affect price, quality, quantity, delivery, or any other term or condition of the contract.

(End of clause)

252.203-7001 PROHIBITION ON PERSONS CONVICTED OF FRAUD OR OTHER DEFENSE-CONTRACT-RELATED FELONIES (MAR 1999)

(a) Definitions. As used in this clause—

(1) “Arising out of a contract with the DoD” means any act in connection with—

(i) Attempting to obtain;

(ii) Obtaining, or

(iii) Performing a contract or first-tier subcontract of any agency, department, or component of the Department of Defense (DoD).

(2) “Conviction of fraud or any other felony” means any conviction for fraud or a felony in violation of state or Federal criminal statutes, whether entered on a verdict or plea, including a plea of *nolo contendere*, for which sentence has been imposed.

(3) “Date of conviction” means the date judgment was entered against the individual.

(b) Any individual who is convicted after September 29, 1988, of fraud or any other felony arising out of a contract with the DoD is prohibited from serving--

(1) In a management or supervisory capacity on any DoD contract or first-tier subcontract;

(2) On the board of directors of any DoD contractor or first-tier subcontractor;

(3) As a consultant, agent, or representative for any DoD contractor or first-tier subcontractor; or

(4) In any other capacity with the authority to influence, advise, or control the decisions of any DoD contractor or subcontractor with regard to any DoD contract or first-tier subcontract.

(c) Unless waived, the prohibition in paragraph (b) of this clause applies for not less than 5 years from the date of conviction.

(d) 10 U.S.C. 2408 provides that a defense contractor or first-tier subcontractor shall be subject to a criminal penalty of not more than \$500,000 if convicted of knowingly—

(1) Employing a person under a prohibition specified in paragraph (b) of this clause; or

(2) Allowing such a person to serve on the board of directors of the contractor or first-tier subcontractor.



(e) In addition to the criminal penalties contained in 10 U.S.C. 2408, the Government may consider other available remedies, such as—

- (1) Suspension or debarment;
- (2) Cancellation of the contract at no cost to the Government; or
- (3) Termination of the contract for default.

(f) The Contractor may submit written requests for waiver of the prohibition in paragraph (b) of this clause to the Contracting Officer. Requests shall clearly identify—

- (1) The person involved;
- (2) The nature of the conviction and resultant sentence or punishment imposed;
- (3) The reasons for the requested waiver; and
- (4) An explanation of why a waiver is in the interest of national security.

(g) The Contractor agrees to include the substance of this clause, appropriately modified to reflect the identity and relationship of the parties, in all first-tier subcontracts exceeding the simplified acquisition threshold in Part 2 of the Federal Acquisition Regulation, except those for commercial items or components.

(h) Pursuant to 10 U.S.C. 2408(c), defense contractors and subcontractors may obtain information as to whether a particular person has been convicted of fraud or any other felony arising out of a contract with the DoD by contacting The Office of Justice Programs, The Denial of Federal Benefits Office, U.S. Department of Justice, telephone (202) 616-3507.

(End of clause)

#### 252.203-7002 DISPLAY OF DOD HOTLINE POSTER (DEC 1991)

(a) The Contractor shall display prominently in common work areas within business segments performing work under Department of Defense (DoD) contracts, DoD Hotline Posters prepared by the DoD Office of the Inspector General.

(b) DoD Hotline Posters may be obtained from the DoD Inspector General, ATTN: Defense Hotline, 400 Army Navy Drive, Washington, DC 22202-2884.

(h) The Contractor need not comply with paragraph (a) of this clause if it has established a mechanism, such as a hotline, by which employees may report suspected instances of improper conduct, and instructions that encourage employees to make such reports.

(End of clause)

#### 252.204-7000 DISCLOSURE OF INFORMATION (DEC 1991)

(a) The Contractor shall not release to anyone outside the Contractor's organization any unclassified information, regardless of medium (e.g., film, tape, document), pertaining to any part of this contract or any program related to this contract, unless--

(1) The Contracting Officer has given prior written approval; or

(2) The information is otherwise in the public domain before the date of release.

(b) Requests for approval shall identify the specific information to be released, the medium to be used, and the purpose for the release. The Contractor shall submit its request to the Contracting Officer at least 45 days before the proposed date for release.

(c) The Contractor agrees to include a similar requirement in each subcontract under this contract. Subcontractors shall submit requests for authorization to release through the prime contractor to the Contracting Officer.

(End of clause)

252.204-7003 CONTROL OF GOVERNMENT PERSONNEL WORK PRODUCT (APR 1992)

The Contractor's procedures for protecting against unauthorized disclosure of information shall not require Department of Defense employees or members of the Armed Forces to relinquish control of their work products, whether classified or not, to the contractor.

(End of clause)

252.205-7000 PROVISION OF INFORMATION TO COOPERATIVE AGREEMENT HOLDERS (DEC 1991)

(a) Definition.

"Cooperative agreement holder" means a State or local government; a private, nonprofit organization; a tribal organization (as defined in section 4(c) of the Indian Self-Determination and Education Assistance Act (Pub. L. 93-268; 25 U.S.C. 450 (c))); or an economic enterprise (as defined in section 3(e) of the Indian Financing Act of 1974 (Pub. L. 93-362; 25 U.S.C. 1452(e))) whether such economic enterprise is organized for profit or nonprofit purposes; which has an agreement with the Defense Logistics Agency to furnish procurement technical assistance to business entities.

(b) The Contractor shall provide cooperative agreement holders, upon their request, with a list of those appropriate employees or offices responsible for entering into subcontracts under defense contracts. The list shall include the business address, telephone number, and area of responsibility of each employee or office.

(c) The Contractor need not provide the listing to a particular cooperative agreement holder more frequently than once a year.

(End of clause)

252.209-7000 ACQUISITION FROM SUBCONTRACTORS SUBJECT TO ONSITE INSPECTION UNDER THE INTERMEDIATE-RANGE NUCLEAR FORCES (INF) TREATY (NOV 1995)

(a) The Contractor shall not deny consideration for a subcontract award under this contract to a potential subcontractor subject to on-site inspection under the INF Treaty, or a similar treaty, solely or in part because of the actual or potential presence of Soviet inspectors at the subcontractor's facility, unless the decision is approved by the Contracting Officer.

(b) The Contractor shall incorporate this clause, including this paragraph (b), in all solicitations and contracts exceeding the simplified acquisition threshold in part 13 of the Federal Acquisition Regulation, except those for commercial items.

(End of clause)

252.223-7004 DRUG-FREE WORK FORCE (SEP 1988)

(a) Definitions.

(1) "Employee in a sensitive position," as used in this clause, means an employee who has been granted access to classified information; or employees in other positions that the Contractor determines involve national security; health or safety, or functions other than the foregoing requiring a high degree of trust and confidence.

(2) "Illegal drugs," as used in this clause, means controlled substances included in Schedules I and II, as defined by section 802(6) of title 21 of the United States Code, the possession of which is unlawful under chapter 13 of that Title. The term "illegal drugs" does not mean the use of a controlled substance pursuant to a valid prescription or other uses authorized by law.

(b) The Contractor agrees to institute and maintain a program for achieving the objective of a drug-free work force. While this clause defines criteria for such a program, contractors are encouraged to implement alternative approaches comparable to the criteria in paragraph (c) that are designed to achieve the objectives of this clause.

(c) Contractor programs shall include the following, or appropriate alternatives:

(1) Employee assistance programs emphasizing high level direction, education, counseling, rehabilitation, and coordination with available community resources;

(2) Supervisory training to assist in identifying and addressing illegal drug use by Contractor employees;

(3) Provision for self-referrals as well as supervisory referrals to treatment with maximum respect for individual confidentiality consistent with safety and security issues;

(4) Provision for identifying illegal drug users, including testing on a controlled and carefully monitored basis. Employee drug testing programs shall be established taking account of the following:

(i) The Contractor shall establish a program that provides for testing for the use of illegal drugs by employees in sensitive positions. The extent of and criteria for such testing shall be determined by the Contractor based on considerations that include the nature of the work being performed under the contract, the employee's duties, and efficient use of Contractor resources, and the risks to health, safety, or national security that could result from the failure of an employee adequately to discharge his or her position.

(ii) In addition, the Contractor may establish a program for employee drug testing--

(A) When there is a reasonable suspicion that an employee uses illegal drugs; or

(B) When an employees has been involved in an accident or unsafe practice;

(C) As part of or as a follow-up to counseling or rehabilitation for illegal drug use;

(D) As part of a voluntary employee drug testing program.

(iii) The Contractor may establish a program to test applicants for employment for illegal drug use.

(iv) For the purpose of administering this clause, testing for illegal drugs may be limited to those substances for which testing is prescribed by section 2..1 of subpart B of the "Mandatory Guidelines for Federal Workplace Drug Testing Programs" (53 FR 11980 (April 11, 1988), issued by the Department of Health and Human Services.

(d) Contractors shall adopt appropriate personnel procedures to deal with employees who are found to be using drugs illegally. Contractors shall not allow any employee to remain on duty or perform in a sensitive position who is found to use illegal drugs until such times as the Contractor, in accordance with procedures established by the Contractor, determines that the employee may perform in such a position.

(e) The provisions of this clause pertaining to drug testing program shall not apply to the extent that are inconsistent with state or local law, or with an existing collective bargaining agreement; provided that with respect to the latter, the Contractor agrees those issues that are in conflict will be a subject of negotiation at the next collective bargaining session.

(End of clause)

252.225-7012 Preference for Certain Domestic Commodities (APR 2002)

(a) Definitions. As used in this clause--

(1) Component means any item supplied to the Government as part of an end product or of another component.

(2) End product means supplies delivered under a line item of this contract.

(b) The Contractor shall deliver under this contract only such of the following items, either as end products or components, that have been grown, reprocessed, reused, or produced in the United States, its possessions, or Puerto Rico:

(1) Food.

(2) Clothing.

(3) Tents, tarpaulins, or covers.

(4) Cotton and other natural fiber products.

(5) Woven silk or woven silk blends.

(6) Spun silk yarn for cartridge cloth.

(7) Synthetic fabric, and coated synthetic fabric, including all textile fibers and yarns that are for use in such fabrics.

(8) Canvas products.

(9) Wool (whether in the form of fiber or yarn or contained in fabrics, materials, or manufactured articles).

(10) Any item of individual equipment (Federal Supply Class 8465) manufactured from or containing fibers, yarns, fabrics, or materials listed in this paragraph (b).

(c) This clause does not apply--

(1) To items listed in section 25.104(a) of the Federal Acquisition Regulation (FAR), or other items for which the Government has determined that a satisfactory quality and sufficient quantity cannot be acquired as and when needed at U.S. market prices;

(2) To end products incidentally incorporating cotton, other natural fibers, or wool, for which the estimated value of the cotton, other natural fibers, or wool--

(i) Is not more than 10 percent of the total price of the end product; and (ii) Does not exceed the simplified acquisition threshold in FAR part 2;

(3) To foods that have been manufactured or processed in the United States, its possessions, or Puerto Rico, regardless of where the foods (and any component if applicable) were grown or produced;

(4) To chemical warfare protective clothing produced in the countries listed in subsection 225.872-1 of the Defense FAR Supplement; or

(5) To fibers and yarns that are for use in synthetic fabric or coated synthetic fabric (but does apply to the synthetic or coated synthetic fabric itself), if--

(i) The fabric is to be used as a component of an end product that is not a textile product. Examples of textile products, made in whole or in part of fabric, include--

(A) Draperies, floor coverings, furnishings, and bedding (Federal Supply Group 72, Household and Commercial Furnishings and Appliances);

(B) Items made in whole or in part of fabric in Federal Supply Group 83, Textile/leather/furs/apparel/findings/ tents/flags, or Federal Supply Group 84, Clothing, Individual Equipment and Insignia;

(C) Upholstered seats (whether for household, office, or other use); and

(D) Parachutes (Federal Supply Class 1670); or

(ii) The fibers and yarns are para-aramid fibers and yarns manufactured in the Netherlands.

(End of clause)

## 252.225-7031 SECONDARY ARAB BOYCOTT OF ISRAEL (JUN 1992)

(a) Definitions. As used in this clause--

(1) "Foreign person" means any person other than a United States person as defined in Section 16(2) of the Export Administration Act of 1979 (50 U.S.C. App. Sec 2415).

(2) "United States person" is defined in Section 16(2) of the Export Administration Act of 1979 and means any United States resident or national (other than an individual resident outside the United States and employed by other than a United States person), any domestic concern (including any permanent domestic establishment of any foreign concern), and any foreign subsidiary or affiliate (including any permanent foreign establishment) of any domestic concern which is controlled in fact by such domestic concerns, as determined under regulations of the President.

(b) Certification. By submitting this offer, the Offeror, if a foreign person, company or entity, certifies that it--

(1) Does not comply with the Secondary Arab Boycott of Israel; and

(2) Is not taking or knowingly agreeing to take any action, with respect to the Secondary Boycott of Israel by Arab countries, which 50 U.S.C. App. Sec 2407(a) prohibits a United States person from taking.

(End of clause)

252.227-7000 Non-estoppel. (OCT 1966)

The Government reserves the right at any time to contest the enforceability, validity, scope of, or the title to any patent or patent application herein licensed without waiving or forfeiting any right under this contract.

(End of clause)

252.227-7022 GOVERNMENT RIGHTS (UNLIMITED) (MAR 1979)

The Government shall have unlimited rights, in all drawings, designs, specifications, notes and other works developed in the performance of this contract, including the right to use same on any other Government design or construction without additional compensation to the Contractor. The Contractor hereby grants to the Government a paid-up license throughout the world to all such works to which he may assert or establish any claim under design patent or copyright laws. The Contractor for a period of three (3) years after completion of the project agrees to furnish the original or copies of all such works on the request of the Contracting Officer.

(End of clause)

252.227-7023 DRAWINGS AND OTHER DATA TO BECOME PROPERTY OF GOVERNMENT. (MAR 1979)

All designs, drawings, specifications, notes and other works developed in the performance of this contract shall become the sole property of the Government and may be used on any other design or construction without additional compensation to the Contractor. The Government shall be considered the "person for whom the work was prepared" for the purpose of authorship in any copyrightable work under 17 U.S.C. 201(b). With respect thereto, the Contractor agrees not to assert or authorize others to assert any rights nor establish any claim under the design patent or copyright laws. The Contractor for a period of three (3) years after completion of the project agrees to furnish all retained works on the request of the Contracting Officer. Unless otherwise provided in this contract, the Contractor shall have the right to retain copies of all works beyond such period.

(End of clause)

#### 252.227-7033 RIGHTS IN SHOP DRAWINGS (APR 1966)

(a) Shop drawings for construction means drawings, submitted to the Government by the Construction Contractor, subcontractor or any lower-tier subcontractor pursuant to a construction contract, showing in detail (i) the proposed fabrication and assembly of structural elements and (ii) the installation (i.e., form, fit, and attachment details) of materials or equipment. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(b) This clause, including this paragraph (b), shall be included in all subcontracts hereunder at any tier.

#### 252.231-7000 SUPPLEMENTAL COST PRINCIPLES (DEC 1991)

When the allowability of costs under this contract is determined in accordance with part 31 of the Federal Acquisition Regulation (FAR), allowability shall also be determined in accordance with part 231 of the Defense FAR Supplement, in effect on the date of this contract.

(End of clause)

#### 252.236-7000 MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991)

(a) The Contractor shall furnish a price breakdown, itemized as required and within the time specified by the Contracting Officer, with any proposal for a contract modification.

(b) The price breakdown --

(1) Must include sufficient detail to permit an analysis of profit, and of all costs for --

(i) Material;

(ii) Labor;

(iii) Equipment;

(iv) Subcontracts; and

(v) Overhead; and

(2) Must cover all work involved in the modification, whether the work was deleted, added, or changed.

(c) The Contractor shall provide similar price breakdowns to support any amounts claimed for subcontracts.

(d) The Contractor's proposal shall include a justification for any time extension proposed.



252.236-7008 CONTRACT PRICES - BIDDING SCHEDULES. (DEC 1991)

(a) The Government's payment for the items listed in the Bidding Schedule shall constitute full compensation to the Contractor for --

(1) Furnishing all plant, labor, equipment, appliances, and materials; and

(2) Performing all operations required to complete the work in conformity with the drawings and specifications.

(b) The Contractor shall include in the prices for the items listed in the Bidding Schedule all costs for work in the specifications, whether or not specifically listed in the Bidding Schedule.

252.242-7000 POSTAWARD CONFERENCE (DEC 1991)

The Contractor agrees to attend any postaward conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation subpart 42.5.

(End of clause)

252.243-7001 PRICING OF CONTRACT MODIFICATIONS (DEC 1991)

When costs are a factor in any price adjustment under this contract, the contract cost principles and procedures in FAR part 31 and DFARS part 231, in effect on the date of this contract, apply.

252.243-7002 REQUESTS FOR EQUITABLE ADJUSTMENT (MAR 1998)

(a) The amount of any request for equitable adjustment to contract terms shall accurately reflect the contract adjustment for which the Contractor believes the Government is liable. The request shall include only costs for performing the change, and shall not include any costs that already have been reimbursed or that have been separately claimed. All indirect costs included in the request shall be properly allocable to the change in accordance with applicable acquisition regulations.

(b) In accordance with 10 U.S.C. 2410(a), any request for equitable adjustment to contract terms that exceeds the simplified acquisition threshold shall bear, at the time of submission, the following certificate executed by an individual authorized to certify the request on behalf of the Contractor:

I certify that the request is made in good faith, and that the supporting data are accurate and complete to the best of my knowledge and belief.

-----  
(Official's Name)

-----  
(Title)

(c) The certification in paragraph (b) of this clause requires full disclosure of all relevant facts, including--

(1) Cost or pricing data if required in accordance with subsection 15.403-4 of the Federal Acquisition Regulation (FAR); and

(2) Information other than cost or pricing data, in accordance with subsection 15.403-3 of the FAR, including actual cost data and data to support any estimated costs, even if cost or pricing data are not required.

(d) The certification requirement in paragraph (b) of this clause does not apply to----

(1) Requests for routine contract payments; for example, requests for payment for accepted supplies and services, routine vouchers under a cost-reimbursement type contract, or progress payment invoices; or

(2) Final adjustment under an incentive provision of the contract.

#### 252.247-7024 Notification of Transportation of Supplies by Sea (MAR 2000)

(a) The Contractor has indicated by the response to the solicitation provision, Representation of Extent of Transportation by Sea, that it did not anticipate transporting by sea any supplies. If, however, after the award of this contract, the Contractor learns that supplies, as defined in the Transportation of Supplies by Sea clause of this contract, will be transported by sea, the Contractor --

(1) Shall notify the Contracting Officer of that fact; and

(2) Hereby agrees to comply with all the terms and conditions of the Transportation of Supplies by Sea clause of this contract.

(b) The Contractor shall include this clause; including this paragraph (b), revised as necessary to reflect the relationship of the contracting parties--

(1) In all subcontracts under this contract, if this contract is a construction contract; or

(2) If this contract is not a construction contract, in all subcontracts under this contract that are for--

(i) Noncommercial items; or

(ii) Commercial items that--

(A) The Contractor is reselling or distributing to the Government without adding value (generally, the Contractor does not add value to items that it subcontracts for f.o.b. destination shipment);

(B) Are shipped in direct support of U.S. military contingency operations, exercises, or forces deployed in humanitarian or peacekeeping operations; or

(C) Are commissary or exchange cargoes transported outside of the Defense Transportation System in accordance with 10 U.S.C. 2643.

(End of clause)

## Section 00800 Special Contract Requirements

CLAUSES INCORPORATED BY FULL TEXT .....	2
52.0001-4001 CONTRACT ADMINISTRATION DATA.....	2
52.211-10 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK.....	2
52.211-12 LIQUIDATED DAMAGES – CONSTRUCTION .....	3
52.211-18 VARIATION IN ESTIMATED QUANTITY (APR 1984).....	3
52.211-4002 VARIATION IN ESTIMATED QUANTITIES - SUBDIVIDED ITEMS (MAR 1995) ...	3
(EFARS 52.211-5001).....	3
52.222-23 NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY FOR CONSTRUCTION (FEB 1999) .....	3
52.228-14 IRREVOCABLE LETTER OF CREDIT (DEC 1999).....	4
52.231-5000 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE .....	8
MAR 1995)--EFARS.....	8
52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—CENTRAL CONTRACTOR REGISTRATION (MAY 1999).....	8
52.232-4001 CONTINUING CONTRACTS (ALTERNATE) (MAR 1995) EFARS 52-232-5002 .....	10
52.236-4 PHYSICAL DATA (APR 1984).....	11
52.236-16 QUANTITY SURVEYS (APR 1984).....	11
52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997) .....	11
252.236-7001 CONTRACT DRAWINGS, MAPS, AND SPECIFICATIONS (AUG 2000) .....	12
252.247-7023 Transportation of Supplies by Sea (MAY 2002) .....	13

## CLAUSES INCORPORATED BY FULL TEXT

## 52.0001-4001 CONTRACT ADMINISTRATION DATA

The Contract Administration Office for this contract subsequent to award is:

Department of the Army  
Los Angeles District, Corps of Engineers  
P.O. Box 532711  
Los Angeles, California 90053-2325

ATTN: Mary Ann Powers

Telephone No: (213) 452-3254

Payment will be made by:

USACE Finance Center  
ATTN: CEFC-AO-P  
5270 Integrity Drive  
Millington, TN 38054-5005

Submit Invoices to:

[Enter address where contractor is to submit invoices]

## 52.211-10 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK

The Contractor shall be required to

- (a) provide payment and performance bonds within 10 days after award of the contract,
- (b) commence work under this contract within 10 calendar days after the date the Contractor receives the Notice to Proceed,
- (c) prosecute the work diligently, and
- (d) complete the entire Base Bid work ready for use not later than 70 calendar days after receipt of Notice to Proceed. The time stated for completion shall include final cleanup of the premises.
- (e) If awarded, the Second Year Cycle of dredging shall be completed within 70 calendar days after receipt of SF 30 "Modification of Contract." The time stated for completion shall include final cleanup of the premises.
- (f) If awarded, the Third Year Cycle of dredging shall be completed within 70 calendar days after receipt of SF 30 "Modification of Contract." The time stated for completion shall include final cleanup of the premises.

(End of clause)

## 52.211-12 LIQUIDATED DAMAGES – CONSTRUCTION

- (a) If the Contractor fails to complete the work within the time specified in the contract, or any extension, the Contractor shall pay to the Government as liquidated damages, the sum of **\$907.00** for each day of delay.
- (b) If the Government terminates the Contractor's right to proceed, the resulting damage will consist of liquidated damages until such reasonable time as may be required for final completion of the work together with any increased costs occasioned the Government in completing the work.
- (c) If the Government does not terminate the Contractor's right to proceed, the resulting damage will consist of liquidated damages until the work is completed or accepted.

(End of clause)

## 52.211-18 VARIATION IN ESTIMATED QUANTITY (APR 1984)

If the quantity of a unit-priced item in this contract is an estimated quantity and the actual quantity of the unit-priced item varies more than 15 percent above or below the estimated quantity, an equitable adjustment in the contract price shall be made upon demand of either party. The equitable adjustment shall be based upon any increase or decrease in costs due solely to the variation above 115 percent or below 85 percent of the estimated quantity. If the quantity variation is such as to cause an increase in the time necessary for completion, the Contractor may request, in writing, an extension of time, to be received by the Contracting Officer within 10 days from the beginning of the delay, or within such further period as may be granted by the Contracting Officer before the date of final settlement of the contract. Upon the receipt of a written request for an extension, the Contracting Officer shall ascertain the facts and make an adjustment for extending the completion date as, in the judgement of the Contracting Officer, is justified.

52.211-4002 VARIATION IN ESTIMATED QUANTITIES - SUBDIVIDED ITEMS (MAR 1995)  
(EFARS 52.211-5001)

This variation in estimated quantities clause is applicable only to Items Nos. 2A, 2B, 4A, 4B, and 6A, 6B.

- (a) Variation from the estimated quantity in the actual work performed under any second or subsequent sub-item or elimination of all work under such a second or subsequent sub-item will not be the basis for an adjustment in contract unit price.
- (b) Where the actual quantity of work performed for Items Nos. 2A, 4A, and 6A is less than 85% of the quantity of the first sub-item listed under such item, the Contractor will be paid at the contract unit price for that sub-item for the actual quantity of work performed and, in addition, an equitable adjustment shall be made in accordance with the clause FAR 52.211-18, Variation in Estimated Quantities.
- (c) If the actual quantity of work performed under Items Nos. 2A, 4A, and 6A exceeds the 115% or is less than 85% of the total estimated quantity of the sub-items under that item and / or if the quantity of work performed under the second sub-item or any subsequent sub-item under Items Nos. 2B, 4B, and 6B exceeds 115% or is less than the 85% of the estimated quantity of any such sub-item, and if such variation causes an increase or a decrease in the time required for performance of this contract the contract completion time will be adjusted in accordance with the clause FAR 52.211-18, Variation in Estimated Quantities.

(End of clause)

52.222-23 NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL  
EMPLOYMENT OPPORTUNITY FOR CONSTRUCTION (FEB 1999)

- (a) The offeror's attention is called to the Equal Opportunity clause and the Affirmative Action Compliance Requirements for Construction clause of this solicitation.

(b) The goals for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

Goals for minority participation for each trade	Goals for female participation for each trade
24.0 to 30.0 %	6.9%

These goals are applicable to all the Contractor's construction work performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, the Contractor shall apply the goals established for the geographical area where the work is actually performed. Goals are published periodically in the Federal Register in notice form, and these notices may be obtained from any Office of Federal Contract Compliance Programs office.

(c) The Contractor's compliance with Executive Order 11246, as amended, and the regulations in 41 CFR 60-4 shall be based on (1) its implementation of the Equal Opportunity clause, (2) specific affirmative action obligations required by the clause entitled "Affirmative Action Compliance Requirements for Construction," and (3) its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade. The Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor, or from project to project, for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, Executive Order 11246, as amended, and the regulations in 41 CFR 60-4. Compliance with the goals will be measured against the total work hours performed.

(d) The Contractor shall provide written notification to the Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, within 10 working days following award of any construction subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the --

- (1) Name, address, and telephone number of the subcontractor;
- (2) Employer's identification number of the subcontractor;
- (3) Estimated dollar amount of the subcontract;
- (4) Estimated starting and completion dates of the subcontract; and
- (5) Geographical area in which the subcontract is to be performed.

(e) As used in this Notice, and in any contract resulting from this solicitation, the "covered area" is [Contracting Officer shall insert description of the geographical areas where the contract is to be performed, giving the State, county, and city].

(End of provision)

#### 52.228-14 IRREVOCABLE LETTER OF CREDIT (DEC 1999)

(a) "Irrevocable letter of credit" (ILC), as used in this clause, means a written commitment by a federally insured financial institution to pay all or part of a stated amount of money, until the expiration date of the letter, upon presentation by the Government (the beneficiary) of a written demand therefor. Neither the financial institution nor the offeror/Contractor can revoke or condition the letter of credit.

(b) If the offeror intends to use an ILC in lieu of a bid bond, or to secure other types of bonds such as performance and payment bonds, the letter of credit and letter of confirmation formats in paragraphs (e) and (f) of this clause shall be used.

(c) The letter of credit shall be irrevocable, shall require presentation of no document other than a written demand and the ILC (including confirming letter, if any), shall be issued/confirmed by an acceptable federally insured financial institution as provided in paragraph (d) of this clause, and--

(1) If used as a bid guarantee, the ILC shall expire no earlier than 60 days after the close of the bid acceptance period;

(2) If used as an alternative to corporate or individual sureties as security for a performance or payment bond, the offeror/Contractor may submit an ILC with an initial expiration date estimated to cover the entire period for which financial security is required or may submit an ILC with an initial expiration date that is a minimum period of one year from the date of issuance. The ILC shall provide that, unless the issuer provides the beneficiary written notice of non-renewal at least 60 days in advance of the current expiration date, the ILC is automatically extended without amendment for one year from the expiration date, or any future expiration date, until the period of required coverage is completed and the Contracting Officer provides the financial institution with a written statement waiving the right to payment. The period of required coverage shall be:

(i) For contracts subject to the Miller Act, the later of--

(A) One year following the expected date of final payment;

(B) For performance bonds only, until completion of any warranty period; or

(C) For payment bonds only, until resolution of all claims filed against the payment bond during the one-year period following final payment.

(ii) For contracts not subject to the Miller Act, the later of--

(A) 90 days following final payment; or

(B) For performance bonds only, until completion of any warranty period.

(d) Only federally insured financial institutions rated investment grade or higher shall issue or confirm the ILC. The offeror/Contractor shall provide the Contracting Officer a credit rating that indicates the financial institution has the required rating(s) as of the date of issuance of the ILC. Unless the financial institution issuing the ILC had letter of credit business of less than \$25 million in the past year, ILCs over \$5 million must be confirmed by another acceptable financial institution that had letter of credit business of less than \$25 million in the past year.

(e) The following format shall be used by the issuing financial institution to create an ILC:

\_\_\_\_\_  
[Issuing Financial Institution's Letterhead or Name and Address]

Issue Date \_\_\_\_\_

IRREVOCABLE LETTER OF CREDIT NO. \_\_\_\_\_

Account party's name \_\_\_\_\_

Account party's address \_\_\_\_\_



For Solicitation No. \_\_\_\_\_ (for reference only)

TO: [U.S. Government agency]

[U.S. Government agency's address]

1. We hereby establish this irrevocable and transferable Letter of Credit in your favor for one or more drawings up to United States \$ \_\_\_\_\_. This Letter of Credit is payable at [issuing financial institution's and, if any, confirming financial institution's] office at [issuing financial institution's address and, if any, confirming financial institution's address] and expires with our close of business on \_\_\_\_\_, or any automatically extended expiration date.

2. We hereby undertake to honor your or the transferee's sight draft(s) drawn on the issuing or, if any, the confirming financial institution, for all or any part of this credit if presented with this Letter of Credit and confirmation, if any, at the office specified in paragraph 1 of this Letter of Credit on or before the expiration date or any automatically extended expiration date.

3. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this Letter of Credit that it is deemed to be automatically extended without amendment for one year from the expiration date hereof, or any future expiration date, unless at least 60 days prior to any expiration date, we notify you or the transferee by registered mail, or other receipted means of delivery, that we elect not to consider this Letter of Credit renewed for any such additional period. At the time we notify you, we also agree to notify the account party (and confirming financial institution, if any) by the same means of delivery.

4. This Letter of Credit is transferable. Transfers and assignments of proceeds are to be effected without charge to either the beneficiary or the transferee/assignee of proceeds. Such transfer or assignment shall be only at the written direction of the Government (the beneficiary) in a form satisfactory to the issuing financial institution and the confirming financial institution, if any.

5. This Letter of Credit is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of \_\_\_\_\_ [state of confirming financial institution, if any, otherwise state of issuing financial institution].

6. If this credit expires during an interruption of business of this financial institution as described in Article 17 of the UCP, the financial institution specifically agrees to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

\_\_\_\_\_

[Issuing financial institution]

(f) The following format shall be used by the financial institution to confirm an ILC:

\_\_\_\_\_  
[Confirming Financial Institution's Letterhead or Name and Address]

(Date) \_\_\_\_\_

Our Letter of Credit Advice Number \_\_\_\_\_

Beneficiary: \_\_\_\_\_ [U.S. Government agency]

Issuing Financial Institution: \_\_\_\_\_

Issuing Financial Institution's LC No.: \_\_\_\_\_

Gentlemen:

1. We hereby confirm the above indicated Letter of Credit, the original of which is attached, issued by \_\_\_\_\_ [name of issuing financial institution] for drawings of up to United States dollars \_\_\_\_\_/U.S. \$ \_\_\_\_\_ and expiring with our close of business on \_\_\_\_\_ [the expiration date], or any automatically extended expiration date.

2. Draft(s) drawn under the Letter of Credit and this Confirmation are payable at our office located at \_\_\_\_\_.

3. We hereby undertake to honor sight draft(s) drawn under and presented with the Letter of Credit and this Confirmation at our offices as specified herein.

4. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this confirmation that it be deemed automatically extended without amendment for one year from the expiration date hereof, or any automatically extended expiration date, unless:

(a) At least 60 days prior to any such expiration date, we shall notify the Contracting Officer, or the transferee and the issuing financial institution, by registered mail or other receipted means of delivery, that we elect not to consider this confirmation extended for any such additional period; or

(b) The issuing financial institution shall have exercised its right to notify you or the transferee, the account party, and ourselves, of its election not to extend the expiration date of the Letter of Credit.

5. This confirmation is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of \_\_\_\_\_ [state of confirming financial institution].

6. If this confirmation expires during an interruption of business of this financial institution as described in Article 17 of the UCP, we specifically agree to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

\_\_\_\_\_

[Confirming financial institution]

(g) The following format shall be used by the Contracting Officer for a sight draft to draw on the Letter of Credit:

SIGHT DRAFT

\_\_\_\_\_

[City, State]

(Date) \_\_\_\_\_

[Name and address of financial institution]

Pay to the order of \_\_\_\_\_ [Beneficiary Agency] \_\_\_\_\_ the sum of United States  
\$ \_\_\_\_\_. This draft is drawn under Irrevocable Letter of Credit No.

\_\_\_\_\_.

\_\_\_\_\_  
[Beneficiary Agency]

By: \_\_\_\_\_

(End of clause)

#### 52.231-5000 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE MAR 1995)--EFARS

(a) This clause does not apply to terminations. See 52.249-5000, Basis for Settlement of Proposals and FAR Part 49.

(b) Allowable cost for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor at any tier shall be based on actual cost data for each piece of equipment or groups of similar serial and series for which the Government can determine both ownership and operating costs from the contractor's accounting records. When both ownership and operating costs cannot be determined for any piece of equipment or groups of similar serial or series equipment from the contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP 1110-1-8, Construction Equipment Ownership and Operating Expense Schedule, Region \_\_\_\_\_. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the contracting officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retroactive pricing, the schedule in effect at the time the work was performed shall apply.

(c) Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d)(ii) and FAR 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees.

(d) When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the contracting officer shall request the contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, Contract Pricing Proposal Cover Sheet.

(End of clause)

#### 52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—CENTRAL CONTRACTOR REGISTRATION (MAY 1999)

(a) Method of payment. (1) All payments by the Government under this contract shall be made by electronic funds transfer (EFT), except as provided in paragraph (a)(2) of this clause. As used in this clause, the term "EFT" refers to the funds transfer and may also include the payment information transfer.

(2) In the event the Government is unable to release one or more payments by EFT, the Contractor agrees to either--

(i) Accept payment by check or some other mutually agreeable method of payment; or

(ii) Request the Government to extend the payment due date until such time as the Government can make payment by EFT (but see paragraph (d) of this clause).

(b) Contractor's EFT information. The Government shall make payment to the Contractor using the EFT information contained in the Central Contractor Registration (CCR) database. In the event that the EFT information changes, the Contractor shall be responsible for providing the updated information to the CCR database.

(c) Mechanisms for EFT payment. The Government may make payment by EFT through either the Automated Clearing House (ACH) network, subject to the rules of the National Automated Clearing House Association, or the Fedwire Transfer System. The rules governing Federal payments through the ACH are contained in 31 CFR part 210.

(d) Suspension of payment. If the Contractor's EFT information in the CCR database is incorrect, then the Government need not make payment to the Contractor under this contract until correct EFT information is entered into the CCR database; and any invoice or contract financing request shall be deemed not to be a proper invoice for the purpose of prompt payment under this contract. The prompt payment terms of the contract regarding notice of an improper invoice and delays in accrual of interest penalties apply.

(e) Contractor EFT arrangements. If the Contractor has identified multiple payment receiving points (i.e., more than one remittance address and/or EFT information set) in the CCR database, and the Contractor has not notified the Government of the payment receiving point applicable to this contract, the Government shall make payment to the first payment receiving point (EFT information set or remittance address as applicable) listed in the CCR database.

(f) Liability for uncompleted or erroneous transfers. (1) If an uncompleted or erroneous transfer occurs because the Government used the Contractor's EFT information incorrectly, the Government remains responsible for--

(i) Making a correct payment;

(ii) Paying any prompt payment penalty due; and

(iii) Recovering any erroneously directed funds.

(2) If an uncompleted or erroneous transfer occurs because the Contractor's EFT information was incorrect, or was revised within 30 days of Government release of the EFT payment transaction instruction to the Federal Reserve System, and--

(i) If the funds are no longer under the control of the payment office, the Government is deemed to have made payment and the Contractor is responsible for recovery of any erroneously directed funds; or

(ii) If the funds remain under the control of the payment office, the Government shall not make payment, and the provisions of paragraph (d) of this clause shall apply.

(g) EFT and prompt payment. A payment shall be deemed to have been made in a timely manner in accordance with the prompt payment terms of this contract if, in the EFT payment transaction instruction released to the Federal Reserve System, the date specified for settlement of the payment is on or before the prompt payment due date, provided the specified payment date is a valid date under the rules of the Federal Reserve System.

(h) EFT and assignment of claims. If the Contractor assigns the proceeds of this contract as provided for in the assignment of claims terms of this contract, the Contractor shall require as a condition of any such assignment, that the assignee shall register in the CCR database and shall be paid by EFT in accordance with the terms of this clause. In all respects, the requirements of this clause shall apply to the assignee as if it were the Contractor. EFT information that shows the ultimate recipient of the transfer to be other than the Contractor, in the absence of a proper assignment of claims acceptable to the Government, is incorrect EFT information within the meaning of paragraph (d) of this clause.

(i) Liability for change of EFT information by financial agent. The Government is not liable for errors resulting from changes to EFT information made by the Contractor's financial agent.

(j) Payment information. The payment or disbursing office shall forward to the Contractor available payment information that is suitable for transmission as of the date of release of the EFT instruction to the Federal Reserve System. The Government may request the Contractor to designate a desired format and method(s) for delivery of payment information from a list of formats and methods the payment office is capable of executing. However, the Government does not guarantee that any particular format or method of delivery is available at any particular payment office and retains the latitude to use the format and delivery method most convenient to the Government. If the Government makes payment by check in accordance with paragraph (a) of this clause, the Government shall mail the payment information to the remittance address contained in the CCR database.

(End of Clause)

52.232-4001 CONTINUING CONTRACTS (ALTERNATE) (MAR 1995) EFARS 52-232-5002

(a) Funds are not available at the inception of this contract to cover the entire contract price. The sum of \$1,000.00 has been reserved for this contract and is available for payment to the contractor during the current fiscal year. It is expected that Congress will make appropriations for future fiscal years from which additional funds, together with funds provided by one or more non-federal project sponsors will be reserved for this contract. The liability of the United States for payment beyond the funds reserved for this contract is contingent on the reservation of additional funds.

(b) Failure to make payment in excess of the amount currently reserved, or that may be reserved from time to time, shall not be considered a breach of this contract, and shall not entitle the contractor to a price adjustment under the terms of this contract except as specifically provided in paragraphs (e) and (h) below.

(c) The Government may at any time reserve additional funds for payments under the contract if there are funds available for such purpose. The contracting officer will promptly notify the contractor of any additional funds reserved for the contract by issuing an administrative modification to the contract.

(d) If earnings will be such that funds reserved for the contract will be exhausted before the end of any fiscal year, the contractor shall give written notice to the contracting officer of the estimated date of exhaustion and of additional funds which will be needed to meet payments due or to become due under this contract during that fiscal year. This notice shall be given not less than 45 nor more than 60 days prior to the estimated date of exhaustion.

(e) No payments will be made after exhaustion of funds except to the extent that additional funds are reserved for the contract. If and when sufficient additional funds are reserved, the contractor shall be entitled to simple interest on any payment that the contracting officer determines was actually earned under the terms of this contract and would have been made except for exhaustion of funds. Interest shall be computed from the time such payment would otherwise have been made until actually or constructively made, and shall be at the rate established by the Secretary of the Treasury pursuant to Public Law 92-41, 85 Stat 97, as in effect on the first day of the delay in such payment.

(f) Any suspension, delay, or interruption of work arising from exhaustion or anticipated exhaustion of funds shall not constitute a breach of this contract and shall not entitle the contractor to any price adjustment under a "Suspension of Work" or similar clause or in any other manner under this contract.

(g) An equitable adjustment in performance time shall be made for any increase in the time required for performance of any part of the work arising from exhaustion of funds or the reasonable anticipation of exhaustion of funds.

(h) If, upon the expiration of sixty (60) days after the beginning of the fiscal year following an exhaustion of funds, the Government has failed to reserve sufficient additional funds to cover payments otherwise due, the contractor, by written notice delivered to the contracting officer at any time before such additional funds are reserved, may elect to treat his right to proceed with the work as having been terminated. Such a termination shall be at no cost to the Government, except that, to the extent that additional funds to make payment therefore are allocated to this contract, it may be treated as a termination for the convenience of the Government.

(i) If at any time it becomes apparent that the funds reserved for any fiscal year are in excess of the funds required to meet all payments due or to become due the contractor because of work performed and to

be performed under this contract during the fiscal year, the Government reserves the right, after notice to the contractor, to reduce said reservation by the amount of such excess.

(j) The term "Reservation" means monies that have been set aside and made available for payments under this contract.

(End of clause)

#### 52.236-4 PHYSICAL DATA (APR 1984)

Data and information furnished or referred to below is for the Contractor's information. The Government shall not be responsible for any interpretation of or conclusion drawn from the data or information by the Contractor.

(a) The indications of physical conditions on the drawings and in the specifications are the result of site investigations by surveys, diver borings, and core borings.

(b) Weather conditions . . . . . (insert a summary of weather records and warnings).

(c) Transportation facilities . . . . . (insert a summary of transportation facilities providing access from the site, including information about their availability and limitations).

(End of clause)

#### 52.236-16 QUANTITY SURVEYS (APR 1984)

(a) Quantity surveys shall be conducted, and the data derived from these surveys shall be used in computing the quantities of work performed and the actual construction completed and in place.

(b) The Government shall conduct the original and final surveys and make the computations based on them. The Contractor shall conduct the surveys for any periods for which progress payments are requested and shall make the computations based on these surveys. All surveys conducted by the Contractor shall be conducted under the direction of a representative of the Contracting Officer, unless the Contracting Officer waives this requirement in a specific instance.

(c) Promptly upon completing a survey, the Contractor shall furnish the originals of all field notes and all other records relating to the survey or to the layout of the work to the Contracting Officer, who shall use them as necessary to determine the amount of progress payments. The Contractor shall retain copies of all such material furnished to the Contracting Officer.

(End of clause)

#### 52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or

"acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.

(c) Where "as shown," "as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

(End of clause)

#### 252.236-7001 CONTRACT DRAWINGS, MAPS, AND SPECIFICATIONS (AUG 2000)

(a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

(b) The Contractor shall--

- (1) Check all drawings furnished immediately upon receipt;
- (2) Compare all drawings and verify the figures before laying out the work;
- (3) Promptly notify the Contracting Officer of any discrepancies;
- (4) Be responsible for any errors that might have been avoided by complying with this paragraph (b); and
- (5) Reproduce and print contract drawings and specifications as needed.

(c) In general--

(1) Large-scale drawings shall govern small-scale drawings; and

(2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified on the following index of drawings:

Title	File	Drawing No.
Vicinity Map, Location Map, and Index to Contract Drawings		File No. B-0328

(End of clause)

252.247-7023 Transportation of Supplies by Sea (MAY 2002)

(a) Definitions. As used in this clause --

(1) "Components" means articles, materials, and supplies incorporated directly into end products at any level of manufacture, fabrication, or assembly by the Contractor or any subcontractor.

(2) "Department of Defense" (DoD) means the Army, Navy, Air Force, Marine Corps, and defense agencies.

(3) "Foreign flag vessel" means any vessel that is not a U.S.-flag vessel.

(4) "Ocean transportation" means any transportation aboard a ship, vessel, boat, barge, or ferry through international waters.

(5) "Subcontractor" means a supplier, materialman, distributor, or vendor at any level below the prime contractor whose contractual obligation to perform results from, or is conditioned upon, award of the prime contract and who is performing any part of the work or other requirement of the prime contract.

(6) "Supplies" means all property, except land and interests in land, that is clearly identifiable for eventual use by or owned by the DoD at the time of transportation by sea.

(i) An item is clearly identifiable for eventual use by the DoD if, for example, the contract documentation contains a reference to a DoD contract number or a military destination.

(ii) "Supplies" includes (but is not limited to) public works; buildings and facilities; ships; floating equipment and vessels of every character, type, and description, with parts, subassemblies, accessories, and equipment; machine tools; material; equipment; stores of all kinds; end items; construction materials; and components of the foregoing.

(7) "U.S.-flag vessel" means a vessel of the United States or belonging to the United States, including any vessel registered or having national status under the laws of the United States.

(b)(1) The Contractor shall use U.S.-flag vessels when transporting any supplies by sea under this contract.

(2) A subcontractor transporting supplies by sea under this contract shall use U.S.-flag vessels if--



(i) This contract is a construction contract; or

(ii) The supplies being transported are--

(A) Noncommercial items; or

(B) Commercial items that--

(1) The Contractor is reselling or distributing to the Government without adding value (generally, the Contractor does not add value to items that it contracts for f.o.b. destination shipment);

(2) Are shipped in direct support of U.S. military contingency operations, exercises, or forces deployed in humanitarian or peacekeeping operations; or

(3) Are commissary or exchange cargoes transported outside of the Defense Transportation System in accordance with 10 U.S.C. 2643.

(c) The Contractor and its subcontractors may request that the Contracting Officer authorize shipment in foreign-flag vessels, or designate available U.S.-flag vessels, if the Contractor or a subcontractor believes that --

(1) U.S.-flag vessels are not available for timely shipment;

(2) The freight charges are inordinately excessive or unreasonable; or

(3) Freight charges are higher than charges to private persons for transportation of like goods.

(d) The Contractor must submit any request for use of other than U.S.-flag vessels in writing to the Contracting Officer at least 45 days prior to the sailing date necessary to meet its delivery schedules. The Contracting Officer will process requests submitted after such date(s) as expeditiously as possible, but the Contracting Officer's failure to grant approvals to meet the shipper's sailing date will not of itself constitute a compensable delay under this or any other clause of this contract. Requests shall contain at a minimum --

(1) Type, weight, and cube of cargo;

(2) Required shipping date;

(3) Special handling and discharge requirements;

(4) Loading and discharge points;

(5) Name of shipper and consignee;

(6) Prime contract number; and

(7) A documented description of efforts made to secure U.S.-flag vessels, including points of contact (with names and telephone numbers) with at least two U.S.-flag carriers contacted. Copies of telephone notes, telegraphic and facsimile message or letters will be sufficient for this purpose.

(e) The Contractor shall, within 30 days after each shipment covered by this clause, provide the Contracting Officer and the Maritime Administration, Office of Cargo Preference, U.S. Department of Transportation, 400 Seventh Street SW., Washington, DC 20590, one copy of the rated on board vessel operating carrier's ocean bill of lading, which shall contain the following information:

(1) Prime contract number;

- (2) Name of vessel;
- (3) Vessel flag of registry;
- (4) Date of loading;
- (5) Port of loading;
- (6) Port of final discharge;
- (7) Description of commodity;
- (8) Gross weight in pounds and cubic feet if available;
- (9) Total ocean freight in U.S. dollars; and
- (10) Name of the steamship company.

(f) The Contractor shall provide with its final invoice under this contract a representation that to the best of its knowledge and belief--

- (1) No ocean transportation was used in the performance of this contract;
- (2) Ocean transportation was used and only U.S.-flag vessels were used for all ocean shipments under the contract;
- (3) Ocean transportation was used, and the Contractor had the written consent of the Contracting Officer for all non-U.S.-flag ocean transportation; or
- (4) Ocean transportation was used and some or all of the shipments were made on non-U.S.-flag vessels without the written consent of the Contracting Officer. The Contractor shall describe these shipments in the following format:

ITEM DESCRIPTION	CONTRACT LINE ITEMS	QUANTITY
_____	_____	_____
_____	_____	_____
_____	_____	_____
TOTAL	_____	_____

(g) If the final invoice does not include the required representation, the Government will reject and return it to the Contractor as an improper invoice for the purposes of the Prompt Payment clause of this contract. In the event there has been unauthorized use of non-U.S.-flag vessels in the performance of this contract, the Contracting Officer is entitled to equitably adjust the contract, based on the unauthorized use.

(h) In the award of subcontracts for the types of supplies described in paragraph (b)(2) of this clause, the Contractor shall flow down the requirements of this clause as follows:

- (1) The Contractor shall insert the substance of this clause, including this paragraph (h), in subcontracts that exceed the simplified acquisition threshold in part 2 of the Federal Acquisition Regulation.
- (2) The Contractor shall insert the substance of paragraphs (a) through (e) of this clause, and this paragraph (h), in subcontracts that are at or below the simplified acquisition threshold in part 2 of the Federal Acquisition Regulation.

(End of clause)

General Decision Number CA030001

General Decision Number CA030001

Superseded General Decision No. CA020001

State: California Construction Type:

BUILDING

DREDGING

HEAVY HIGHWAY

RESIDENTIAL

County(ies):

SAN DIEGO BUILDING CONSTRUCTION PROJECTS; DREDGING PROJECTS (does not include hopper dredge work); HEAVY CONSTRUCTION PROJECTS (does not include water well drilling); HIGHWAY CONSTRUCTION PROJECTS; RESIDENTIAL CONSTRUCTION PROJECTS (consisting of single family homes and apartments up to and including 4 stories)

Modification Number Publication Date

0 06/13/2003

COUNTY(ies):

SAN DIEGO ASBE0005B 08/05/2002

	Rates	Fringes
ASBESTOS WORKER/INSULATOR		
Includes the application of all insulating materials, protective coverings, coatings, & finishes to all types of mechanical systems	33.06	8.11

-----  
ASBE0005D 01/01/2003

	Rates	Fringes
ASBESTOS REMOVAL WORKER / HAZARDOUS MATERIAL HANDLER		
Includes preparation, wetting, stripping, removal, scrapping, vacuuming, bagging and disposing of all insulation materials from mechanical systems, whether they contain asbestos or not	15.75	2.55

-----  
BOIL0092F 10/01/2002

	Rates	Fringes
BOILERMAKER	31.96	13.30

-----  
BRCA0004M 11/01/2002

	Rates	Fringes
BRICKLAYER; MARBLE SETTER	36.00	7.20

-----  
BRCA0018E 02/01/2002

	Rates	Fringes
TILE LAYER	23.00	3.48
MARBLE AND TILE FINISHER	14.75	3.48

-----  
BRCA0018F 12/01/2000

	Rates	Fringes
TERRAZZO WORKER	26.78	5.34
TERRAZZO FINISHER	20.53	5.34

CARP0002B 07/01/2001		
	Rates	Fringes
DIVERS:		
Diver, wet	486.08 per day	5.61
Diver, stand-by	243.04 per day	5.61
Diver tender	235.04 per day	5.61
-----		
CARP0002L 07/01/2002		
	Rates	Fringes
CARPENTER:		
Residential/Light Commercial	19.68	6.68
Commercial Building	24.60	6.68
Bridge	28.78	6.68
MILLWRIGHT	29.15	6.68
PILEDRIIVER	28.78	6.68
-----		
CARP0002U 07/01/2001		
	Rates	Fringes
Work on wood framed construction of single family residences, apartments or condominiums under four (4) stories:		
DRYWALL INSTALLER/LATHER	19.00	5.18
DRYWALL STOCKER/SCRAPPER	9.28	5.42
All other work:		
DRYWALL INSTALLER/LATHER	18.55	6.43
DRYWALL STOCKER/SCRAPPER	9.28	5.42
-----		
CARP0003H 08/01/2002		
	Rates	Fringes
MODULAR FURNITURE INSTALLER	14.00	5.16
FULL WALL TECHNICIAN	20.14	5.16
MOBILE FILING SYSTEM INSTALLERS	13.10	4.66
-----		
ELEC0569A 12/01/2002		
	Rates	Fringes
All other residential and building construction:		
ELECTRICIAN	30.21	3%+6.67
CABLE SPLICER	30.96	3%+6.67
-----		
ELEC0569E 06/01/2001		
	Rates	Fringes
Work on family residences, single family homes, duplexes, condominiums, apartments that do not exceed three (3) stories:		
ELECTRICIAN	17.00	3.73
-----		
ELEC0569F 07/01/2001		
	Rates	Fringes
SOUND TECHNICIAN	19.98	3%+5.14
TELEPHONE INTERCONNECT TECHNICIAN	16.59	3%+5.14
SOUNDMAN	14.98	3%+4.22
SOUND TECHNICIAN: Terminating, operating and performing final check-out		

SOUNDMAN: Wire-pulling, splicing, assembling and installing devices

SCOPE OF WORK

Assembly, installation, operation, service and maintenance of components or systems as used in closed circuit television, amplified master television distribution, CATV on private property, intercommunication, burglar alarm, fire alarm, life support and all security alarms, private and public telephone and related telephone interconnect, public address, paging, audio, language, electronic, background music system less than line voltage or any system acceptable for class two wiring for private, commercial, or industrial use furnished by leased wire, frequency modulation or other recording devices, electrical apparatus by means of which electricity is applied to the amplification, transmission, transference, recording or reproduction of voice, music, sound, impulses and video. Excluded from this Scope of Work - transmission, service and maintenance of background music. All of the above shall include the installation and transmission over fiber optics.

-----  
ELEC0569G 07/01/2001

	Rates	Fringes
Work on street lighting; traffic signals; and underground systems and/or established easements outside of buildings:		

Utility technician #1	16.38	3%+2.99
Utility technician #2	10.56	3%+2.49

STREET LIGHT & TRAFFIC SIGNAL WORK:

UTILITY TECHNICIAN #1: Installation of street lights and traffic signals, including electrical circuitry, programmable controller, pedestal-mounted electrical meter enclosures and laying of pre-assembled cable in ducts. The layout of electrical systems and communication installation including proper position of trench depths, and radius at duct banks, location for manholes, street lights and traffic signals.

UTILITY TECHNICIAN #2: Distribution of material at jobsite, installation of underground ducts for electrical, telephone, cable TV land communication systems. The setting, leveling, grounding and racking of precast manholes, handholes and transformer pads.

-----  
ELEC0569H 07/01/2001

	Rates	Fringes
Tunnel work:		
ELECTRICIAN	27.30	3% + 6.47
CABLE SPLICER	28.25	3% + 6.47

-----  
ELEC1245A 06/01/2002

	Rates	Fringes
LINE CONSTRUCTION		
Lineman; Cable splicer	33.16	4.5%+7.08
Equipment specialist (operates crawler tractors, commercial motor vehicles, backhoes, trenchers, cranes (50 tons and below), and overhead and		

underground distribution line equipment)	28.19	4.5%+6.80
Groundman	21.56	4.5%+6.80
Powderman	31.51	4.5%+6.84

-----  
ELEV0018A 09/15/2001

	Rates	Fringes
ELEVATOR MECHANIC	33.695	7.455

## FOOTNOTE:

Vacation Pay: 8% with 5 or more years of service, 6% for 6 months to 5 years service. Paid Holidays: New Years Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day and Friday after, and Christmas Day.

-----  
ENGI0012B 06/16/2002

	Rates	Fringes
POWER EQUIPMENT OPERATORS:		

GROUP 1	27.85	11.85
GROUP 2	28.63	11.85
GROUP 3	28.92	11.85
GROUP 4	30.21	11.85
GROUP 5	30.43	11.85
GROUP 6	30.54	11.85
GROUP 7	30.66	11.85
GROUP 8	30.83	11.85
GROUP 9	30.93	11.85
GROUP 10	30.96	11.85
GROUP 11	31.04	11.85
GROUP 12	31.16	11.85
GROUP 13	31.33	11.85
GROUP 14	31.43	11.85
GROUP 15	31.54	11.85
GROUP 16	31.66	11.85
GROUP 17	31.83	11.85
GROUP 18	31.93	11.85
GROUP 19	32.04	11.85
GROUP 20	32.16	11.85
GROUP 21	32.33	11.85

## CRANES, PILEDRIVING &amp; HOISTING:

GROUP 1	29.00	11.85
GROUP 2	29.78	11.85
GROUP 3	30.07	11.85
GROUP 4	30.21	11.85
GROUP 5	30.43	11.85
GROUP 6	30.54	11.85
GROUP 7	30.66	11.85
GROUP 8	30.83	11.85
GROUP 9	31.00	11.85
GROUP 10	32.00	11.85
GROUP 11	33.00	11.85
GROUP 12	34.00	11.85
GROUP 13	35.00	11.85

## POWER EQUIPMENT OPERATORS - TUNNEL:

GROUP 1	30.28	11.85
GROUP 2	30.57	11.85
GROUP 3	30.71	11.85
GROUP 4	30.93	11.85

GROUP 5	31.04	11.85
GROUP 6	31.16	11.85
GROUP 7	31.46	11.85

FOOTNOTES: Premium pay of \$2.75 per hour shall be paid on all power equipment operator work within the boundaries of Camp Pendleton. Workers required to suit up and work in a hazardous material environment: \$1.00 per hour additional. Combination mixer and compressor operator on gunite work shall be classified as a concrete mobile mixer operator.

#### POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Bargeman; Brakeman; Compressor operator; Ditch witch, with seat or similar type equipment; Elevator operator-inside; Engineer oiler; Generator operator; Generator, pump or compressor plant operator; Pump operator; Signalman; Switchman

GROUP 2: Asphalt-rubber plant operator (nurse tank operator); Concrete mixer operator - skip type; Conveyor operator; Fireman; Hydrostatic pump operator; Oil crusher (asphalt or concrete plant); PJU side dump jack; Screening and Conveyor machine operator (or similar types); Skiploader (wheel up to 3/4 yd. without attachment); Tar pot fireman; Temporary heating plant operator; Trenching machine oiler

GROUP 3: Asphalt-rubber blend operator; Skid steer (loader; Equipment greaser (rack); Ford Ferguson (with dragtype attachments); Helicopter radioman (ground); Stationary pipe wrapping and cleaning machine operator

GROUP 4: Asphalt plant fireman; Backhoe operator (mini-max or similar type); Boring machine operator; Boxman or mixerman (asphalt or concrete), chip spreading machine operator;, Concrete cleaning decontamination machine operator; Concrete pump operator (small portable); Drilling machine operator, small auger types (Texoma super economatic or similar types - Hughes 100 or 200 or similar types - drilling depth of 30' maximum); Guard rail post driver operator; Highline cableway signalman; Horizontal directional drilling machine; Hydra-hammer-aero stomper; Micro Tunneling (above ground tunnel); Power concrete curing machine operator; Power concrete saw operator; Power -driven jumbo form setter operator; Power sweeper operator; Roller operator (compacting); Screed operator (asphalt or concrete); Trenching machine operator (up to 6 ft.)

Vacuum or muck truck

GROUP 5: Articulating material hauler; Asphalt plant engineer; Batch plant operator; Bit sharpener; Concrete joint machine operator (canal and similar type); Dandy digger; Concrete planer operator; Deck engine operator; Derrick (oilfield type); Drilling machine operator, bucket or auger types Calweld 100 bucket or similar types - Watson 1000 auger or similar types - Texoma 330, 500 or 600 auger or similar types - drilling depth of 45' maximum); Drilling machine operator (including water well drilling); Equipment greaser (grease truck), Hydrographic seeder machine operator (straw, pulp or seed); Jackson track maintainer, or similar type; Kalamazoo switch tamper, or similar type; Machine tool operator; Maginnis internal full slab vibrator; Mechanical berm, curb or gutter (concrete or asphalt), Mechanical finisher operator (concrete, Clary-Johnson-Bidwell or similar); Pavement breaker operator (truck mounted), Road oil mixing machine operator; Roller operator (asphalt or finish); Rubber-tired earth-moving equipment (single engine, up to and including



25 yds. struck), self-propelled tar pipelining machine operator; Skiploader operator (Crawler and wheel type, over 3/4 yd. and up to and including 1-1/2 yds.); Slip form pump operator (power driven hydraulic lifting device for concrete forms); Tractor operator-bulldozer, tamper-scraper (single engine, up to 100 h.p. flywheel and similar types, up to and including D-5 and similar types); Tugger hoist operator (1 drum); Ultra high pressure waterjet cutting tool system operator; Vacuum blasting machine operator

GROUP 6: Asphalt or concrete spreading operator (tamping or finishing); Asphalt paving machine operator (Barber-Greene or similar type); Asphalt-rubber distributor operator; Backhoe operator (up to and including 3/4 yd.), small Ford, Case or similar; Cast-in-place pipe laying machine operator; Combination mixer and compressor operator (gunite work); Compactor operator (self-propelled); Concrete mixer operator (paving); Crushing plant operator; Drill doctor; Drilling machine operator, bucket or auger types (Calweld 150 bucket or similar types - Watson 1500, 2000, 2500 auger or similar types - Texoma 700, 800 auger or similar types - drilling depth of 60' maximum); Elevating grader operator; Grade checker; Gradall operator; Grouting machine operator; Heavy-duty repairman; heavy equipment robotics operator; Kalamazoo balliste regulator or similar type; Kolman belt loader and similar type; Le Tourneau blob compactor or similar type; Loader operator (Athey, Euclid, Sierra and similar types); Ozzie padder or similar types; Pneumatic concrete placing machine operator (Hackley-Presswell or similar type); Pumpcrete gun operator; Rotary drill operator (excluding caisson type); Rubber-tired earth-moving equipment operator (single engine, Caterpillar, Euclid, Athey wagon and similar types with any and all attachments over 25 yds. up to and including 50 cu. yds. struck); Rubber-tired earth-moving equipment operator (multiple engine up to and including 25 yds. struck); Rubber-tired scraper operator (self-loading paddle wheel type - John Deere, 1040 and similar single unit); Self-propelled curb and gutter machine operator; skiploader operator (crawler and wheel type over 1-1/2 yds. up to and including 6-1/2 yds.); Soil remediation plant operator; Surface heaters and planer operator; Tractor compressor drill combination operator; Tractor operator (any type larger than D-5- 100 flywheel h.p. and over, or similar - bulldozer, tamper, scraper and push tractor, single engine); Tractor operator (boom attachments); Traveling pipe wrapping, cleaning and bending machine operator; Trenching machine operator (over 6 ft. depth capacity, manufacturer's rating); Ultra High pressure waterjet cutting tool system mechanic

GROUP 7: Drilling machine operator, bucket or auger types (Calweld 200 B bucket or similar types - Watson 3000 or 5000 auger or similar types - Texoma 900 auger or similar types - drilling depth of 105' maximum); Dual drum mixer; Dynamic compactor LDC350 (or similar types); Monorail locomotive operator (diesel, gas or electric); Motor patrol-blade operator (single-engine); Multiple-engine tractor operator (Euclid and similar type-except Quad 9 cat.); Pre-stressed wrapping machine operator; Rubber-tired earth-moving equipment operator (single-engine, over 50 yds. struck); Rubber-tired earth-moving equipment operator (multiple-engine, Euclid, caterpillar and similar over 25 yds. and up to 50 yds.); Tower crane repairman; Tractor loader

operator (Crawler and wheel type over 6-1/2 yds.); Woods mixer operator (and similar Pugmill equipment)

GROUP 8: Auto grader operator; Automatic slip form operator; Drilling machine operator, bucket or auger types (Calweld, auger 200 CA or similar types - Watson auger 6000 or similar types - drilling depth of 175' maximum); Hoe ram or similar with compressor; Mass excavator operator (less than 750 cu. yds.); Mechanical finishing machine operator; Mobile form traveler operator; Motor patrol operator (multi-engine); Pipe mobile machine operator; Rubber-tired earth-moving equipment operator (multiple-engine, Euclid, caterpillar and similar type, over 50 cu. yds. struck), Rubber-tired self-loading scraper operator (paddle-wheel auger type self-loading-two (2) or more units)

GROUP 9: Rubber-tired earth-moving equipment operator operating equipment with push-pull system, (single-engine, up to and including 25 yds. struck)

GROUP 10: Canal liner operator; Canal trimmer operator; Remote-control earth-moving equipment operator (operating a second piece of equipment: \$1.00 per hour additional); wheel excavator operator (over 750 cu. yds.)

GROUP 11: Rubber-tired earth-moving equipment operator, operating equipment with push-pull system (single engine, caterpillar, Euclid, Athey wagon, and similar types with any and all attachments over 25 yds. and up to and including 50 yds. struck); Rubber-tired earth-moving equipment operator, operating equipment with push-pull system (multiple-engine - up to and including 25 yds. struck)

GROUP 12: Rubber-tired earth-moving equipment operator, operating equipment with push-pull system (single-engine, over 50 yds. struck); Rubber-tired earth-moving equipment operator, operating equipment with push-pull system (multiple-engine, Euclid, caterpillar and similar, over 25 yds. and up to 50 yds. struck)

GROUP 13: Rubber-tired earth-moving equipment operator, operating equipment with push-pull system (multiple-engine, Euclid, caterpillar and similar, over 50 cu. yds. struck); Tandem tractor operator (operating crawler-type tractors in tandem-Quad 9 and similar type)

GROUP 14: Rubber-tired earth-moving equipment operator, operating in tandem (scrapers, belly dumps and similar types in any combination, excluding compaction units-single engine, up to and including 25 yds. struck)

GROUP 15: Rotex concrete belt operator (or similar type); Rubber-tired earth-moving equipment operator, operating in tandem (scrapers, belly dumps and similar types in any combination, excluding compaction units - single-engine, caterpillar, Euclid, Athey wagon and similar types with any and all attachments over 25 yds. and up to and including 50 cu. yds. struck); Rubber-tired earth-moving equipment operator, operating in tandem (scrapers, belly dumps and similar types in any combination, excluding compaction units - multiple-engine, up to and including 25 yds. struck)

GROUP 16: Rubber-tired earth-moving equipment operator, operating in tandem (scrapers, belly dumps and similar types in any combination, excluding compaction units - single-engine, over 50 yds. struck), rubber-tired earth-moving equipment operator, operating in tandem (scrapers, belly dumps, and similar types in

any combination, excluding compaction units - multiple engine, Euclid, caterpillar and similar, over 25 yds. and up to 50 yds. struck)

GROUP 17: Rubber-tired earth-moving equipment operator, operating in tandem (scrapers, belly dumps and similar types in any combination, excluding compaction units - multiple-engine, Euclid, caterpillar and similar, over 50 cu. yds. struck)

GROUP 18: Rubber-tired earth-moving equipment operator, operating equipment with the tandem push-pull system (single engine, up to and including 25 yds. struck)

GROUP 19: Rubber-tired earth-moving equipment operator, operating equipment with the tandem push-pull system (single-engine, caterpillar, Euclid, Athey wagon and similar types with any and all attachments over 25 yds. and up to and including 50 yds. struck); Rubber-tired earth-moving equipment operator, operating with the tandem push-pull system (multiple-engine, up to and including 25 yds. struck)

GROUP 20: Rubber-tired earth-moving equipment operator, operating equipment with the tandem push-pull system (single-engine, over 50 yds. struck); Rubber-tired earth-moving equipment operator, operating equipment with the tandem push-pull system (multiple engine, Euclid, caterpillar and similar, over 25 yds. and up to 50 yds. struck)

GROUP 21: Concrete pump operator-truck mounted; Rubber-tired earth-moving equipment operator, operating equipment with the tandem push-pull system (multiple-engine, Euclid, caterpillar and similar type, over 50 cu. yds. struck)

#### CRANES, PILEDRIVING AND HOISTING CLASSIFICATIONS

GROUP 1: Engineer oiler, fork lift operator (includes loed, lull or similar types)

GROUP 2: Truck crane oiler

GROUP 3: A-frame or winch truck operator, Ross carrier operator (jobsite)

GROUP 4: Bridge-type unloader and turntable operator, helicopter hoist operator

GROUP 5: Stinger crane (Austin-Western or similar type), tugger hoist operator (1 drum)

GROUP 6: Bridge crane operator, Cretor crane operator, hoist operator (Chicago boom and similar type), lift mobile operator, lift slab machine operator (Vagtborg and similar types), material hoist operator, polar gantry crane operator, shovel, backhoe, dragline, clamshell operator (over 3/4 yd. and up to 5 cu. yds. mrc), tugger hoist operator (2 drum)

GROUP 7: Pedestal crane operator; Shovel, backhoe, dragline, clamshell operator (over 5 cu. yds. mrc), tower crane repair, tugger hoist operator (3 drum)

GROUP 8: Crane operator (up to and including 25 ton capacity), crawler transporter operator, derrick barge operator (up to and including 25 ton capacity), hoist operator, stiff legs, Guy derrick or similar type (up to and including 25 ton capacity), shovel, backhoe, dragline, clamshell operator (over 7 cu. yds. mrc)

GROUP 9: Crane operator (over 25 tons and up to and including 50 tons mrc), derrick barge operator (over 25 tons up to and including 50 tons mrc), highline cableway operator, hoist operator, stiff legs, Guy derrick or similar type (over 25 tons up to and including 50 tons mrc), K-crane operator, polar crane

operator

GROUP 10: Crane operator (over 50 tons and up to and including 100 tons mrc), derrick barge operator (over 50 tons up to and including 100 tons mrc), hoist operator, stiff legs, Guy derrick or similar type (over 50 tons up to and including 100 tons mrc), mobile tower crane operator (over 50 tons, up to and including 100 ton M.R.C.), tower crane operator and tower gantry

GROUP 11: Crane operator (over 100 tons and up to and including 200 tons mrc), derrick barge operator (over 100 tons up to and including 200 tons mrc), hoist operator, stiff legs, Guy derrick or similar type (over 100 tons up to and including 200 tons mrc), mobile tower crane operator (over 100 tons up to and including 200 tons mrc)

GROUP 12: Crane operator (over 200 tons up to and including 300 tons mrc), derrick barge operator (over 200 tons up to and including 300 tons mrc), hoist operator, stiff legs, Guy derrick or similar type (over 200 tons, up to and including 300 tons mrc), mobile tower crane operator (over 200 tons, up to and including 300 tons mrc)

GROUP 13: Crane operator (over 300 tons), derrick barge operator (over 300 tons), helicopter pilot, hoist operator, stiff legs, Guy derrick or similar type (over 300 tons), mobile tower crane operator (over 300 tons)

#### TUNNEL CLASSIFICATIONS

GROUP 1: Skiploader (wheel type up to 3/4 yd. without attachment)

GROUP 2: Power-driven jumbo form setter operator

GROUP 3: Dinkey locomotive or motorperson (up to and including 10 tons)

GROUP 4: Bit sharpener; Equipment greaser (grease truck); Slip form pump operator (power-driven hydraulic lifting device for concrete forms; Tugger hoist operator (1 drum); Tunnel locomotive operator (over 10 and up to and including 30 tons)

GROUP 5: Backhoe operator (up to and including 3/4 yd.); Small Ford, Case or similar; Drill doctor; Grouting machine operator; Heading shield operator; Heavy-duty repair person; Loader operator (Athey, Euclid, Sierra and similar types); Mucking machine operator (1/4 yd., rubber-tired, rail or track type); Pneumatic concrete placing machine operator (Hackley-Presswell or similar type); Pneumatic heading shield (tunnel); Pumpcrete gun operator; Tractor compressor drill combination operator; Tugger hoist operator (2 drum); Tunnel locomotive operator (over 30 tons)

GROUP 6: Heavy-duty repairman

GROUP 7: Tunnel mole boring machine operator

-----  
ENGI0012D 08/01/2002

	Rates	Fringes
POWER EQUIPMENT OPERATORS:		
DREDGING:		
Leverman	34.65	11.85
Dredge dozer	31.18	11.85
Deckmate	31.07	11.85
Winch operator (stern winch on dredge)	30.52	11.85
Fireman; deckhand and bargeman	29.98	11.85
Barge mate	30.59	11.85

-----  
 IRON0001F 07/01/2002

	Rates	Fringes
IRONWORKERS:		
Fence erector	26.97	16.29
Ornamental, reinforcing and structural	26.86	16.29

FOOTNOTE: Work at San Clemente Island additional \$3.00 per hour.  
 -----

LABO0089A 07/01/2002

	Rates	Fringes
LABORERS:		
Wood or metal frame construction of single family residences, apartments and condominiums - excluding		
(a) projects that exceed three stories over a garage level,		
(b) any utility work such as telephone, gas, water, sewer and other utilities and		
(c) any fine grading work, utility work or paving work in the future street and public right-of-way; but including all rough grading work at the job site behind the existing right of way:		
Cleanup, landscaping, fencing (chain link and wood)	18.49	5.58
Other work on such projects	19.49	5.58

## OTHER RESIDENTIAL AND BUILDING CONSTRUCTION

## LABORERS:

GROUP 1	20.87	7.68
GROUP 2	21.42	7.68
GROUP 3	21.97	7.68
GROUP 4	23.52	7.68
GROUP 5	23.87	7.68

## LABORER CLASSIFICATIONS

GROUP 1: Cleaning and handling of panel forms; Concrete Screeding for Rought Strike-off; Concrete, water curing; Demolition laborer; Flagman; Gas, oil and/or water pipeline laborer; General Laborer; General clean-up laborer; Landscape laborer; Jetting laborer; Temporary water and air lines laborer; Material hoseman (walls, slabs, floors and decks); Plugging, filling of Shee-bolt holes; Dry packing of concrete; Railroad maintenance, Repair Trackman and road beds, Streetcar and railroad construction trac laborers; Slip form raisers; Slurry seal crews (mixer operator, applicator operator, squeegee man, Shuttle man, top man), filing of cracks by any method on any surface; Tarman and mortar man; Tool crib or tool house laborer; Window cleaner; Wire Mesh puling-all concrete pouring operations

GROUP 2: Asphalt Shoveler; Cement Dumper (on 1 yard or larger mixer and handling bulk cement); Cesspool digger and installer; Chucktender; Chute man, pouring concrete, the handling of the cute from ready mix trucks, such as walls, slabs, decks, floors, foundations, footings, curbs, gutters and sidewalks; Concrete curer-impervious membrane and form oiler; Cutting torch operator (demoliton); Guinea chaser; Headboard man-asphlt; Laborer,

packing rod steel and pans; membrane vapor barrier installer; Power broom sweepers (small); Riiprap, stonepaver, placing stone or wet sacked concrete; Roto scraper and tiller; Tank sealer and cleaner; Tree climber, faller, chain saw operator, Pittsburgh Chipper and similar type brush shredders; Underground laborers, including caisson bellow

GROUP 3: Buggymobile; Concrete cutting torch; Concrete cutting torch; Concrete pile cutter; Driller, jackhammer, 2 1/2 feet drill steel or longer; Dri Pak-it machine; High sealer (including drilling of same); Hydro seeder and similar type; Impact wrench, multi-plate; Kettlemen, potmen and men applying asphalt, lay-kold, creosote, line caustic and similar type materials (applying means applying, dipping, brushing or handling of such materials for pipe wrapping and waterproofing); Operators of pneumatic, gas, electric tools, vibrating machines, pavement breakers, air blasting, come-along, and similar mechanical tools not separately classified herein; Pipelayers back up man coating, grouting, making of joints, sealing, caulking, diapering and including rubber gasket joints, pointing and any and all other services; Rotary Scarifier or multiple head concrete chipping scarifier; Steel header board man and guideline setter; Tampers, Barko, Wacker and similar type; Trenching machine, hand propelled

GROUP 4: Asphalt raker, luterman, ironer, asphalt dumpman and asphalt spreader boxes (all types); Concrete core cutter (walls, floors or ceilings), Grinder or sander; Concrete saw man; cutting walls or flat work, scoring old or new concrete; Cribber, shorer, lagging, sheeting and trench bracing, hand-guided lagging hammer; Laser beam in connection with laborer's work; Oversize concrete vibrator operator 70 pounds and over; Pipelayer performing all services in the laying, installation and all forms of connection of pipe from the point of receiving pipe in the ditch until completion of operation, including any and all forms of tubular material, whether pipe, metallic or non-metallic, conduit, and any other stationary type of tubular device used for the conveying of any substance or element, whether water, sewage, solid, gas, air or other product whatsoever and without regard to the nature of material from which the tubular material is fabricated; No joint pipe and stripping of same; Prefabricated manhole installer; Sandblaster (nozzleman), Porta shot-blast, water blasting

GROUP 5: Blasters Powderman-All work of loading holes, placing and blasting of all powder and explosives of whatever type, regardless of method used for such loading and placing; Driller-all power drills, excluding jackhammer, whether core, diamond, wagon, track, multiple unit, and any and all other types of mechanical drills without regard to the form of motive power.

-----  
LABO0089B 05/01/2002

	Rates	Fringes
BRICK TENDER	19.00	8.24

FOOTNOTES: Work on refractory stack work in excess of 100 ft. in height: fifty cents (\$0.50) per hour additional.

Work on refractory work where extreme heat prevents continuous work: fifty (\$0.50) per hour additional.

Work with carbon brick, acid brick or phenolic mortar: fifty (\$0.50) per hour additional.

Work on a swinging scaffold above fifty ft.: thirty-five cents (\$0.35) per hour additional.

---

LABO0089C 08/07/2002		
	Rates	Fringes
RESIDENTIAL CONSTRUCTION (excluding North Island Naval Air Station, Coronado Naval Amphibious Base and Imperial Beach Naval Air Station)		
Work on single family homes, apartments and condominiums not exceeding three stories:		
PLASTER TENDER	21.00	10.17
PLASTER CLEAN-UP TENDER LABORER	18.45	10.17
ALL OTHER RESIDENTIAL AND BUILDING CONSTRUCTION:		
PLASTER TENDER	23.00	10.17
PLASTER CLEAN-UP LABORER	20.45	10.17
North Island Naval Air Station, Coronado Naval Amphibious Base and Imperial Beach Naval Air Station)		
Work on single family homes, apartments and condominiums not exceeding three stories:		
PLASTER TENDER	24.00	10.17
PLASTER CLEAN-UP TENDER LABORER	20.45	10.17
ALL OTHER RESIDENTIAL CONSTRUCTION AND BUILDING CONSTRUCTION1		
PLASTER TENDER	26.00	10.17
PLASTER CLEAN-UP TENDER LABORER	23.45	10.17

---

LABO0089D 07/01/2002		
	Rates	Fringes
HEAVY AND HIGHWAY CONSTRUCTION LABORERS:		
GROUP 1	20.85	7.58
GROUP 2	21.20	7.58
GROUP 3	21.45	7.58
GROUP 4	21.85	7.58
GUNITE WORK:		
GROUP 1	18.91	7.18
GROUP 2	19.21	7.18
GROUP 3	19.41	7.18
TUNNEL WORK:		
GROUP 1	19.21	7.18
GROUP 2	19.41	7.18
GROUP 3	19.66	7.18
GROUP 4		

#### LABORER CLASSIFICATIONS

GROUP 1: Laborer (general construction); Asphalt ironer - spreader; Boring machine tender; Carpenter tender; Caulker; Cesspool digger and installer; Chucktender (except tunnels); Concrete curer (impervious membrane and form oiler); Concrete water curing (excluding use of water trucks); Cutting torch operator (demolition); Driller's tender (caisson) including bellows; Dri-pak-it machine, concrete cutting torch; Dry packing of concrete, plugging, filling of shee bolt holes; Fence

erector; Fine grader on highways, streets and airport paving (sewer and drainage lines when employed); Flag person; Form blower; Gas and oil pipeline laborer; Guinea chaser; Housemover; Jet; Landscape gardener and nursery; Packing rod steel and pans; Pipelayer's backup (coating, grouting, making of joints, sealing, caulking, diapering and including rubber gasket joints, pointing and any and all other service railroad work); Laborer; Rigging and signaling; Riprap stonepaver; Sandblaster (pot tender); Scaler; Septic tank digger and installer (lead); Tank scaler and cleaner; Tool shed checker; Window cleaner

GROUP 2: Buggymobile; Cement dumper (on 1 yd. or larger mixers and handling bulk cement); Concrete saw (excluding tractor type), roto-scraper, chipping hammer, concrete core cutter, concrete grinder and sander; Cribber - shorer, lagging and trench bracing, hand-guided lagging hammer; Driller - all power drills, including jackhammer, whether Core, Diamond, Wagon, Track, multiple unit, and all types of mechanical drills without regard to the form of motive power; Driller (all other where drilling is for use of explosives); Gas and oil pipeline wrapper (pot tender and form); Gas and oil pipeline wrapper (6-inch pipe and over); Operator and tender of pneumatic, gas and electric tools, concrete pumps, vibrating machines, multi-plate impact wrench and similar mechanical tools not separately classified herein; Pipelayer (excludes all pressurized and vacuum piping) (performing all services outside the building line in the laying and installation of pipe from the point of receiving pipe until completion of the operation, including any and all forms of tubular material, whether pipe, metallic or non-metallic conduit and any other stationary type of tubular device used for the conveying of any substance or element, whether water, sewage, solid, gas, air or other products whatsoever and without regard to the nature of material from which the tubular material is fabricated); Powder blasters' tender; Prefabricated manhole installer; Rock slinger; Sandblaster, waterblaster & nozzle operator); Scaler (using bos'n chair, safety belt); Steel headerboard; Tree climber, using mechanical tools; Welding in connection with laborer's work

GROUP 3: Asphalt raker; Layton box spreader (or similar type)

GROUP 4: Blasters Powderman-All work of loading holes, placing and blasting of all powder and explosives of whatever type, regardless of method used for such loading and placing

#### GUNITE LABORER CLASSIFICATIONS

GROUP 1: Rebound man

GROUP 2: Gun man

GROUP 3: Nozzle man

#### TUNNEL LABORER CLASSIFICATIONS

GROUP 1: Bull gang, mucker, track; Chucktender, cabletender; Concrete crew (includes rodder and spreader); Dump; Grout crew; Tender for steel form raisers and setters; Mucker - tunnel (hand or machine); Nipper; Swamper (brake and switch on tunnel work); Vibrator, jackhammer, pneumatic tools (except driller) multi-plate impact wrench

GROUP 2: Blaster, driller, powder; Cherry picker; Grout gun; Kemper and other pneumatic concrete placer operator; Miner in short dry tunnels under streets, highways and similar places; Miner - tunnel (hand or machine); Powder (tunnel work); Steel form raiser and setter; Timber, retimber wood or steel



GROUP 3: Powder - primer house (licensed) on tunnel work; Shaft and raise miner; Shifter; Blaster (licensed) all work of loading holes, placing & blasting all powder & explosives of whatever type regardless of method used for such loading and placing

-----  
LABO0882A 01/01/2003

	Rates	Fringes
ASBESTOS REMOVAL LABORER	22.00	7.90
SCOPE OF WORK: includes site mobilization, initial site clean-up, site preparation, removal of asbestos-containing material and toxic waste (including lead abatement and any other toxic materials), encapsulation, enclosure and disposal of asbestos-containing materials and toxic waste (including lead abatement and any other toxic materials) by hand or with equipment or machinery; scaffolding, fabrication of temporary wooden barriers, and assembly of decontamination stations.		

-----  
LABO1184A 07/01/2002

	Rates	Fringes
LABORERS - STRIPING:		
GROUP 1	20.65	8.42
GROUP 2	21.50	8.42
GROUP 3	23.82	8.42
GROUP 4	26.02	8.42

LABORERS - STRIPING CLASSIFICATIONS

GROUP 1: Protective coating, pavement sealing, including repair and filling of cracks by any method on any surface in parking lots, game courts and playgrounds; carstops; operation of all related machinery and equipment; equipment repair technician

GROUP 2: Traffic surface abrasive blaster; pot tender - removal of all traffic lines and markings by any method (sandblasting, waterblasting, grinding, etc.) and preparation of surface for coatings. Traffic control person: controlling and directing traffic through both conventional and moving lane closures; operation of all related machinery and equipment

GROUP 3: Traffic delineating device applicator: Layout and application of pavement markers, delineating signs, rumble and traffic bars, adhesives, guide markers, other traffic delineating devices including traffic control. This category includes all traffic related surface preparation (sandblasting, waterblasting, grinding) as part of the application process. Traffic protective delineating system installer: removes, relocates, installs, permanently affixed roadside and parking delineation barricades, fencing, cable anchor, guard rail, reference signs, monument markers; operation of all related machinery and equipment; power broom sweeper

GROUP 4: Striper: layout and application of traffic stripes and markings; hot thermo plastic; tape traffic stripes and markings, including traffic control; operation of all related machinery and equipment

-----  
PAIN0036D 07/01/2002

	Rates	Fringes
BUILDING AND HEAVY CONSTRUCTION:		
PAINTER (includes lead abatement)	25.02	5.89
RESIDENTIAL CONSTRUCTION		

PAINTER (includes lead abatement)	18.40	4.65
-----		
PAIN0036K 10/01/2002		
	Rates	Fringes
RESIDENTIAL CONSTRUCTION: Applies to work performed on exterior and interior wood framing apartments, single family homes and multi-duplexes up to and including four stories:		
DRYWALL FINISHER	18.00	4.26
All other residential work:		
DRYWALL FINISHER	20.40	7.28
BUILDING AND HEAVY CONSTRUCTION: DRYWALL FINISHER	20.40	7.28
-----		
PAIN0036N 01/01/2003		
	Rates	Fringes
GLAZIERS	27.35	8.69
GLASSWORKER	16.16	4.05
-----		
PAIN0036V 01/01/2003		
	Rates	Fringes
SOFT FLOOR LAYER	19.32	6.65
-----		
PLAS0200E 08/07/2002		
	Rates	Fringes
NORTH ISLAND NAVAL AIR STATION; COLORADO NAVAL AMPHIBIOUS BASE; IMPERIAL BEACH NAVAL AIR STATION:		
PLASTERER	29.77	6.76
REMAINDER OF COUNTY:		
PLASTERER	26.77	6.76
-----		
PLAS0500A 06/30/2002		
	Rates	Fringes
Work shall include work inside the building line, meeting the following criteria:		
(1) a residential wood frame project of any size		
(2) work classified as Type III, IV or Type V construction		
(3) interior tenant improvement work regardless the size of the project		
(4) Any wood frame project of four stories or less		
CEMENT MASON	21.97	4.80
(5) work classified as type I and II construction		
CEMENT MASONS	23.62	4.80
-----		
PLAS0500E 06/16/2002		
	Rates	Fringes

## ALL OTHER WORK:

CEMENT MASONS	25.57	5.33
-----		
PLUM0016F 07/01/2002		
	Rates	Fringes
Work on strip malls, light commercial, tenant improvement and remodel work		
PLUMBER; PIPEFITTER; STEAMFITTER	23.03	8.24
Work on new additions and remodeling of single family homes, bars, restaurants, stores and commercial buildings, not to exceed 5,000 sq. ft. of floor space		
PLUMBER; PIPEFITTER; STEAMFITTER	28.92	9.44
All other work:		
Camp Pendleton:		
PLUMBER; PIPEFITTER; STEAMFITTER; AIR		
CONDITIONING & REFRIGERATION	32.06	10.01
Remainder of County		
PLUMBER; PIPEFITTER; STEAMFITTER	29.81	10.01
LANDSCAPE AND IRRIGATION WORK		
PLUMBER; PIPEFITTER	23.27	9.56
SEWER AND STORM DRAIN WORK		
PLUMBER; PIPEFITTER	20.25	9.75
-----		
PLUM0016K 07/01/2002		
	Rates	Fringes
WORK PERFORMED ON THE FOLLOWING STRUCTURES:		
a. One or two family dwellings		
b. All multiple family dwelling units which are permitted to have a single exterior up to and including four stories; and		
c. Townhouses, condominiums or similar structures with units stacked vertically up to and including four stories		
PLUMBERS AND PIPEFITTERS	24.31	7.42
-----		
PLUM0345A 07/01/2002		
	Rates	Fringes
LANDSCAPE & IRRIGATION FITTER	23.27	9.56
-----		
ROOF0045B 07/01/2002		
	Rates	Fringes
ROOFERS	21.20	3.88
-----		
SFCA0669A 04/01/2003		
	Rates	Fringes
SPRINKLER FITTER (FIRE)	27.05	6.10
-----		
SHEE0206A 08/01/2002		

	Rates	Fringes
CAMP PENDLETON		
a. Existing residential buildings, both single and multi-family, where each unit is heated and/or cooled by a separate system		
b. New single family residential buildings including tracts.		
c. New multi-family residential buildings, not exceeding five stories of living space in height, provided each unit is heated or cooled by a separate system. Hotels and motels are excluded.		
d. LIGHT COMMERCIAL WORK: Any sheet metal, heating and air conditioning work performed on a project where the total construction cost, excluding land, is under \$1,000,000		
e. TENANT IMPROVEMENT WORK: Any work necessary to finish interior spaces to conform to the occupants of commercial buildings, after completion of the building shell		
SHEETMETAL TECHNICIAN	17.83	2.52
All other Work		
SHEETMETAL WORKER	27.90	11.00
REMAINDER OF COUNTY		
a. Existing residential buildings, both single and multi-family, where each unit is heated and/or cooled by a separate system		
b. New single family residential buildings including tracts.		
c. New multi-family residential buildings, not exceeding five stories of living space in height, provided each unit is heated or cooled by a separate system. Hotels and motels are excluded.		
d. LIGHT COMMERCIAL WORK Any sheet metal, heating and air conditioning work performed on a project where the total construction cost, excluding land, is under \$1,000,000		
e. TENANT IMPROVEMENT WORK: Any work necessary to finish interior spaces to conform to the occupants of commercial buildings, after completion of the building shell		
SHEETMETAL TECHNICIAN	17.83	2.42
All other Work		

SHEETMETAL WORKER	25.90	11.00
-----		
TEAM0036A 06/01/2002		
	Rates	Fringes
TRUCK DRIVERS:		
GROUP 1	10.76	11.12
GROUP 2	20.35	11.12
GROUP 3	20.55	11.12
GROUP 4	20.75	11.12
GROUP 5	20.95	11.12
GROUP 6	21.45	11.12
GROUP 7	22.95	11.12

FOOTNOTE: HAZMAT PAY: Work on a hazmat job, where hazmat certification is required, shall be paid, in addition to the classification working in, as follows: Levels A, B and C - +\$1.00 per hour. Workers shall be paid hazmat pay in increments of four (4) and eight (8) hours.

#### TRUCK DRIVER CLASSIFICATIONS

GROUP 1: Swamper; fuel person (fueler without trucks)

GROUP 2: Two-axle dump trucks; two-axle flat bed; bunkerman concrete pumping truck; industrial lift truck; forklift under 15,000 lbs

GROUP 3: Two-axle water truck; three-axle dump truck; three-axle flat bed; erosion control nozzleman; dumpcrete truck less than 6 1/2 yd00; forklift 15,000 lbs. and over; Prell truck; pipeline work truck driver; road oil spreader, cement distributor or slurry driver; bootman; Ross carrier

GROUP 4: Off-road dump trucks under 35 tons mfg rated capacity; four axles but less than seven axles; low-bed truck and trailer; transit mix trucks under 8 yds.; three axle water trucks; erosion control drive; grout mixer truck; dumpcrete, 6-1/2 yds. and over; dumpster trucks; DW 10's, 20's and over; fuel truck and dynamite; truck greaser; truck mounted mobile sweeper; winch truck, two axles

GROUP 5: Off-road dump trucks 35 tons and over mfg rated capacity; 7 axles or more; transit mix trucks 8 yds. and over; A-frame trucks or Swedish crane; tireman, winch truck 3 axles or more

GROUP 6: Off-road special equipment (including but not limited to water pull tankers, Athey wagons, DJB, B70 Euclids or like equipment)

GROUP 7: Repairman

-----  
WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29 CFR 5.5(a)(1)(ii)).

-----

In the listing above, the "SU" designation means that rates listed under that identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations  
Wage and Hour Division  
U. S. Department of Labor  
200 Constitution Avenue, N. W.  
Washington, D. C. 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator  
U.S. Department of Labor  
200 Constitution Avenue, N. W.  
Washington, D. C. 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board  
U. S. Department of Labor  
200 Constitution Avenue, N. W.  
Washington, D. C. 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

General Decision Number CA030006

General Decision Number CA030006  
 Superseded General Decision No. CA020006  
 State: California Construction Type:  
 HOPPER DREDGE WORK  
 County(ies):  
 STATEWIDE  
 HOPPER DREDGE CONSTRUCTION PROJECTS  
 Modification Number Publication Date  
 0 06/13/2003

COUNTY(ies):  
 STATEWIDE  
 SUCA5005B 01/01/1985

	Rates	Fringes
SELF-PROPELLED HOPPER DREDGE:		
Drag tender	8.78	4.23

FOOTNOTE:

Nine paid holidays: New Year's Day, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Paul Hall's Birthday (Aug. 20th), Veterans Day, Thanksgiving Day and Christmas Day.

-----  
 Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29 CFR 5.5(a)(1)(ii)).  
 -----

In the listing above, the "SU" designation means that rates listed under that identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations  
 Wage and Hour Division  
 U. S. Department of Labor  
 200 Constitution Avenue, N. W.

Washington, D. C. 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator  
U.S. Department of Labor  
200 Constitution Avenue, N. W.  
Washington, D. C. 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board  
U. S. Department of Labor  
200 Constitution Avenue, N. W.  
Washington, D. C. 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION



SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01200

GENERAL REQUIREMENTS

07/03

PART 1 GENERAL

- 1.1 APPLICABLE PUBLICATIONS
- 1.2 SUBMITTALS
- 1.3 PROJECT SIGNS AND BULLETIN BOARDS
  - 1.3.1 General
  - 1.3.2 Construction Signs
    - 1.3.2.1 Materials
    - 1.3.2.2 Execution
  - 1.3.3 Bulletin Board at the Contractor's office
  - 1.3.4 Maintenance and Disposal
- 1.4 GOVERNMENT FIELD OFFICE
- 1.5 PUBLIC UTILITIES
  - 1.5.1 General
  - 1.5.2 Utilities To be Relocated or Protected
  - 1.5.3 Relocation or Removal
  - 1.5.4 Coordination
  - 1.5.5 Utilities Not Shown
  - 1.5.6 Electric Current
- 1.6 NOTICES
  - 1.6.1 Oceanside Harbor
  - 1.6.2 Traffic Routing
  - 1.6.3 Existing Bench Marks and R/W Markers
  - 1.6.4 United States Coast Guard
  - 1.6.5 Discharge Pipeline
- 1.7 POINTS OF CONTACT
- 1.8 AIDS TO NAVIGATION
- 1.9 DREDGING AIDS
- 1.10 RESTRICTIONS
  - 1.10.1 Dredging of Del Mar Channel
  - 1.10.2 Pipeline and Power Line Crossings
  - 1.10.3 Disposal
  - 1.10.4 Construction Vehicles
  - 1.10.5 Obstruction of Channel
  - 1.10.6 Booster Pump
  - 1.10.7 Method of Dredging
- 1.11 MARINE PLANT
- 1.12 PUBLIC SAFETY
- 1.13 GENERAL SAFETY REQUIREMENTS
  - 1.13.1 General
  - 1.13.2 Job Hazard Analysis
- 1.14 SIGNAL LIGHTS
- 1.15 RADIO COMMUNICATION
- 1.16 PERMITS
- 1.17 REPAIR OF STREETS, ACCESS ROADS, AND WORK AREAS
- 1.18 INSPECTION

1.19	NAVIGATION
1.20	WORK AREAS AND EASEMENTS
1.21	CORPS OF ENGINEERS RESERVE FLEET (CERF) IMPLEMENTATION
1.22	TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER
1.23	ENTRANCE CHANNEL WAVE CONDITIONS
1.24	CONTRACTOR MOORING AREA
1.25	COORDINATION WITH OTHER CONSTRUCTION
1.26	OCEANSIDE ANNUAL TRIATHLON
PART 2	MATERIALS (NOT APPLICABLE)
PART 3	EXECUTION (NOT APPLICABLE)

-- End of Section Table of Contents --

## SECTION 01200

## GENERAL REQUIREMENTS

07/03

## PART 1 GENERAL

## 1.1 APPLICABLE PUBLICATIONS

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

## CODE OF FEDERAL REGULATIONS (CFR)

CFR 29	Part 1926	Safety and Health Regulations for Construction
CFR 33	Part 80	Colregs Demarcation Lines
CFR 33	Part 156	Oil and Hazardous Material Transfer Operations

## CORPS OF ENGINEERS (COE)

EM 385-1-1	(1996) Safety and Health Requirements Manual
ER 415-1-5-89	Construction Time Extensions for Weather

## DEPARTMENT OF COMMERCE (DOC)

DOC PS 1	(1983) Construction and Industrial Plywood
DOC PS 20-70	American Softwood Lumber Standard

## FEDERAL SPECIFICATIONS (FS)

FS FF-B-575	(Rev C) Bolts, Hexagon and Square
FS FF-N-105	(Rev B; Int Am 4) Nails, Brads, Staples and Spikes: Wire, Cut and Wrought
FS FF-N-836	(Rev D; Am 2) Nut: Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding and Single Ball Seat
FS TT-E-529	(Rev D) Enamel, Alkyd, Semi-Gloss
FS TT-P-25	(Rev E; Am 2) Primer Coating, Exterior (Undercoat for Wood, Ready-Mixed, White and Tints)

## 1.2 SUBMITTALS

Government approval is required for all submittals with a "GA" designation; submittals having an "FIO" designation are for information only. The following shall be submitted in accordance with Section 01330 SUBMITTAL

## PROCEDURES:

## SD-01 Preconstruction Submittals

Work and Storage Areas Plan; G

Site Safety Health Plan; G

Job Hazards Safety Analysis; G

## 1.3 PROJECT SIGNS AND BULLETIN BOARDS

## 1.3.1 General

The Contractor shall construct and erect a project sign and hard hat sign and a bulletin board at respective locations designated by the Contracting Officer. The signs shall conform to the requirements of the drawings attached at the end of this section. Signs shall be erected as soon as possible and within 5 days after commencement of work under this contract.

## 1.3.2 Construction Signs

## 1.3.2.1 Materials.

Lumber shall conform to DOC PS 20-70, and shall be seasoned Douglas Fir, S4S, Grade D or better except that posts, braces and spacers shall be construction Grade (WCLB).

Plywood shall conform to DOC PS 1, grade AC, Group 1, Exterior.

Bolts, Nuts and Nails. Bolts and nuts shall be galvanized conform to FS FF-B-575 and FS FF-N-836. Nails shall conform to FS FF-N-105.

Paints and Oils. Paints shall conform to FS TT-P-25 for primer and FS TT-E-529 for finish paint and lettering.

## 1.3.2.2 Execution.

The following signs shall be erected:

Project Sign at location designated by the Contracting Officer.

Warning Signs facing approaching traffic on all haul roads crossing under overhead power transmission lines.

Two (2) hard hat signs at locations directed.

Four (4) beach disposal signs at locations directed.

Project and hard hat signs shall be constructed as detailed in Figures 1, 2, and 3. Decals for hard hat signs will be furnished by the Contracting Officer.

Warning Signs shall be constructed of plywood not less than 1/2 inch thick and shall be securely bolted to the supports with the bottom of the sign face 3 feet above the ground. The sign face shall be 2 x 4 feet, all letters shall be 4 inches in height. Haul road signs shall depict the wording: "WARNING: OVERHEAD TRANSMISSION LINES". Beach disposal signs shall depict the wording: "DANGER - KEEP OUT, BEACH CLOSED, U.S. ARMY CORPS OF ENGINEERS BEACH NOURISHMENT PROJECT".

All exposed surfaces and edges of plywood shall be given one coat of linseed oil and be wiped prior to applying primer. All exposed surfaces of signs and supports shall be given one coat of primer and 2 finish coats of white paint. Except as otherwise indicated, lettering on all signs shall be black and sized as indicated.

#### 1.3.3 Bulletin Board at the Contractor's office

A weatherproof bulletin board, approximately 36 inches wide and 30 inches high, with hinged glass door shall be provided adjacent to or mounted on the Contractor's project office. If adjacent to the office, the bulletin board shall be securely mounted on no less than 2 posts. Bulletin board and posts shall be painted or have other approved factory finish. The bulletin board shall be easily accessible at all times and shall contain wage rates, equal opportunity notice, and such other items required to be posted.

#### 1.3.4 Maintenance and Disposal

The Contractor shall maintain the signs in good condition throughout the life of the project. Signs shall remain the property of the Contractor and upon completion of the project they shall be removed from the site.

#### 1.4 GOVERNMENT FIELD OFFICE

The Contractor shall provide, as a minimum, an adequate room in the Contractor's project trailer/office for the Contracting Officer's Representative.

At completion of each dredge cycle, the office shall remain the property of the Contractor and shall be removed from the site.

#### 1.5 PUBLIC UTILITIES

##### 1.5.1 General

The approximate location of all pipelines, sewer lines, and other utilities known to exist within the limits of the work are indicated on the drawings.

The sizes, locations, and names of owners of such utilities are given from available information, but their accuracy is not guaranteed. Except as otherwise indicated on the drawings, all existing utilities will be left in place and the Contractor shall conduct his operations in such a manner that the utilities will be protected from damage at all times, or arrangements shall be made by the Contractor for their relocation at the Contractor's own expense. The Contractor shall be responsible for any damage to utilities known to exist and shall reimburse the owners for such damage caused by his operations.

##### 1.5.2 Utilities To be Relocated or Protected

The Contractor shall notify the Contracting Officer, in writing, 14 calendar days prior to starting work on any utility to be relocated or protected. On each relocation, notification shall include dates on which the Contractor plans excavation, by-pass work, removal work and/or installation work, as applicable.

### 1.5.3 Relocation or Removal

Utilities to be relocated or removed not as part of this contract are designated "To be Relocated by Others" or "To be Removed by Others," respectively. Utilities shown on the plans and not so designated shall be left in place and will be subject to the provisions of the paragraph entitled "Protection of Existing Vegetation, Structures, Utilities, and Improvements" of Section 00700 CONTRACT CLAUSES. The Contractor without cost to the Government, may make arrangements with the owner for the temporary relocation and restoration of utilities not designated to be relocated, or for additional work in excess of the work needed to relocate utilities designated for relocation.

### 1.5.4 Coordination

The Contractor shall consult and cooperate with the owner of utilities that are to be relocated or removed by others to establish a mutual performance schedule and to enable coordination of such work with the construction work. These consultations shall be held as soon as possible after award of the contract or sufficiently in advance of anticipated interference with construction operations to provide required time for the removal or relocation of affected utilities.

### 1.5.5 Utilities Not Shown

If the Contractor encounters, within the construction limits of the entire project, utilities not shown on the plans and not visible as of the date of this contract and if such utilities will interfere with construction operations, he shall immediately notify the Contracting Officer in writing to enable a determination by the Contracting Officer as to the necessity for removal or relocation. If such utilities are left in place, removed or relocated, as directed by the Contracting Officer, the Contractor shall be entitled to an equitable adjustment for any additional work or delay.

### 1.5.6 Electric Current

All electric current required by the Contractor shall be furnished at his expense. All temporary lines shall be furnished, installed, connected, and maintained by the Contractor in a workmanlike manner satisfactory to the Contracting Officer Representative and shall be removed by the Contractor in a like manner at his expense prior to final acceptance of the construction.

## 1.6 NOTICES

Copies of letters or notifications made to utility companies, U.S. Coast Guard, Harbor District, County, etc. shall be provided to the Contracting Officer.

### 1.6.1 Oceanside Harbor

The Contractor shall notify the Contracting Officer, the Oceanside Harbor District, and Marine Corps(Camp Pendleton) Public Works at least 2 weeks in advance of commencement of each cycle's dredge operation. The following information shall be provided:

- a. Size and type of construction equipment performing work in the project area, including any equipment to be working on the beach.

- b. 24-hour telephone numbers of the project engineer, superintendent, and foreman.
- c. Schedule for completion of project.

Oceanside Harbor District  
1540 Harbor Drive N.                      tel (760) 435-4000  
Oceanside, CA 92054                      fax (760) 439-3058

#### 1.6.2 Traffic Routing

The Contractor shall notify the Contracting Officer Representative 7 days in advance of the time work will be started in areas requiring the rerouting of traffic, traffic lane striping, or removal of street signs. The foregoing shall apply to progressive modifications of traffic routing within an area in which work is in progress.

#### 1.6.3 Existing Bench Marks and R/W Markers

The Contractor shall notify the Contracting Officer, in writing, 7 days in advance of the time he proposes to remove any bench mark or right-of-way marker.

#### 1.6.4 United States Coast Guard

The Contractor shall notify the Commander Eleventh Coast Guard District, and the Coast Guard Marine Safety Office - San Diego not less than 14 calendar days prior to commencing work for each dredge cycle. The notifications (either letter or fax) shall include as a minimum the following information:

- a. Project description and location including latitude/longitude (NAD 83).
  - b. The size and type of any floating construction equipment to be used.
  - c. Name and radio call signs for working vessels.
  - d. Telephone number for 24-hour on-site contact and name and phone number of Project Engineer.
  - e. The schedule for completing the project.
  - f. Potential hazards to navigation.
- Recommend the following language to be used in the Local Notice to Mariners: "Mariners are urged to transit at their slowest safe speed to minimize wake, and to proceed with caution after passing arrangements have been made."

#### Mail address:

Commander (oan)  
Eleventh Coast Guard District  
Building 50-6  
Coast Guard Island  
Alameda, CA 94501-5100  
ATTN: Local Notice to Mariners  
TEL: (510)437-2970 FAX: (510)437-5836  
e-mail: rmentz@d11.uscg.mil  
cc: mcarlson@d11.uscg.mil

U.S. Coast Guard  
Marine Safety Office  
2716 N. Harbor Drive  
San Diego, CA 92101  
Attn: Commander Metruck  
Phone # (619) 683-6500  
Fax # (619) 683-6504

## 1.6.5 Discharge Pipeline

If a discharge pipeline is used, the Contractor shall notify the City of Oceanside of the proposed location of the discharge pipeline not less than ten (10) working days in advance of placing the discharge pipeline. P.O.C. for the City of Oceanside is Mr. Ray Duncan, Lifeguard Manager.

## 1.7 POINTS OF CONTACT

The following is a list of points of contact:

<u>Company or Agency</u>	<u>Contact</u>	<u>Telephone</u>
U.S. Army Corps of Engineers		
Resident Engineer	Dan Moore	(909) 981-5571
Project Engineer	Kevin Thomas	(858) 674-6765
Construction Representative	Randy Lee	(858) 674-6765
City of Oceanside - Dept. of Harbor & Beaches		
Maintenance Manager	Frank Quan	(760) 435-4032
Lifeguard Manager	Ray Duncan	(760) 435-4014
Harbor Patrol	Sgt. Dan Polder	(760) 435-4050
Camp Pendleton Public Works	Laquetta Montgomery	(760) 725-6398
Del Mar Boat Basin - Harbor Master	Ray Moon	(760) 725-7245
U.S. Coast Guard		
Local Notice to Mariners	QM2 Rachel Mentz	(510) 437-2976
Aids-to-Navigation	LT. Jerry Johnson	(510) 437-2969
Marine Safety Office - San Diego	CDR Metruck	(619) 683-6500

## 1.8 AIDS TO NAVIGATION

The Contractor shall not remove, relocate, obstruct, willfully damage, make fast to, or interfere with any aids to navigation. The Contractor shall notify the Eleventh Coast Guard District in writing with a copy to the Contracting Officer not less than 30 calendar days in advance of the time he plans to operate any equipment adjacent to any aids to navigation which requires relocation or removal.

## 1.9 DREDGING AIDS

The Contractor shall coordinate with the Harbor Patrol prior to placing any buoy or other aid marker in the water. Buoys and other dredging aid markers shall be equipped with the necessary lights and the Contractor shall insure that all lights are in proper working order prior to installation. Buoys and dredging aids markers shall be maintained throughout the length of the dredging operation and shall not be colored, marked, or placed in a manner that will obstruct or be confused with other navigational aids. The Contractor's buoys and aid markers shall conform to U.S. Coast Guard regulations.



## 1.10 RESTRICTIONS

### 1.10.1 Dredging of Del Mar Channel

The portion of Del Mar Channel located between stations 0+680 and 1+600 consists of material that may contain more than 20% fines. When dredging between stations 0+680 and 1+600 of the Del Mar Channel, the Contractor shall dispose of material either at the nearshore disposal site, or directly into the surf zone at the beach disposal site.

### 1.10.2 Pipeline and Power Line Crossings

a. General. Should submerged discharge pipelines cause shoaling in the navigation channel, the Contractor shall remove such shoals and restore to the depths required by the contract and/or as existed prior to the laying of the submerged pipe. Materials so removed shall be disposed of in a manner approved by the Contracting Officer. No separate payment will be made for the removal of such shoals and all costs thereof shall be included in the contract price.

b. Channel Crossings. Where the Contractor's discharge pipe and any required power lines cross navigation channels, the top of the pipe and power lines shall be submerged and maintained to a minimum depth of -4.6 meters (MLLW) to provide an unrestricted navigation over the pipe and power lines for a distance of not less than 90 meters normal to the channel alignment. The Contractor shall provide anchors or weights to prevent the submerged pipeline and lines from floating. The Contractor shall remove the anchor or weights after completion of dredging operations.

c. River Crossings. The Contractor shall coordinate the discharge pipe location across the San Luis Rey River with the Contracting Officer prior to placement. In the event that flow out of the San Luis Rey River threatens the pipe, the Contractor shall remove or sufficiently anchor endangered portions of the pipe to prevent damage. The Contractor shall not cause any blockage at the mouth of the San Luis Rey River that would interfere with the normal tidal flow or the normal flow characteristics of the river.

### 1.10.3 Disposal

a. Discharge Pipeline. The discharge pipeline, if used, shall be buried in the vicinity of the North Coast Village Condominiums, from the San Luis Rey River to just south of the North Coast Village Condominiums, a length of approximately 350 meters.

(1) For noise reduction purposes, the pipe in front of the North Coast Village Condominiums shall be covered with a minimum of 0.5 meters of sand.

Other restrictions may be designated on the plans. After emerging onto the beach south of Oceanside Pier, the discharge pipeline shall be placed within a 6-meter wide corridor as approved by the Contracting Officer and in accordance with the restrictions of this section. All dredge disposal activities will occur south of the Oceanside Public Pier. The location of the discharge lines shall be subject to approval by the Contracting Officer prior to the installation of the discharge lines. The Contractor shall notify the Contracting Officer, in writing, not less than 10 calendar days in advance of the time the discharge pipeline will be placed and shall also notify the City of Oceanside as required per paragraph: Notices.

(2) The Contractor may temporarily close portions of the City beach as

required to safely lay discharge pipeline and to place and grade the dredged material. These closures shall be kept to a minimum. The Contractor shall be responsible for providing and placing all necessary signs, barricades, and safety devices. The Contractor shall coordinate beach closings with the Contracting Officer and the City of Oceanside Lifeguard Manager.

b. Beach Access Ramp. Where the discharge pipeline is laid on the beach surface, the Contractor shall provide access ramps over the discharge pipeline at not more than 100-meter intervals to provide access for emergency vehicles to the beach, unless otherwise authorized or directed by the Contracting Officer. The ramps shall not be less than 4 meters wide and shall be constructed with material from the adjacent area. Maintenance and protection of the discharge pipeline and ramps shall be the responsibility of the Contractor. The discharge pipeline shall be free from holes, and joints shall be watertight outside the designated limits of the disposal area.

#### 1.10.4 Construction Vehicles

a. The Contractor shall secure variances to City of Oceanside ordinances for vehicular access to the beach. All Contractor's vehicles granted a variance shall display necessary permit at all times.

b. Any access from improved roads onto the beach shall be coordinated with the Oceanside Lifeguard Manager, Mr. Ray Duncan.

#### 1.10.5 Obstruction of Channel

The Government will not undertake to keep the harbor entrance or navigation channels free from vessels or other obstructions. The Contractor shall be required to conduct the work in such a manner as to obstruct navigation as little as possible, and in case the Contractor's plant so obstructs the channel as to make difficult or endanger the passage of vessels, said plant shall be promptly moved on the approach of any vessel to such an extent as may be necessary to afford a practicable passage. Upon the completion of the work, the Contractor shall promptly remove his plant, including ranges, temporary buoys, and piles and other marks placed by him under the contract in navigable waters or on shore.

All underwater and above surface hazards to navigation associated with this work shall be marked with a white light of at least 40 candella.

#### 1.10.6 Booster Pump

A booster unit, if required, shall be located in the Harbor Beach area, north of the bypass pumphouse, which is located in the vicinity of the Contractor's field office area. The booster pump shall be mounted on rubber to reduce vibration, be equipped with sufficient muffler system to reduce both the noise and odor, and the blower shall be vented toward the ocean to minimize the noise level. The booster unit shall be fully enclosed, to a height not less than 2 meters, with a bamboo or grape stake chainlink fence.

#### 1.10.7 Method of Dredging

This contract is suitable for the following methods of dredging: hydraulic pipeline (cutter head), hopper dredge, and clamshell-barge. The

Contractor shall comply with all applicable Federal, State, County, and municipal laws, regulations, and permits governing the work.

#### 1.11 MARINE PLANT

a. All marine plant and equipment which are required by federal regulations to be inspected by the United States Coast Guard, shall have valid certifications. No marine plant or equipment requiring Coast Guard inspection shall be put into use on the job without the required certification issued by the U.S. Coast Guard Officer in Charge of Marine Inspections.

b. All marine construction equipment shall monitor appropriate VHF marine safety radio channels.

c. Fuel transfer operations shall conform to U.S. Coast Guard design regulations, CFR 33 Part 156.

#### 1.12 PUBLIC SAFETY

Attention is invited to the CONTRACT CLAUSE: PERMITS AND RESPONSIBILITIES.

The Contractor shall provide temporary fencing, barricades, and/or guards, as required, to provide protection in the interest of public safety. Whenever the Contractor's operations create a condition hazardous to the public, he shall furnish at his own expense and without cost to the Government, such flagmen and guards as are necessary to give adequate warning to the public of any dangerous conditions to be encountered and he shall furnish, erect, or maintain such fences, barricades, lights, signs and other devices as are necessary to prevent accidents and avoid damage or injury to the public. Flagmen and guards, while on duty and assigned to give warning and safety devices shall conform to applicable city, county, and state requirements. Should the Contractor appear to be neglectful or negligent in furnishing adequate warning and protection measures, the Contracting Officer may direct attention to the existence of a hazard and the necessary warning and protective measures shall be furnished and installed by the Contractor without additional cost to the Government. Should the Contracting Officer point out the inadequacy of warning and protective measures, such action of the Contracting Officer shall not relieve the Contractor from any responsibility for public safety or abrogate his obligation to furnish and pay for those devices. The installation of any general illumination shall not relieve the Contractor of his responsibility for furnishing and maintaining any protective facility.

The Contractor shall furnish flagmen, watchmen, or other security personnel to control traffic and protect pedestrians in the vicinity of the discharge pipe at all times while discharging material in the disposal area.

#### 1.13 GENERAL SAFETY REQUIREMENTS

##### 1.13.1 General

The Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, (see CONTRACT CLAUSES: SECTION 00700, ACCIDENT PREVENTION), the Occupational Safety and Health Act (OSHA) Standards for Construction (Title 29, Code of Federal Regulations Part 1926 as revised from time to time), and the Dredging Contractor of America (DCA) / United States Army Corps of Engineers (USACE) Dredging Safety Management Program (DMSP) are all

applicable to this contract. In case of conflict, the most stringent requirement of the three standards is applicable. Pursuant to EM 385-1-1, the Contractor shall submit a Site Safety Health Plan / Accident Prevention Plan (APP).

If the Contractor is a currently accepted participant in the Dredging Contractors of America (DCA) / United States Army Corps of Engineers (USACE) Dredging Safety Management Program (DSMP), as determined by the DCA/USACE Joint Committee, and holds a current valid Certificate of Compliance for both the Contractor Program and the dredges to be used to perform the work required under this contract, the Contractor may, in lieu of the submission of a Site Safety Health Plan / Accident Prevention Plan,

- (a) make available for review, upon request, the Contractor's current Safety Management System (SMS) documentation,
- (b) submit to the Contracting Officer the current valid Company Certificate of Compliance for its SMS
- (c) submit the current dredge(s) Certificate of Compliance based on third party audit, and
- (d) submit for review and acceptance, site specific addenda to the SMS as specified in the solicitation.

#### 1.13.2 Job Hazard Analysis

Based on the construction schedule, the Contractor shall submit a Job Hazards Safety Analysis of each major phase of work prior to entering that phase of activity. The analysis shall include major or high risk hazards, as well as commonly recurring deficiencies that might possibly be encountered for that operation, and shall identify proposed methods and techniques of accomplishing each phase in a safe manner. The Prime Contractor's superintendent shall take active participation in the Job Hazard Analysis, including the subcontractors' work. Prior to start of actual work a meeting shall be held with Prime Contractor, Government, and affected subcontractor to review the Job Hazard Analysis. In addition, job site meetings shall be held to indoctrinate foreman and workers on details of this analysis.

#### 1.14 SIGNAL LIGHTS

The Contractor shall display signal lights and conduct his operations in accordance with the General Regulations of the Department of the Army and of the Coast Guard, governing lights and day signals to be displayed by towing vessels with tows, on which no signals can be displayed, vessels working on dredges, jetties, submarine or bank protection operations, lights to be displayed on dredge pipelines, and day signals to be displayed by vessels of more than 65 feet in length moored or anchored in a fairway or channel, and the passing by other vessels of floating plant working in navigable channels, as approved by the Secretary of the Army (33 C.F.R. 201.1-201.16) and the Commandant U.S. Coast Guard (33 C.F.R. 80.18-80.31a and 33 C.F.R. 95.51-95.70). All Contractor's anchor buoys, floating line, and plant shall be marked with flashing beacon lights after dark. Obstructions and hazards to navigation mentioned above shall be painted for visibility during daylight hours.

## 1.15 RADIO COMMUNICATION

To facilitate and insure the safe passage of vessels in the channel, the Contractor shall provide, operate and maintain on his plant, radio facilities capable of voice communication with vessels using the channel. Station licensing and frequency authorizations shall be the responsibility of the Contractor.

## 1.16 PERMITS

Reference is made to the clause of the contract entitled: PERMITS AND RESPONSIBILITIES, which obligate the Contractor to obtain all required licenses and permits.

## 1.17 REPAIR OF STREETS, ACCESS ROADS, AND WORK AREAS

The Contractor shall restore streets, sidewalks, parking lots, and access roads (used for haul routes and mobilizing equipment) and work areas to original condition upon completion of the work for each dredge cycle. Contractor shall restore to the City of Oceanside standards.

## 1.18 INSPECTION

Reference is made to the clause of the contract entitled: INSPECTION OF CONSTRUCTION. In addition, the Contractor will be required:

a. To furnish, on the notification of the Contracting Officer, his authorized representative, or any Corps inspector, the use of such boats, boatmen, laborers, and material forming a part of the ordinary and usual equipment and crew of the plant as may be reasonably necessary in inspecting and supervising the work.

b. To furnish, on the notification of the Contracting Officer, his authorized representative, or any Corps inspector, suitable transportation from all points on shore designated by the Contracting Officer to and from the various pieces of plant, and to and from the work areas. Should the Contractor refuse, neglect, or delay compliance with these requirements, the specific facilities may be furnished and maintained by the Contracting Officer, and the cost thereof will be deducted from any amounts due or to become due the Contractor.

c. Upon notification of the Contracting Officer, his authorized representative, or any Corps inspector, to allow authorized representatives of the California Regional Water Quality Control Board and the San Diego County Air Pollution Control District to:

enter upon the Contractor's premises where a regulated facility or activity is located or conducted, or where records are kept;

have access to and copy, at reasonable times, any records that must be kept per agency requirements;

inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated by these agencies;

and sample or monitor at reasonable times any substances or parameters at any location for the purpose of assuring compliance with agency regulations.

#### 1.19 NAVIGATION

The Contractor's operations shall conform to the U.S. Coast Guard publication "Navigation Rules, International-Inland, INST M16672.28" latest edition.

#### 1.20 WORK AREAS AND EASEMENTS

The Contractor shall submit a Work and Storage Areas Plan for approval within 15 days after receipt of Notice to Proceed. The Contractor's work areas and temporary construction easements are as indicated, subject to approval of the Contracting Officer. The Contractor's work area(s) shall be fenced according to the instruction of the Contracting Officer. Upon completion of the work, the fence materials shall become the property of the Contractor and shall be removed from the site.

Any damage to electrical underground installations, light poles, pavement, fence, shrubs or other facilities within the Contractor's work area shall be repaired or replaced by and at the expense of the Contractor.

The Contractor shall mark the shoreward limits of the construction easement by means of suitable marker buoys. The remaining portion of the navigation channel shall not be obstructed and shall remain open to traffic. Areas within the construction easement not being used by the Contractor for construction shall be made available for anchorage, however, moorings within the easement will be moved by others within 5 days after written notice by the Contractor to the Contracting Officer.

#### 1.21 CORPS OF ENGINEERS RESERVE FLEET (CERF) IMPLEMENTATION

If the work specified in this contract is performed by a hopper dredge(s), the owner must have an active Basic Ordering Agreement (BOA) for the hopper dredge(s) on file with the Corps. The Contractor shall be obligated to make the hopper dredge(s) available to serve in the Corps of Engineers Reserve Fleet (CERF) at any time that the hopper dredge(s) is performing work under this contract. When the Contracting Officer is notified of the decision to activate this dredge(s) into the CERF, he shall take appropriate action to release the dredge(s). He may then extend or terminate the contract to implement whichever action is in the best interest of the Government. The CERF Contractor shall also be subject to the following conditions:

a. The Director of Civil Works may require the Contractor to perform emergency dredging at another CONUS (48 contiguous states) site for a period of time equal to the remaining time under this contract at the date of notification plus up to ninety (90) days at the previously negotiated rate which appears on the schedule of prices in the BOA.

b. The Chief of Engineers may require the Contractor to perform emergency dredging at an OCONUS (Outside CONUS which includes Alaska, Hawaii, Puerto Rico, the Virgin Islands, or U.S. Trust Territories) site for a period of time equal to the time remaining under this contract at the date of notification plus up to one hundred eighty (180) days at the negotiated rate which appears on the schedule of prices in the BOA.

c. The CERF shall be activated by the Chief of Engineers or the

Director of Civil Works; then the Ordering Contracting Officer will notify the Contractor. From the time of notification, the selected hopper dredge(s) must depart for the emergency assignment within seventy-two (72) hours for CONUS or ten (10) days for OCONUS assignments.

d. A confirming delivery order will be issued pursuant to the Basic Ordering Agreement (BOA) by the Ordering Contracting Officer. Such delivery order shall utilize the schedule of rates in the BOA for the specific hopper dredge(s).

e. If during the time period specified in the paragraphs above, a CERF vessel(s) is still required, the contract performance may be continued for additional time by mutual agreement.

#### 1.22 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER

This provision specifies the procedure for determination of time extensions for unusually severe weather in accordance with the CONTRACT CLAUSES: SECTION 00700, entitled DEFAULT (FIXED PRICE CONSTRUCTION). In order for the Contracting Officer to award a time extension under this clause, the following conditions must be satisfied:

a. The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than the adverse weather anticipated for the project location during any given month.

b. The unusually severe weather must actually cause a delay to the completion of the project. The delay must be beyond the control and without the fault or negligence of the Contractor.

The following schedule of monthly anticipated adverse weather delays is based on Coastal Data Information Program (CDIP) wave data collected from the Oceanside array for the years 1976 to 1991 and will constitute the base line for monthly weather time evaluations. Significant wave height exceeding one (1) meter will constitute adverse weather conditions. The Contractor's progress schedule must reflect the following schedule of anticipated adverse weather delays in all weather dependent activities.

#### MONTHLY ANTICIPATED ADVERSE WEATHER DAYS Work Days Based on Five (5) Day Work Week

JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
6	5	6	4	4	4	2	2	2	3	4	4

c. Upon acknowledgment of the Notice to Proceed and continuing throughout the contract, the Contractor will record on the daily CQC report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delay days must prevent work on critical activities for 50 percent or more of the Contractor's scheduled work day. The number of actual adverse weather days shall include days impacted by actual adverse weather (even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. If the number of actual adverse weather delay days exceeds the number of days anticipated in paragraph b, the Contracting Officer will convert any qualifying days to calendar days, giving full consideration for equivalent fair weather work

days, and issue a modification in accordance with the Contract Clause entitled: DEFAULT (FIXED PRICE CONSTRUCTION).

#### 1.23 ENTRANCE CHANNEL WAVE CONDITIONS

The outer part of the Oceanside Harbor Entrance Channel is not protected by breakwaters. This exposed section of channel can experience high sea conditions. The Contractor should anticipate rough sea conditions in this part of the work area, and plan his work accordingly to perform dredging in the outer portion of the Entrance Channel during windows of not rough sea conditions.

Contractor can check wave data at the Oceanside Offshore Wave Buoy at the Coastal Data Information Program (CDIP) website <http://cdip.ucsd.edu/>. The Oceanside Buoy is located 4 miles offshore of Oceanside. Funding for this wave buoy may be suspended at any time, resulting in termination of buoy data.

#### 1.24 CONTRACTOR MOORING AREA

Temporary emergency mooring space for the dredge will be available inside Del Mar Boat Basin. The Contractor shall be responsible for coordinating with the Marine Corps representative for mooring location. P.O.C. is Laquetta Montgomery of Camp Pendleton Public Works.

#### 1.25 COORDINATION WITH OTHER CONSTRUCTION

The Contractor shall coordinate work with other construction projects in the vicinity of the project.

#### 1.26 OCEANSIDE ANNUAL TRIATHLON


The Oceanside Triathlon is held annually in the Spring, typically the first Saturday in April. The triathlon includes a swim event in the harbor. If dredging is ongoing during the time of this event, dredge activities shall be shut down for a minimum 30-hour window from 12:00 noon the day before the event, to 6:00 p.m the day of the event. Pipelines and equipment within Oceanside Harbor shall be positioned so as not to interfere with the triathlon events.

#### PART 2 MATERIALS (NOT APPLICABLE)

#### PART 3 EXECUTION (NOT APPLICABLE)

-- End of Section --






Space	Height	Line	Description	Letter Height	Stroke
A	75	1	U.S. ARMY	140	22
B	50	2	PROJECT NOMENCLATURE	100	16
C	50	3	CORPS OF ENGINEERS CASTLE (DECAL)	345	
D	70	4	U.S. ARMY ENGINEER DISTRICT	70	9
E	50	5	DISTRICT NAME	60	6
F	50	6	CORPS OF ENGINEERS	65	9
G	75				

Letter Color -- Black

PROJECT SIGN  
(Army-Civil Works)

Figure 1  
October 1996


All units are in millimeters.



# SIGN DETAILS

Figure 2  
October 1996

All units are in millimeters unless otherwise indicated.




#### General Notes

1. Green & white paint shall be opaque glossy as specified in ANSI Z53.1
2. Bolt sign to post with two 15 mm dia. carriage bolts.

Figure 3  
October 1996

All units are in millimeters unless otherwise indicated.



<u>SPACE</u>	<u>HEIGHT</u>	<u>LINE</u>	<u>DESCRIPTION</u>	<u>LETTER HEIGHT</u>
A	125			
B	75	1	CONTRACTOR'S NAME	125
C	150	2	ADDRESS	75
D	75	3	SAFETY IS A JOB REQUIREMENT	115 & 75
E	75	4	ALL LETTERING	75
F	75	5	ALL LETTERING	75
G	125	6	ALL LETTERING	75

Notes

Lettering shall be black No. 27038 standard 595.  
Sign shall be installed in the same manner  
as the Project Sign.

SAFETY SIGN  
STANDARD DETAIL

All units are in millimeters.

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01270

MEASUREMENT AND PAYMENT

**02/94**

PART 1 GENERAL

- 1.1 SUBMITTALS
- 1.2 LUMP SUM PAYMENT ITEMS
  - 1.2.1 Mobilization and Demobilization
- 1.3 UNIT PRICE PAYMENT ITEMS
  - 1.3.1 Dredging

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section Table of Contents --

## SECTION 01270

MEASUREMENT AND PAYMENT  
02/94

## PART 1 GENERAL

## 1.1 SUBMITTALS

None

## 1.2 LUMP SUM PAYMENT ITEMS

Payment items for the work of this contract for which contract lump sum payments will be made are listed in the BIDDING SCHEDULE and described below. All costs for items of work, which are not specifically mentioned to be included in a particular lump sum or unit price payment item, shall be included in the listed lump sum item most closely associated with the work involved. The lump sum price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for which separate payment is not otherwise provided.

## 1.2.1 Mobilization and Demobilization

## a. Payment

Payment will be made for costs associated with mobilization and demobilization as defined in Special Clause PAYMENT FOR MOBILIZATION AND DEMOBILIZATION.

## b. Unit of Measure

Unit of measure: Job.

## 1.3 UNIT PRICE PAYMENT ITEMS

Payment items for the work of this contract on which the contract unit price payments will be made are listed in the BIDDING SCHEDULE and described below. The unit price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for each of the unit price items.

## 1.3.1 Dredging

## a. Payment

Payment will be made for costs associated with dredging, including overdepth dredging, transporting and deposition of dredge material at designated disposal sites, and other operations incidental thereto, including hydrographic surveys and water quality control and monitoring.

## b. Measurement

The total quantity of dredge material for which payment will be made will be by in-place (quantity) measurement in by computing the difference in available material between the pre-dredge survey and the post-dredge survey. Available material is defined as material located within the boundaries of the dredge prism. Specifically, a quantity of available material will be computed between the dredge prism and the bottom surface shown by the soundings of the Government's pre-dredge survey, and a quantity of available material will be computed between the dredge prism and the bottom surface shown by the Government's post-dredge survey. The difference between these two available quantities (pre-dredge and post-dredge) will constitute the quantity of material dredged. Misplaced materials (including any required removal and placement), excessive overdepth dredging and material falling or drawn into the cut from beyond the side slope plane or beyond the limits indicated, will be excluded from the quantities for which payment will be made. The Triangulated Irregular Network (TIN) method will be used for quantity determination. For method of soundings, see SECTION 02020 DREDGING.

## c. Unit of Measure

Unit of measure: cubic.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01330

SUBMITTAL PROCEDURES

**02/02**

PART 1 GENERAL

- 1.1 SUBMITTAL IDENTIFICATION (SD)
- 1.2 SUBMITTAL CLASSIFICATION
  - 1.2.1 Government Approved
  - 1.2.2 Information Only
- 1.3 APPROVED SUBMITTALS
- 1.4 DISAPPROVED SUBMITTALS
- 1.5 WITHHOLDING OF PAYMENT
- 1.6 GENERAL
- 1.7 SUBMITTAL REGISTER
- 1.8 SCHEDULING
- 1.9 TRANSMITTAL FORM (ENG FORM 4025)
- 1.10 SUBMITTAL PROCEDURES
  - 1.10.1 Procedures
  - 1.10.2 Deviations
- 1.11 CONTROL OF SUBMITTALS
- 1.12 GOVERNMENT APPROVED SUBMITTALS
- 1.13 INFORMATION ONLY SUBMITTALS
- 1.14 STAMPS

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --



## SECTION 01330

## SUBMITTAL PROCEDURES

02/02

## PART 1 GENERAL

## 1.1 SUBMITTAL IDENTIFICATION (SD)

Submittals required are identified by SD numbers and titles as follows:

SD-01 Preconstruction Submittals

SD-03 Product Data

SD-04 Samples

SD-06 Test Reports

## 1.2 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

## 1.2.1 Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

## 1.2.2 Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

## 1.3 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

#### 1.4 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

#### 1.5 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

#### 1.6 GENERAL

The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) System Manager and each item shall be stamped, signed, and dated by the CQC System Manager indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

#### 1.7 SUBMITTAL REGISTER

At the end of this section is a submittal register showing items of equipment and materials for which submittals are required by the specifications; this list may not be all inclusive and additional submittals may be required. The Contractor shall maintain a submittal register for the project in accordance with Section 01312A QUALITY CONTROL SYSTEM (QCS). The Government will provide the initial submittal register in electronic format. Thereafter, the Contractor shall maintain a complete list of all submittals, including completion of all data columns. Dates on which submittals are received and returned by the Government will be included in its export file to the Contractor. The Contractor shall track all submittals.

#### 1.8 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 10 calendar days exclusive of mailing time) shall be allowed and shown on the register for

review and approval. No delay damages or time extensions will be allowed for time lost in late submittals.

#### 1.9 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG Form 4025) attached to this section shall be used for submitting both Government approved and information only submittals in accordance with the instructions on the reverse side of the form. These forms will be furnished to the Contractor. This form shall be properly completed by filling out all the heading blank spaces and identifying each item submitted. Special care shall be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submitted for each item.

#### 1.10 SUBMITTAL PROCEDURES

Submittals shall be made as follows:

##### 1.10.1 Procedures

Submittals shall be made to the Contracting Officer's Representative. Two (2) copies of submittals for Information Only are required. Six (6) copies are required for all other submittals.

##### 1.10.2 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

#### 1.11 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

#### 1.12 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so stamped and dated. Four copies of the submittal will be retained by the Contracting Officer and two copies of the submittal will be returned to the Contractor.

#### 1.13 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so

prescribe.

#### 1.14 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

CONTRACTOR
(Firm Name)
_____ Approved
_____ Approved with corrections as noted on submittal data and/or attached sheets(s).
SIGNATURE: _____
TITLE: _____
DATE: _____

PART 2 PRODUCTS  
(Not used)

PART 3 EXECUTION  
(Not used)

-- End of Section --

CONTRACT NO.

## Oceanside Harbor Maintenance Dredging

CONTRACTOR:  
SCHEDULE DATES

CONTRACTOR  
ACTION

APPROVING AUTHORITY

ACTIVITY NO

TRANSMITTAL NO

S  
P  
E  
C  
  
S  
E  
C  
T

DESCRIPTION	ITEM SUBMITTED

PARAGRAPH #

GOVERNANCE REVIEW

SUBMIT

APPROVAL  
NEEDED  
BY

MATERIAL  
NEEDED  
BY

ACTION CODE

DATE  
OF  
ACTIONDATE RCD  
FROM  
CONTRDATE FWD  
TO APPR  
AUTH/

DATE FW	
TO OTHER	
REVIEWE	

0

DATE RCD	
FROM OTH	
REVIEWER	

1

ACTION CODE

DATE  
OF  
ACTION

MAILED  
TO  
CONTR/

DATE RCD  
FRM APPR  
AUTH

REMARKS

PAGE 1 OF 1 PAGES



## INSTRUCTIONS

1. Section I will be initiated by the Contractor in the required number of copies.
2. Each transmittal shall be numbered consecutively in the space provided for "Transmittal No.". This number, in addition to the contract number, will form a serial number for identifying each submittal. For new submittals or resubmittals mark the appropriate box; on resubmittals, insert transmittal number of last submission as well as the new submittal number.
3. The "Item No." will be the same "Item No." as indicated on ENG FORM 4288-R for each entry on this form.
4. Submittals requiring expeditious handling will be submitted on a separate form.
5. Separate transmittal form will be used for submittals under separate sections of the specifications.
6. A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications--also, a written statement to that effect shall be included in the space provided for "Remarks".
7. Form is self-transmittal, letter of transmittal is not required.
8. When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certificate" in column c, Section I.
9. U.S. Army Corps of Engineers approving authority will assign action codes as indicated below in space provided in Section I, column i to each item submitted. In addition they will ensure enclosures are indicated and attached to the form prior to return to the contractor. The Contractor will assign action codes as indicated below in Section I, column g, to each item submitted.

### THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED

- |   |   |
|---|---|
| A -- Approved as submitted.   | E -- Disapproved (See attached).  |
| B -- Approved, except as noted on drawings.   | F -- Receipt acknowledged.  |
| C -- Approved, except as noted on drawings.<br>Refer to attached sheet resubmission required. | FX -- Receipt acknowledged, does not comply<br>as noted with contract requirements. |
| D -- Will be returned by separate correspondence.   | G -- Other (Specify)  |

10. Approval of items does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

(Reverse of ENG Form 4025-R)

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01354

ENVIRONMENTAL PROTECTION FOR CIVIL WORKS

10/95

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DEFINITIONS
- 1.3 SUBMITTALS
- 1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS
  - 1.4.1 Protection of Features
  - 1.4.2 Permits
  - 1.4.3 Special Environmental Requirements
  - 1.4.4 Environmental Assessment of Contract Deviations
- 1.5 ENVIRONMENTAL PROTECTION PLAN
  - 1.5.1 Compliance
  - 1.5.2 Laws and Regulations and Permits
  - 1.5.3 Contents

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 SPECIAL ENVIRONMENTAL PROTECTION REQUIREMENTS
  - 3.1.1 U.S. Department of Agriculture (USDA) Quarantined Considerations
  - 3.1.2 Soil Disposal Areas on Government Property
  - 3.1.3 Disposal of Solid Wastes
  - 3.1.4 Clearing Debris
  - 3.1.5 Disposal of Contractor Generated Hazardous Wastes
  - 3.1.6 Fuels and Lubricants
- 3.2 HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES
  - 3.2.1 Known Historic, Archaeological, and Cultural Resources
  - 3.2.2 Discovered Historic, Archaeological, and Cultural Resources
- 3.3 PROTECTION OF WATER RESOURCES
  - 3.3.1 The Contractor shall perform discharge monitoring, inspections, and testing, reporting and record keeping as set forth below::
  - 3.3.2 Floating Debris
  - 3.3.3 Other Discharge
  - 3.3.4 Commitments
- 3.4 PROTECTION OF FISH AND WILDLIFE RESOURCES
  - 3.4.1 Marine Mammals
  - 3.4.2 Dead or Injured Wildlife
- 3.5 PROTECTION OF AIR RESOURCES
  - 3.5.1 Air Pollution Control District
  - 3.5.2 Other Commitments
- 3.6 NOISE
- 3.7 INSPECTION
- 3.8 TRAINING OF CONTRACTOR PERSONNEL



-- End of Section Table of Contents --

## SECTION 01354

ENVIRONMENTAL PROTECTION FOR CIVIL WORKS  
10/95

## PART 1 GENERAL

## 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

## CODE OF FEDERAL REGULATIONS (CFR)

36 CFR 800.11	Properties Discovered During Implementation of an Undertaking
40 CFR 261	Identification and Listing of Hazardous Waste

## ENGINEERING MANUALS (EM)

EM 385-1-1	(1996) Safety and Health Requirements Manual
------------	---

## 1.2 DEFINITIONS

Environmental pollution and damage is defined as the presence of chemical, physical, or biological elements or agents that adversely affect human health or welfare; unfavorably alter ecological balances of plant or animal communities; or degrade the environment from an aesthetic, cultural, or historic perspective.

Environmental protection is the prevention/control of pollution and habitat disruption that may occur during construction. The control of environmental pollution and damage requires consideration of air, water, land, biological, noise, cultural, and visual resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive materials; and other pollutants.

## 1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

## SD-01 Preconstruction Submittals

Environmental Protection Plan; G.

## SD-06 Test Reports

Water Monitoring;

## 1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

The Contractor shall comply with all applicable Federal, State, and local laws and regulations. The Contractor shall provide environmental protective measures and procedures to prevent and control pollution, limit habitat disruption, and correct environmental damage that occurs during construction.

## 1.4.1 Protection of Features

This section supplements the Contract Clause PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS. The Contractor shall prepare a list of features requiring protection under the provisions of the contract clause which are not specially identified on the drawings as environmental features requiring protection. The Contractor shall protect those environmental features, indicated specially on the drawings, in spite of interference which their preservation may cause to the Contractor's work under the contract.

## 1.4.2 Permits

This section supplements the Contractor's responsibility under the contract clause PERMITS AND RESPONSIBILITIES. The Government has not obtained any permits for this project with the exception of the California Coastal Commission and California Regional Water Quality Control Board permits. It is the Contractor's responsibility to obtain all other necessary permits and abide by the conditions set within each document. If there is a conflict among the conditions, the Contractor shall request clarification from the Corps.

## 1.4.3 Special Environmental Requirements

The Contractor shall comply with the special environmental requirements included at the end of this section. These special environmental requirements are an outgrowth of environmental commitments made by the Government during the project development.

## 1.4.4 Environmental Assessment of Contract Deviations

The Contract specifications have been prepared to comply with the special conditions and mitigation measures of an environmental nature which were established during the planning and development of this project. The Contractor is advised that deviations from the drawings or specifications (e.g., proposed alternate borrow areas, disposal areas, staging areas, alternate access routes, scheduling delays, etc.) could result in the requirement for the Government to reanalyze the project from an environmental standpoint. Deviations from the construction methods and procedures indicated by the plans and specifications which may have an environmental impact will require an extended review, processing, and

approval time by the Government.

The Contracting Officer reserves the right to disapprove alternate methods, even if they are more cost effective, if the Contracting Officer determines that the proposed alternate method will have an adverse environmental impact.

#### 1.5 ENVIRONMENTAL PROTECTION PLAN

Within 20 calendar days of Contract Award, the Contractor shall submit an Environmental Protection Plan for review and acceptance by the Contracting Officer. The Contractor shall incorporate Government comments into the final Environmental Protection Plan within 15 days after receipt of comments from the Government.

Acceptance is conditional and is predicated upon satisfactory performance during construction. The Government reserves the right to require the Contractor to make changes in the Environmental Protection Plan or operations if the Contracting Officer determines that environmental protection requirements are not being met.

The plan shall detail the actions which the Contractor shall take to comply with all applicable Federal, State, and local laws and regulations concerning environmental protection and pollution control and abatement, as well as the additional specific requirements of this contract. The Contractor shall address each topic at a level of detail commensurate with the environmental issue and required construction task(s). No physical work at the site shall begin prior to acceptance of the Contractor's plan or an interim plan covering the work to be performed. The Environmental Protection Plan shall be current and maintained on site by the Contractor, and shall include, but not be limited to, the following:

##### 1.5.1 Compliance

No requirement in this Section shall be construed as relieving the Contractor of any applicable Federal, State, or local environmental protection laws and regulations. During construction, the Contractor shall be responsible for identifying, implementing, and submitting for approval any additional requirements to be included in the Environmental Protection Plan.

### 1.5.2 Laws and Regulations and Permits

The Contractor shall provide as part of the Environmental Protection Plan a list of all Federal, State and local environmental laws and regulations, and permits concerning environmental protection, pollution control, and abatement that are applicable to the Contractor's proposed operation and the requirements imposed by those laws, regulations and permits. Permits obtained by the Contractor shall be attached to, and specific conditions included in the Environmental Protection plan.

### 1.5.3 Contents

The environmental protection plan shall include, but shall not be limited to, the following:

a. Name(s) of person(s) within the Contractor's organization who is(are) responsible for ensuring adherence to the Environmental Protection Plan.

b. Name(s) and qualifications of person(s) responsible for manifesting hazardous waste to be removed from the site, if applicable.

c. Name(s) and qualifications of person(s) responsible for training the Contractor's environmental protection personnel.

d. Description of the Contractor's environmental protection personnel training program.

e. Traffic control plans including measures to reduce erosion of temporary roadbeds by construction traffic, especially during wet weather. Plan shall include measures to minimize the amount of mud transported onto paved public roads by vehicles or runoff.

f. Work area plan showing the proposed activity in each portion of the area and identifying the areas of limited use or nonuse. Plan should include measures for marking the limits of use areas including methods for protection of features to be preserved within authorized work areas.

g. The Spill Control plan shall include the procedures, instructions, and reports to be used in the event of an unforeseen spill of a substance regulated by 40 CFR 68, 40 CFR 302, 40 CFR 355, and/or regulated under State or Local laws and regulations. The Spill Control Plan supplements the requirements of EM 385-1-1. This plan shall include as a minimum:

1. The name of the individual who will report any spills or hazardous substance releases and who will follow up with complete documentation. This individual shall immediately notify the Contracting Officer in addition to the legally required Federal, State, and local reporting channels (including the National Response Center 1-800-424-8802) if a reportable quantity is released to the environment. The plan shall contain a list of the required reporting channels and telephone numbers.

2. The name and qualifications of the individual who will be responsible for implementing and supervising the containment and cleanup.

3. Training requirements for Contractor's personnel and methods of accomplishing the training.

4. A list of materials and equipment to be immediately available at

the job site, tailored to cleanup work of the potential hazard(s) identified.

5. The names and locations of suppliers of containment materials and locations of additional fuel oil recovery, cleanup, restoration, and material-placement equipment available in case of an unforeseen spill emergency.

6. The methods and procedures to be used for expeditions contaminant cleanup.

h. A non-hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris. The plan shall include schedules for disposal. The Contractor shall identify any subcontractors responsible for the transportation and disposal of solid waste. Licenses or permits shall be submitted for solid waste disposal sites that are not a commercial operating facility. Evidence of the disposal facility's acceptance of the solid waste shall be attached to this plan during the construction. The Contractor shall attach a copy of each of the Non-hazardous Solid Waste Diversion Reports to the disposal plan. The report shall be submitted after completion of the Work. The report shall indicate the total amount of waste generated and total amount of waste diverted in cubic yards or tons along with the percent that was diverted.

i. A recycling and solid waste minimization plan with a list of measures to reduce consumption of energy and natural resources. The plan shall detail the Contractor's actions to comply with and to participate in Federal, State, Regional, and local government sponsored recycling programs to reduce the volume of solid waste at the source. The Contractor shall collect glass bottles, aluminum cans, and paper at the job site for recycling.

j. An air pollution control plan detailing provisions to assure that dust, debris, materials, trash, etc., do not become air borne and travel off the project site.

k. A contaminant prevention plan that: identifies potentially hazardous substances to be used on the job site; identifies the intended actions to prevent introduction of such materials into the air, water, or ground; and details provisions for compliance with Federal, State, and local laws and regulations for storage and handling of these materials. In accordance with EM 385-1-1, a copy of the Material Safety Data Sheets (MSDS) and the maximum quantity of each hazardous material to be on site at any given time shall be included in the contaminant prevention plan. As new hazardous materials are brought on site or removed from the site, the plan shall be updated.

l. A waste water management plan that identifies the methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines. If a settling/retention pond is required, the plan shall include the design of the pond including drawings, removal plan, and testing requirements for possible pollutants. If land application will be the method of disposal for the waste water, the plan shall include a sketch showing the location for land application along with a description of the pre-treatment methods to be implemented. If surface discharge will be the method of disposal, a

copy of the permit and associated documents shall be included as an attachment prior to discharging the waste water. If disposal is to a sanitary sewer, the plan shall include documentation that the Waste Water Treatment Plant Operator has approved the flow rate, volume, and type of discharge.

m. Environmental Monitoring. The Contractor shall include in the plan the details of environmental monitoring requirements under the laws and regulations and a description of how this monitoring will be accomplished.

n. A historical, archaeological, cultural resources, and biological resources plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, and biological resources known to be on the project site: and/or identifies procedures to be followed if historical archaeological, cultural resources, and biological resources not previously known to be on site or in the area are discovered during construction. The plan shall include methods to assure the protection of known or discovered resources and shall identify lines of communication between Contractor personnel and the Contracting Officer.

## PART 2 PRODUCTS (Not Applicable)

## PART 3 EXECUTION

### 3.1 SPECIAL ENVIRONMENTAL PROTECTION REQUIREMENTS

#### 3.1.1 U.S. Department of Agriculture (USDA) Quarantined Considerations

The Contractor shall thoroughly clean all construction equipment at the prior job site in a manner that ensures all residual soil is removed and that egg deposits from plant pests are not present. The Contractor shall consult with the USDA Plant Protection and Quarantine (USDA - PPQ) jurisdictional office for additional cleaning requirements that may be necessary.

#### 3.1.2 Soil Disposal Areas on Government Property

Material disposal on Government property shall be disposed only in those areas designated on the contract drawings. Hazardous, toxic, and radiological wastes (HTRW) shall not be disposed of on Government property.

Disposal operations shall be managed and controlled to prevent erosion of soil or sediment from entering nearby waters or wetlands. Disposal operations shall be developed and managed in accordance with the grading plan shown on the drawings or as approved by the Contracting Officer.

#### 3.1.3 Disposal of Solid Wastes

Solid waste is rubbish, debris, waste materials, garbage, and other discarded solid materials (excluding clearing debris and hazardous waste as defined in following paragraphs). Solid waste shall be placed in containers and disposed on a regular schedule. All handling and disposal shall be conducted in such a way as to prevent spillage and contamination. The Contractor shall transport all solid waste off Government property and dispose of in compliance with Federal, State, and local requirements.

#### 3.1.4 Clearing Debris

Clearing debris is trees, tree stumps, tree trimmings, and shrubs, and leaves, vegetative matter, excavated natural materials (e.g., dirt, sand, and rock), and demolition products (e.g., brick, concrete, glass, and metals).

a. The Contractor shall collect trees, tree stumps, tree trimmings, shrubs, leaves, and other vegetative matter; and shall transport from Government property for proper disposal in compliance with Federal, State, and local requirements. The Contractor shall segregate the matter where appropriate for proper disposal. Untreated and unpainted scrap lumber may be disposed of with this debris where appropriate.

b. Demolition products shall be transported from Government property for proper disposal in compliance with Federal, State, and local requirements.

#### 3.1.5 Disposal of Contractor Generated Hazardous Wastes

Hazardous wastes are hazardous substances as defined in 40 CFR 261, or as defined by applicable State and local regulations. Hazardous waste generated by construction activities shall be removed from the work area and be disposed in compliance with Federal, State, and local requirements.

The Contractor shall segregate hazardous waste from other materials and wastes, and shall protect it from the weather by placing it in a safe covered location; precautionary measures against accidental spillage such as berming or other appropriate measures shall be taken. Hazardous waste shall be removed from Government property within 60 days. Hazardous waste shall not be dumped onto the ground, into storm sewers or open water courses, or into the sanitary sewer system.

#### 3.1.6 Fuels and Lubricants

Fueling and lubrication of equipment and motor vehicles shall be conducted in a manner that affords the maximum protection against spills and evaporation. Lubricants and waste oil to be discarded shall be stored in marked corrosion-resistant containers and recycled or disposed in accordance with Federal, State, and local laws and regulations.

### 3.2 HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES

#### 3.2.1 Known Historic, Archaeological, and Cultural Resources

There are no known historic, archaeological, and cultural resources associated with this project.

#### 3.2.2 Discovered Historic, Archaeological, and Cultural Resources

If during construction activities, items are observed that may have historic or archaeological value (e.g., anchors, ship wrecks, Native American human remains or associated objects), such observations shall be reported immediately to the Contracting Officer so that the appropriate authorities may be notified and a determination made as to their significance and what, if any, special disposition of the finds should be made. The Contractor shall cease all activities that may result in impact to these resources until the requirements of 36 CFR 800.11, Properties Discovered During Implementation of an Undertaking, are met. The



Contractor shall prevent his employees from trespassing on, removing, or otherwise disturbing such resources.

### 3.3 PROTECTION OF WATER RESOURCES

The Contractor shall keep construction activities under surveillance, management, and control to avoid pollution of surface and ground waters.

3.3.1 The Contractor shall perform discharge monitoring, inspections, and testing, reporting and record keeping as set forth below::

#### a. Turbidity Monitoring

The following sampling protocol shall be undertaken during the dredging and disposal operations. Sampling for the receiving water monitoring shall commence at least one week prior to the start of the dredging and disposal operations and continue at least one week following the completion of all such operations. Sampling shall be conducted a minimum of once a week during dredging and/or disposal operations. Sampling shall be conducted down current of the dredge and/or disposal sites at least one hour after the start of operations. All receiving water monitoring data shall be obtained via grab samples or remote electronic detection equipment. The Contractor shall perform Water Monitoring at the dredge site and nearshore disposal location (if nearshore disposal is utilized). Water samples shall be taken at the following stations:

<u>Station</u>	<u>Description</u>
(A).	30 meters up current of the dredging/disposal operations, safety permitting.
(B).	30 meters down current of the dredging/disposal operations, safety permitting.
(C).	100 meters down current of the dredging/disposal.
(D).	Control site (area not affected by dredging/disposal operations).
(E).	30 meters north of the beach / nearshore disposal site
(F).	30 meters south of the beach / nearshore disposal site
(C).	100 meters south of the beach / nearshore disposal site
(D).	Control site 100 meters north of the beach / nearshore disposal site

<u>Parameter</u>	<u>Units</u>	<u>Station</u>	<u>Frequency</u>
Oxygen	mg/l	A thru H	Weekly
Light Transmittance	% Transmittance	A thru H	Weekly
pH	pH Units	A thru H	Weekly
Suspended Solids	mg/l	A thru H	Twice per dredge cycle
TRPH	mg/l	A thru H	Twice per dredge cycle

Water column light transmittance values from stations C and D shall be averaged for the near surface (1 meter below the surface), mid-water, and bottom (1 meter above the bottom). If the difference in % light

transmittance is 40% or greater, water samples shall be collected at mid-depth from station C and analyzed for total suspended solids. At a minimum, water samples shall be collected at mid-depth from each station once during dredging and analyzed for chemical constituents. Analyte reporting limits shall be appropriately low to allow comparisons with water quality standards applicable to the harbor receiving waters.

Monitoring shall be conducted according to United States Environmental Protection Agency or California Department of Health Services approved test procedures as described in the current Title 40, CFR 136 and CFR 261, or the current California Code of Regulations Title 22, Article 11, as appropriate, unless other test procedures have been specified.

During sampling and measurement operations, the following observations shall be recorded by the individual performing such operations for each monitoring location:

- a. Name of project
- b. Date, exact location and time of sampling or measurements
- c. Name of individual performing sampling or measurements
- d. Speed and direction of current
- e. Tidal stage
- f. General weather conditions and wind velocity
- g. Appearance of trash, floatable material, grease, oil slick, or other objectionable material
- h. Discoloration and extent of visible turbidity plumes
- i. Any distinguishable odors
- j. Quantity of material dredged the previous day
- k. Cumulative total amount of material placed at nearshore disposal area to date
- l. Name of individual performing analyses
- m. Analytical techniques and/or methods to be used to analyze and interpret data
- n. Results

### 3.3.2 Floating Debris

During the performance of the work, the Contractor shall institute and enforce procedures to prevent spills and floating debris from fouling the local water and beach. Should these procedures fail, the Contractor shall promptly clean up all spills and debris. At the end of each work shift, loose materials on adjoining structures and debris in the water and on the beach shall be removed by the Contractor and disposed off site.

### 3.3.3 Other Discharge

Should the Contractor lose, dump, throw overboard, sink or misplace material, plant, machinery appliance, or cause pollution on the waters, the Contractor shall give immediate notice to the Contracting Officer and, if required shall boom, buoy or otherwise mark the location of the incident until the obstruction or pollution problem is removed. Should the Contractor refuse, neglect or delay compliance with these requirements, the necessary removal and cleanup may be deducted from the monies due or to become due to the Contractor.

### 3.3.4 Commitments

- a. The Contractor shall implement a water quality monitoring plan at the dredge site.
- b. If turbidity exceeds 40% of baseline readings, operations shall be modified to reduce turbidity to ambient levels.

## 3.4 PROTECTION OF FISH AND WILDLIFE RESOURCES

The Contractor shall keep construction activities under surveillance, management and control to minimize interference with, disturbance to and damage of fish and wildlife (endangered species and their habitat). Endangered species known to frequent the project area and their respective season include:

California least tern	15 April through 15 September.
California brown pelican	non-breeding individuals may occur year-round

### 3.4.1 Marine Mammals

Personnel shall not harass any marine mammals, fish, or waterfowl.

### 3.4.2 Dead or Injured Wildlife

The Contractor shall report any incidental take (dead or injured species) immediately to the Contracting Officer. The Contracting Officer shall consult with U.S. Fish and Wildlife Service immediately in the event of incidental take in the form of direct mortality through accidental death of California least tern or California brown pelican. Operations may be stopped if it is suspected that the impact of the taking causes an irreversible and adverse impact on the species.

## 3.5 PROTECTION OF AIR RESOURCES

Special management techniques as set out below shall be implemented to control air pollution by the construction activities. These techniques supplement the requirements of Federal, State, and local laws and regulations; and the safety requirements under this Contract. If any of the following techniques conflict with the requirements of Federal, State, or local laws or regulations, or safety requirements under this contract, then those requirements shall be followed in lieu of the following.

The Contractor shall keep construction activities under surveillance, management and control to minimize pollution of air resources.

### 3.5.1 Air Pollution Control District

All activities, equipment, processes, and work operated or performed by the Contractor in accomplishing the specified construction shall be in strict accordance with the San Diego Air Pollution Control District (SDAPCD) permit requirements and all Federal emission and performance laws and standards. The Contractor shall obtain a Permit to Operate from the San Diego Air Pollution Control District prior to commencement of work, pay all associated fees, and follow all permit requirements. Point of contact for SDAPCD is Mr. Ernie Davis, (858) 694-3930. The Contractor should schedule suitable time to acquire appropriate SCAQMD permits, waivers or credits.

Construction equipment shall be properly maintained to minimize release of diesel and hydrocarbon effluent. The Contractor shall follow all air quality standards, including emissions, fuel use, and fuel consumption standards.

### 3.5.2 Other Commitments

- a. Use clean, low sulphur fuel in dredges and/or catalytic converters.
- b. Use distillate oil in marine vessels and clean fuels for on dock equipment.
- c. Properly tune and maintain all construction equipment.
- d. Encourage employees to carpool.

### 3.6 NOISE

a. All internal combustion powered equipment shall be equipped with properly operating mufflers and kept in a proper state of tune to alleviate back-fires. Engines, if exposed, shall be fitted with protective shrouds to reduce motor noise. All portable and support equipment shall be located as far as possible from any sensitive areas.

b. Construction equipment shall be properly maintained and scheduled to minimize nuisance and unsafe noise effects to sensitive biological resources, residential areas, and socio-economic (tourist) environments.

c. The Contractor shall designate a disturbance coordinator responsible for responding to noise complaints. His/her name and telephone number shall be clearly posted at the construction site and at the County of Orange Public Facilities and Resources Department at 1901 Bayside Drive; Newport Beach, California. It is the responsibility of the disturbance coordinator to respond to complaints, determine the cause, and implement measures to mitigate the impact.

### 3.7 INSPECTION

If the Contracting Officer notifies the Contractor in writing of any observed noncompliance with contract requirements or Federal, State, or local laws, regulations, or permits, the Contractor shall inform the Contracting Officer of proposed corrective action and take such action to correct the noncompliance. If the Contractor fails to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action is taken. No time extensions will be granted or costs or damages allowed to the Contractor for any such suspension.

### 3.8 TRAINING OF CONTRACTOR PERSONNEL

Contractor personnel shall be trained in environmental protection and pollution control. The Contractor shall conduct environmental protection/pollution control meetings for all Contractor personnel monthly.

The training and meeting agenda shall include methods of detecting and avoiding pollution, familiarization with pollution standards, both statutory and contractual, installation and care of facilities (vegetative covers, etc.), and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control. Anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants, shall also be discussed. Training shall be provided on the identification of *Caulerpa taxifolia* and eelgrass. Other items to be discussed shall include recognition and protection of archaeological sites and artifacts.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01420

SOURCES FOR REFERENCE PUBLICATIONS

PART 1 GENERAL

1.1 REFERENCES

1.2 ORDERING INFORMATION

-- End of Section Table of Contents --

**SECTION 01420****SOURCES FOR REFERENCE PUBLICATIONS****PART 1 GENERAL****1.1 REFERENCES**

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization, (e.g. ASTM B 564 Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

**1.2 ORDERING INFORMATION**

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided. Documents listed in the specifications with numbers which were not assigned by the standards producing organization should be ordered from the source by title rather than by number. The designations "AOK" and "LOK" are for administrative purposes and should not be used when ordering publications.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)  
100 Barr Harbor Drive  
West Conshohocken, PA 19428-2959  
Ph: 610-832-9585  
Fax: 610-832-9555  
Internet: <http://www.astm.org>  
AOK 5/01  
LOK 3/01

**ENGINEERING MANUALS (EM)**

USACE Publications Depot  
Attn: CEIM-SP-D  
2803 52nd Avenue  
Hyattsville, MD 20781-1102  
Ph: 301-394-0081

**FEDERAL SPECIFICATIONS (FS)**

Order from:  
General Services Administration  
Federal Supply Service Bureau  
470 L'Enfant Plaza, S.W.  
Washington, DC 20407  
Ph: 202-619-8925  
Fax: 202-619-8978

Internet: <http://pub.fss.gsa.gov/>

CORPS OF ENGINEERS (COE)

Order CRD-C DOCUMENTS from:

U.S. Army Engineer Waterways Experiment Station

ATTN: Technical Report Distribution Section, Services  
Branch, TIC

3909 Halls Ferry Rd.

Vicksburg, MS 39180-6199

Ph: 601-634-2664

Fax: 601-634-2388

Internet: <http://www.wes.army.mil/SL/MTC/handbook/handbook.htm>

Order Other Documents from:

USACE Publications Depot

Attn: CEIM-SP-D

2803 52nd Avenue

Hyattsville, MD 20781-1102

Ph: 301-394-0081

Fax: 301-394-0084

Internet: <http://www.usace.army.mil/publications>

or <http://www.hnd.usace.army.mil/techinfo/index.htm>

AOK 5/01

LOK 6/00

DEPARTMENT OF COMMERCE (DOC)

Order Publications From:

National Technical Information Service

5285 Port Royal Road

Springfield, VA 22161

Ph: 703-605-6000

Fax: 703-605-6900

Internet: <http://www.ntis.gov>

AOK 5/01

LOK 6/00

-- End of Section --



SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01451

CONTRACTOR QUALITY CONTROL

**04/97**

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 PAYMENT

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

- 3.1 GENERAL REQUIREMENTS
- 3.2 QUALITY CONTROL PLAN
  - 3.2.1 General
  - 3.2.2 Content of the CQC Plan
  - 3.2.3 Acceptance of Plan
  - 3.2.4 Notification of Changes
- 3.3 COORDINATION MEETING
- 3.4 QUALITY CONTROL ORGANIZATION
  - 3.4.1 Personnel Requirements
  - 3.4.2 CQC System Manager
  - 3.4.3 CQC Personnel
  - 3.4.4 Additional Requirement
  - 3.4.5 Organizational Changes
- 3.5 SUBMITTALS AND DELIVERABLES
- 3.6 CONTROL
  - 3.6.1 Preparatory Phase
  - 3.6.2 Initial Phase
  - 3.6.3 Follow-up Phase
  - 3.6.4 Additional Preparatory and Initial Phases
- 3.7 TESTS
  - 3.7.1 Testing Procedure
  - 3.7.2 Testing Laboratories
    - 3.7.2.1 Capability Check
    - 3.7.2.2 Capability Recheck
  - 3.7.3 on site Laboratory
  - 3.7.4 Furnishing or Transportation of Samples for Testing
- 3.8 COMPLETION INSPECTION
  - 3.8.1 Punch-Out Inspection
  - 3.8.2 Pre-Final Inspection
  - 3.8.3 Final Acceptance Inspection
- 3.9 DOCUMENTATION
- 3.10 NOTIFICATION OF NONCOMPLIANCE
- 3.11 GOVERNMENT RESIDENT MANAGEMENT SYSTEM
- 3.12 PROJECT SCHEDULE

-- End of Section Table of Contents --

## SECTION 01451

## CONTRACTOR QUALITY CONTROL

04/97

## PART 1 GENERAL

## 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

## AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3740 (2001) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction

ASTM E 329 (2000b) Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

## 1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals having an "FIO" designation are for information only. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

## SD-01 Preconstruction Submittals

Project Schedule; G.

Contractor Quality Control (CQC) Plan; G.

## 1.3 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

## PART 2 PRODUCTS (NOT APPLICABLE)

## PART 3 EXECUTION

## 3.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "INSPECTION OF CONSTRUCTION." The quality control system shall consist of plans, procedures, and organization necessary to

produce an end product that complies with the contract requirements. The system shall cover all construction operations, both on site and offsite, and shall be keyed to the proposed construction sequence. The site project superintendent will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for the overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

### 3.2 QUALITY CONTROL PLAN

#### 3.2.1 General

The Contractor shall furnish for review by the Government, not later than 15 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "INSPECTION OF CONSTRUCTION." The plan shall identify personnel, procedures, control, instructions, test, records, and forms to be used. The Government will consider an interim plan for the first 15 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the features of work included in an accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started.

#### 3.2.2 Content of the CQC Plan

The CQC Plan shall include, as a minimum, the following to cover all construction operations, both on site and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents:

- a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. The staff shall include a CQC System Manager who shall report to the project superintendent.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters shall also be furnished to the Government.
- d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. These procedures

shall be in accordance with Section 01330 SUBMITTAL PROCEDURES.

- e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. (Laboratory facilities will be approved by the Contracting Officer.)
- f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.
- h. Reporting procedures, including proposed reporting formats.
- i. A list of the definable features of work. A definable feature of work is a task that is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. This list will be agreed upon during the coordination meeting.

### 3.2.3 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

### 3.2.4 Notification of Changes

After acceptance of the CQC Plan, the Contractor shall notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

### 3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The CQC Plan shall be submitted for review a minimum of 7 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both on site and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by

either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

### 3.4 QUALITY CONTROL ORGANIZATION

#### 3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure contract compliance. The Safety and Health Manager shall receive direction and authority from the CQC System Manager and shall serve as a member of the CQC staff. Personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly will also be included as part of the CQC organization. The Contractor's CQC staff shall maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take action necessary to ensure contract compliance. The CQC staff shall be subject to acceptance by the Contracting Officer. The Contractor shall provide adequate office space, filing systems, and other resources as necessary to maintain an effective and fully functional CQC organization. Complete records of all letters, material submittals, show drawing submittals, schedules, and all other project documentation shall be promptly furnished to the CQC organization by the Contractor. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

#### 3.4.2 CQC System Manager

The Contractor shall identify as CQC System Manager an individual within the on site work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager shall be a graduate engineer, graduate architect, or a graduate of construction management, with a minimum of 5 years construction experience on construction similar to this contract. This CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. The CQC System Manager shall be assigned as System Manager but may have duties as project superintendent in addition to quality control. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

#### 3.4.3 CQC Personnel

In addition to CQC personnel specified elsewhere in the contract, the Contractor shall provide as part of the CQC organization specialized personnel to assist the CQC System Manager for the following areas: civil and dredging. These individuals may be employees of the prime or subcontractor; be responsible to the CQC System Manager; be physically present at the construction site during work on their areas of responsibility; have the necessary education and/or experience in accordance with the experience matrix listed herein. These individuals may perform other duties but must be allowed sufficient time to perform their assigned quality control duties as described in the Quality Control Plan.

## Experience Matrix

	Area	Qualifications
a.	Civil	Graduate Civil Engineer with 2 years experience in the type of work being performed on this project or technician with 5 yrs related experience
b.	Dredging	Experienced engineer or technician with 10 years of marine dredging experience

## 3.4.4 Additional Requirement

In addition to the above experience and education requirements the CQC System Manager shall have completed the course entitled "Construction Quality Management For Contractors". This course is periodically offered, contact U.S. Army Corps of Engineers, Los Angeles District, Emmanuel Molina, at (213) 452-3382 for information.

## 3.4.5 Organizational Changes

The Contractor shall maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

## 3.5 SUBMITTALS AND DELIVERABLES

Submittals, if needed, shall be made as specified in Section 01330 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals and deliverables are in compliance with the contract requirements.

## 3.6 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of work as follows:

## 3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of reference codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the

Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.

- b. A review of the contract drawings.
- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. Review of provisions that have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. A review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.
- i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- j. Discussion of the initial control phase.
- k. The Government shall be notified at least 24 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

### 3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.
- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve all differences.



- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government shall be notified at least 24 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.
- g. The initial phase should be repeated for each new crew to work on site, or any time acceptable specified quality standards are not being met.

### 3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

### 3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if the quality of on-going work is unacceptable, if there are changes in the applicable CQC staff, on site production supervision or work crew, if work on a definable feature is resumed after a substantial period of inactivity, or if other problems develop.

## 3.7 TESTS

### 3.7.1 Testing Procedure

The Contractor shall perform specified or required tests to verify that control measures are adequate to provide a product that conforms to contract requirements. Upon request, the Contractor shall furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of a Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site. The Contractor shall perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.

- e. Results of all tests taken, both passing and failing tests, shall be recorded on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test shall be given. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. An information copy of tests performed by an offsite or commercial test facility shall be provided directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.

### 3.7.2 Testing Laboratories

#### 3.7.2.1 Capability Check

The Government reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing procedures and techniques. Laboratories utilized for testing soils, concrete, asphalt, and steel shall meet criteria detailed in ASTM D 3740 and ASTM E 329.

#### 3.7.2.2 Capability Recheck

If the selected laboratory fails the capability check, the Contractor will be assessed a charge of \$ 675 to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the contract amount due the Contractor.

#### 3.7.3 on site Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

#### 3.7.4 Furnishing or Transportation of Samples for Testing

Costs incidental to the transportation of samples or materials shall be borne by the Contractor. Samples of materials for test verification and acceptance testing will be tested at a commercial laboratory approved by the Contracting Officer.

### 3.8 COMPLETION INSPECTION

#### 3.8.1 Punch-Out Inspection

Near the completion of all work or any increment thereof established by a completion time stated in the Special Clause entitled "Commencement, Prosecution, and Completion of Work," or by specifications, the CQC System Manager shall conduct an inspection of the work. A punch list of items which do not conform to the approved drawings and specifications shall be prepared and included in the CQC documentation, as required by paragraph DOCUMENTATION. The list of deficiencies shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall

notify the Government that the facility is ready for the Government Pre-Final inspection.

### 3.8.2 Pre-Final Inspection

The Government will perform this inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or any particular increment thereof if the project is divided into increments by separate completion dates.

### 3.8.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance at this inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups, and major commands may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14 days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

## 3.9 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subcontractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase should be identified (Preparatory, Initial, Follow-up). List deficiencies noted along with corrective action.

- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- g. Off-site surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.
- j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every 7 days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

### 3.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

### 3.11 GOVERNMENT RESIDENT MANAGEMENT SYSTEM

The use of the Government Resident Management System for Contractor quality control is optional for this contract. If the Contractor chooses to utilize this system, the CQC Programming Module (a computerized executable file which is DOS based and operates on a minimum 80386 IBM compatible computers) will be furnished by the Governmenta.

## 3.12 PROJECT SCHEDULE

Pursuant to the Contract Clause SCHEDULES FOR CONSTRUCTION CONTRACTS (52.236-15), the Contractor shall prepare and submit to the Contracting Officer for approval three copies of a practicable Project Schedule showing the order in which he proposes to perform the work, and the dates on which the Contractor contemplates starting and completing the several salient features of the work. A progress report, showing the progress of the work in relation to the project schedule, shall be submitted to the Contracting Officer not less than weekly. The project schedule shall be revised and resubmitted as needed, or whenever the actual progress is substantially different than the proposed schedule.

-- End of Section --

**CONSTRUCTION QUALITY CONTROL REPORT  
(SAMPLE)**

CONTRACT NO. \_\_\_\_\_

HARBOR & PROJECT \_\_\_\_\_ CONTRACTOR \_\_\_\_\_

DATE \_\_\_\_\_ WEATHER \_\_\_\_\_ DREDGING CYCLE: \_\_\_\_\_

SEA CONDITION \_\_\_\_\_ SWELL/DIRECTION \_\_\_\_\_ TURBIDITY \_\_\_\_\_

PERIOD COVERED \_\_\_\_\_ DREDGE \_\_\_\_\_ MATERIAL \_\_\_\_\_

NO. & LOCATION OF DREDGE SAMPLES TAKEN: \_\_\_\_\_

QUANTITY

CUT

This period total \_\_\_\_\_ Location \_\_\_\_\_

This period per pump hour \_\_\_\_\_ Cut No. \_\_\_\_\_ Sta. \_\_\_\_\_ To Sta. \_\_\_\_\_

To date total \_\_\_\_\_ Avg. Width \_\_\_\_\_ Depth before \_\_\_\_\_

Advance \_\_\_\_\_ Depth after \_\_\_\_\_

Avg. Bank \_\_\_\_\_

FILL PIPELINE

LOCATION      QUANTITY TO DATE

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Floating \_\_\_\_\_ Total \_\_\_\_\_  
Submerged \_\_\_\_\_ Avg. Total \_\_\_\_\_  
Shore \_\_\_\_\_

LABOR DREDGE INFORMATION

# of Crew Leverman

Shift #1 \_\_\_\_\_

Shift #2 \_\_\_\_\_

Shift #3 \_\_\_\_\_

\*Pump Speed (RPM) \_\_\_\_\_

\*Cutter RPM \_\_\_\_\_

\*Cutter type \_\_\_\_\_

\*Runner Diameter \_\_\_\_\_

\*Applicable to cutter suction/suction dredging only.

DOWN TIME

TIME DOWN

TIME RESTART

REASONS

TIME

_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

TOTAL

EQUIPMENT \_\_\_\_\_

DAILY SOUNDINGS

VERTICAL

HORIZONTAL

Minimum \_\_\_\_\_

Maximum \_\_\_\_\_

Average \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

REMARKS \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

SUBMITTED BY: \_\_\_\_\_

SIGNED: \_\_\_\_\_

# HYDRAULIC DAILY REPORT

DREDGE \_\_\_\_\_

WEATHER \_\_\_\_\_

WIND \_\_\_\_\_

SEA \_\_\_\_\_

REPORT NO. \_\_\_\_\_

CONTRACT NO. \_\_\_\_\_

DATE \_\_\_\_\_

TIDE GAGE # \_\_\_\_\_

HORIZONTAL  
POS. \_\_\_\_\_

DREDGING CYCLE: \_\_\_\_\_

## WORK LOCATION SKETCH (Include Dredge Advances, Stationing, & Channel Widths)

---



---



---

## ACTIVITY

Non-Effective Time (hours)	Today	To Date
1. Mob/demob		
2. New area move		
3. Traffic		
4. Weather		
5. Relocate Pipe		
6. Repair Pipe		
7. Handling Anchors		
8. Clearing Pump		
9. Clearing Pipe		
10. Clearing Cutter		
11. Clearing Suction Head		
12. Booster Offline		
13. Dredge Repair		
14. Survey Delay		
15. Other (see remarks)		
TOTALS		

Effective Time (hours)		Today	To Date
1. Dredge/booster			
2. Other (see remarks)			
TOTALS			
Production	Unit	Today	To Date
1. Avg. cut width	ft.		
2. Avg. cut depth	ft.		
3. Advance	ft.		
4. Pipe Change	ft.		

## REMARKS

---



---



---



---



---



---



---



---





DREDGE	REPORT NO.
WEATHER	CONTRACT NO.
WIND	DATE
SEA	TIDE GAGE #
DREDGING CYCLE:	HORIZONTAL POS.

---

---

---

---

Non-Effective Time (hours)	Today	To Date
1. Mob/demob		
2. New area move		
3. Traffic		
4. Weather		
5. Scow Change		
6. Scow Wind		
7. Scow Tug		
8. Scow Repair		
9. Dredge Maintenance		
10. Dredge Repair		
11. Survey Delay		
12. Other(see remarks)		
Non-Effective Totals		

Effective Time (hours)		Today	To Date
1. Dredging			
2. Other (see remarks)			
Effective Totals			
Production	Unit	Today	To Date
1. Avg. cut width	ft.		
2. Avg. cut depth	ft.		
3. Area	sq.ft.		
4. Travel time	hrs.		

ID	START LOAD TIME	STOP LOAD TIME	TOTAL LOAD HRS	TODAY CY	TO DATE CY
TOTALS					

DATE: \_\_\_\_\_

[illegible]

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE WORK

SECTION 02000

MOBILIZATION AND DEMOBILIZATION

**02/99**

PART 1 GENERAL

1.1 SUBMITTALS

1.2 MOBILIZATION AND DEMOBILIZATION

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section Table of Contents --

SECTION 02000

MOBILIZATION AND DEMOBILIZATION  
**02/99**

PART 1 GENERAL

1.1 SUBMITTALS

None

1.2 MOBILIZATION AND DEMOBILIZATION

Mobilization and Demobilization shall include transporting the dredge and all items of attendant dredge plant to the site of the work, setting up the dredge and other equipment, and laying of pipelines and otherwise placing the entire plant in condition for effective dredging. If Contractor utilizes beach disposal, the trenching and laying of buried pipe and other associated work will be part of mobilization and demobilization. Upon completion of each dredge cycle, the Contractor's plant and equipment, including Contractor's trailer(s), shall be removed from the site.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

# SECTION TABLE OF CONTENTS

## DIVISION 02 - SITE WORK

### SECTION 02020

#### DREDGING

**02/99**

#### PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 REQUIRED WORK
- 1.4 AVOIDANCE OF EXISTING CONSTRUCTION
  - 1.4.1 Existing Breakwaters and Jetties
  - 1.4.2 City of Oceanside Ocean Outfall
- 1.5 CHARACTER OF MATERIALS

#### PART 2 PRODUCTS (NOT APPLICABLE)

#### PART 3 EXECUTION

- 3.1 DREDGE AND DISPOSAL PLAN
- 3.2 DISPOSAL OF DREDGED MATERIAL
  - 3.2.1 General
  - 3.2.2 Beach Disposal
  - 3.2.3 Nearshore Disposal
- 3.3 ELECTRONIC POSITIONING SYSTEM FOR NEARSHORE AND OFFSHORE DISPOSAL
  - 3.3.1 EPS/DGPS Configuration
  - 3.3.2 Shore-Based Control
  - 3.3.3 Disposal Vessel Location
  - 3.3.4 Calibration
  - 3.3.5 Backup Equipment
- 3.4 ADDITIONAL MONITORING
  - 3.4.1 Hopper and Hydraulic Dredges
  - 3.4.2 Barges and Scows
- 3.5 DREDGE QUANTITIES FOR PAST 3-YEAR DREDGE CYCLE
- 3.6 OVERDEPTH AND SIDE SLOPES
  - 3.6.1 Overdepth
  - 3.6.2 Side Slopes
  - 3.6.3 Excessive Dredging
  - 3.6.4 Advance Maintenance Depth
- 3.7 SAMPLING OF MATERIAL
- 3.8 CONTRACTOR'S SURVEYS
  - 3.8.1 Survey Data
  - 3.8.2 Sounding Data Standards
  - 3.8.3 Positioning System
  - 3.8.4 Survey Firm Acceptance
  - 3.8.5 Data Processing
- 3.9 PRE-DREDGE AND FINAL SURVEYS
- 3.10 METHOD OF SOUNDINGS
- 3.11 SHOALING
- 3.12 REPORTING REQUIREMENT
- 3.13 FINAL EXAMINATION AND ACCEPTANCE

-- End of Section Table of Contents --

## SECTION 02020

DREDGING  
02/99

## PART 1 GENERAL

## 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

## CORPS OF ENGINEERS (COE)

EM 1110-1-1003 (August 1996) Navstar Global Positioning System Surveying

EM 1110-2-1003 (January 2002) Hydrographic Surveying

## 1.2 SUBMITTALS

Government approval is required for all submittals with a "GA" designation; submittals having an "FIO" designation are for information only. The following shall be submitted in accordance with SECTION 01330 SUBMITTAL PROCEDURES:

## SD-01 Preconstruction Submittals

Dredge and Disposal Plan; G

## SD-03 Product Data

Dredge Disposal Records

## SD-04 Samples

Sediment Samples

## SD-06 Test Reports

Daily Report of Operations

## 1.3 REQUIRED WORK

In the area to be dredged, all materials shall be removed and disposed of as indicated. Should material which cannot be removed without unreasonable methods be encountered, the Contractor shall remove all overlying material which in the judgment of the Contracting Officer Representative, can be removed. Nothing in this paragraph shall be construed as prohibiting the removal of excepted material by special means at prices agreed upon and approved in accordance with the CONTRACT CLAUSE: DIFFERING SITE CONDITIONS.

The dredging area shall be dredged to the indicated depths below mean lower low water (MLLW). Debris shall become the property of the Contractor and shall be removed from the site.

#### 1.4 AVOIDANCE OF EXISTING CONSTRUCTION

##### 1.4.1 Existing Breakwaters and Jetties

The Contractor shall conduct dredging operations in such a manner as to prevent undermining of the breakwaters and jetties. Excessive or unnecessary dredging may result in an unstable condition at the toe of the structures. The Contractor will be required to strictly adhere to the indicated dredging template when working near any structures, and shall be responsible for repairing any damage which may result from failure to comply with the requirements of these specifications.

##### 1.4.2 City of Oceanside Ocean Outfall

An ocean sewer outfall is located approximately 120 meters south of Witherby Street as shown on the drawings. If the nearshore disposal site is utilized, the Contractor shall protect this outfall by keeping all operations, including the setting of anchors, marker buoys, etc., at least 50 meters away from the outfall. The Contractor shall verify the location and alignment of the outfall prior to commencing nearshore disposal operations.

#### 1.5 CHARACTER OF MATERIALS

The material to be removed consists primarily of unconsolidated, poorly-graded sand, silty sand and sandy silt. Tree stumps, tires, trash and other debris which has been deposited within the project boundaries since the last dredging episode may be encountered. Limited amounts of gravels, cobbles and boulders may be encountered, particularly near existing breakwaters, jetties and groins. Past maintenance dredging activities occasionally encountered large breakwater stone.

Sand Bypass Piping. The Oceanside Experimental Sand Bypass System was removed in 1997. However, remnants of the cross channel discharge pipeline, a 16-inch HDPE, may still exist within the harbor. A length of 16-inch HDPE pipe was encountered in the entrance channel near the south jetty spur during the last dredging event, February 2000. In addition to the 16-inch HDPE line, concrete collar weights utilized to anchor the cross-channel discharge line may be encountered along the east side of the Del Mar Channel. The collar weights were initially placed in 1987/88 and are approximately 2 to 3 cubic feet in size.

#### PART 2 PRODUCTS (NOT APPLICABLE)

#### PART 3 EXECUTION

##### 3.1 DREDGE AND DISPOSAL PLAN

The Contractor shall submit a Dredge and Disposal Plan indicating the methods and equipment he proposes to use to dredge, position and dispose. The plan shall be submitted to the Contracting Officer for approval, for each dredge cycle of this contract, at least 20 days prior to start of dredging operations and shall also include, as a minimum, the following information:

- a. Method of dredging and disposal, and name of dredge.



- b. Order of dredging operations and layout of dredging and disposal areas, and anticipated time progress of dredging on a weekly basis.
- c. Layout of all buoys, anchors, pipelines, and ancillary equipment. Time frame for placement of pipeline (if pipeline is used).
- d. Method and equipment for transporting and placing material at the disposal site, and equipment that will be working on the beach.
- e. For beach disposal, a beach disposal plan indicating the targeted beach width of the fill, the starting point of the fill, etc.
- e. Scow dimensions, capacities and names of scows.
- f. A copy of the Daily Report Form to be used for dredging operations.
- g. Lighting plan for night work.
- h. Layout of dredge, including: dimensions; location of engines, fuel storage, electrical/transformer rooms; description of engine types and horsepower ratings, types and size of generating equipment, fuel storage capacity, and vertical clearance. A copy of this information shall be provided to the local fire fighting agency.

### 3.2 DISPOSAL OF DREDGED MATERIAL

#### 3.2.1 General

Dredged material shall be transported and deposited within the disposal limits of the area indicated on the drawings and as specified herein after. Any dredged material that is deposited other than in the area indicated on the drawings, or as approved by the Contracting Officer, will not be included in the measurement and the Contractor may be required to remove such misplaced material and deposit it where directed at his own expense. Debris and other unsuitable materials encountered shall become the property of the Contractor and shall be removed from the site. The Contractor may elect to use the beach disposal site and/or the nearshore disposal site, but shall submit his plan in accordance with paragraph: Dredge and Disposal Plan.

#### 3.2.2 Beach Disposal

If beach disposal is performed, then the Contractor shall provide necessary equipment to shape, groom and dress the beach during fill operations. Disposal operations shall be conducted in such a manner so as to capture the maximum amount of sand and to widen the beach in the most efficient manner, including conducting beach operations 24-hours a day.

Slotted discharge pipes, multiple discharge points or other approved means shall be employed to minimize loss of dredged material.

Outlets of existing storm drain pipes in the disposal area shall be covered prior to placing the fill to protect them from being clogged with fill material. After the disposal operations, the covers shall be removed.

It is anticipated that disposal will begin approximately 100 meters downcoast of Tyson Street and proceed southward as the beach is brought to

grade and prescribed width. Because the amount of material required for a given width of fill cannot be accurately determined until the fill has been placed, the width may be adjusted from time to time as work progresses. The beach fill shall be graded to a reasonably smooth, uniform surface, sloped toward the ocean as indicated or as directed.

At the end of the dredge cycle beach nourishment, the Contractor shall provide a 1-page report listing the beach nourishment information, to include but not be limited to:

- start and end positions of the beachfill
- width of the nourished beach
- start and end dates of beachfill construction
- significant events or problems encountered during the beachfill (i.e any storms that eroded the beach)

### 3.2.3 Nearshore Disposal

a. If the Contractor chooses nearshore disposal, then the dredge material shall be placed in the designated nearshore disposal area. The approximate location of the nearshore disposal area is indicated on the plans. Prior to the disposal of any material in the nearshore disposal area, the corners will be defined by the Contracting Officer. The Contractor shall be responsible for marking the corners of the disposal area with approved buoys and making periodic inspections of the buoy locations. The dredge material shall be deposited in such a manner so as to create a berm approximately parallel to the shoreline. The mound shall be located between the -4.0 and -8.0 meter MLLW contours. Disposal in the nearshore disposal area shall advance only when operational technique, under keel clearance or equipment considerations will permit safe operations.

b. Dredge Disposal Records: For nearshore disposal, the Contractor shall record disposal information. A spreadsheet shall be submitted to the Contracting Officer's Representative listing:

- \* disposal number;
- \* date;
- \* time at commencement and completion of disposal, recorded to the nearest minute;
- \* disposal area (i.e. Oceanside nearshore);
- \* easting and northing of disposal;
- \* quantity of disposal (cubic meters);
- \* cumulative quantity;
- \* area from which the load was dredged (i.e. Station).

<u>Dump#</u>	<u>Date</u>	<u>Time</u>	<u>Disposal Area</u>	<u>Easting</u>	<u>Northing</u>	<u>Qty</u>	<u>Cumulative Qty</u>	<u>Area Dredged (Station)</u>

The spreadsheet shall be produced in Microsoft Excel and e-mailed to the Contracting Officer's Representative daily.

### 3.3 ELECTRONIC POSITIONING SYSTEM FOR NEARSHORE AND OFFSHORE DISPOSAL

The Contractor shall obtain, operate, and maintain a short range Electronic Positioning System (EPS) or Differential Global Positioning System (DGPS) for nearshore and offshore disposal operations. This EPS or DGPS shall be established, operated, and maintained by the Contractor when disposal is

actively underway. The EPS or DGPS shall be capable of displaying and recording the disposal vessel's location in the State Plane Coordinates System based on the California Lambert Conformal Projection System for Zone 5 (SPCS 83 Meters) at 30 second time intervals while traveling to or from the disposal site and during disposal operations. The EPS or DGPS shall be activated at least 1,000 meters from the disposal site when transiting, and shall not be deactivated until at least 1,000 meters from the site on the return trip. Positional data shall be annotated for the time when actual dumping begins and ends and may be required to be taken at more frequent intervals than specified herein above. A record of each dump's positional data, automatically correlated with time, and annotated with date and eccentric distance measurement, if any, shall be submitted to the Contracting Officer as a part of the Daily Quality Control record. The Contractor shall provide access for the Contracting Officer to the EPS or DGPS equipment as part of the Government's quality assurance responsibility.

### 3.3.1 EPS/DGPS Configuration

The EPS or DGPS shall be similar, or equal, in design, performance, accuracy, operation characteristics, and frequency to equipment specified in the following technical materials:

COE EM 1110-1-1003 Navstar Global Positioning System Surveying  
and COE EM 1110-2-1003 Hydrographic Surveying

Information on the above mentioned manuals may be obtained from: U.S. Army Corps of Engineers, Los Angeles District. It is emphasized that Differential GPS positioning techniques shall be used for GPS surveying and further emphasized that an EPS system with a low and medium frequency (long-range navigation system) will not comply with the above specifications. The complete system shall be subject to the approval of the Contracting Officer.

### 3.3.2 Shore-Based Control

The Contractor shall establish horizontal control necessary to locate active and/or passive short range EPS or DGPS transmitter/receiver devices.

Survey control shall meet third order, class I, accuracy standards in accordance with COE EM 1110-2-1003 "Hydrographic Surveying". The Contractor shall obtain all necessary permits, rights-of-entry, or leases required to operate and maintain shore-based electronic equipment on public/private property. The actual number of shore-based control points shall be determined by the Contractor and shall be determined by the operating characteristics of the approved system (i.e., circular). As a minimum, the EPS shall provide at least three redundant lines-of-position from the shore-based network, and for DGPS, ranges from 4 (minimum) or more satellites will be needed for 3-dimensional positioning. The shore-based control points shall be located such that the generated lines-of-position shall intersect at the final vessel location at not less than 40 degrees.

### 3.3.3 Disposal Vessel Location

Except as specified herein after, electronic positioning data shall be received, displayed, and recorded on board the disposal vessel. Positional data may be received, displayed, and recorded on a towing or other adjacent vessel provided the eccentric distance between the vessels is less than 30 meters and that the eccentric distance and bearings remain essentially constant for each successive disposal operation. Eccentric distance measurements shall be computed by means of an electronic data

transmitter/telemetry system. Gyro-radar distance/bearing measurements will not be permitted for eccentric distance measurements. Eccentric coordinates, if any, shall be clearly identified and computed on the hard copy positional record required under paragraph: Electronic Positioning System.

#### 3.3.4 Calibration

EPS calibration techniques and calibration requirements (checklist) for DGPS shall conform to standard hydrographic surveying practice in accordance with Chapters 5 and 6 of COE EM 1110-2-1003, "Hydrographic Surveying". The Contractor shall be responsible for maintaining effective, accurate, and reliable EPS calibration, including periodic survey checks throughout the duration of the contract. Calibration records shall be submitted as part of the daily Quality Control records. Degradation in offshore positional accuracy during the course of this contract may cause a suspension of disposal operations.

#### 3.3.5 Backup Equipment

The Contractor shall provide and maintain the following backup equipment:

For EPS System:

- One shore control transmitter/receiving device.
- One line printer and/or plotter.
- One offshore guidance controller.
- One power supply.
- Spare parts kit for the receiver.

For GPS System:

- One Complete Differential GPS (DGPS) equipment and accessories.

In the event of a failure of the EPS or DGPS, the Contractor shall immediately notify the Contracting Officer.

### 3.4 ADDITIONAL MONITORING

#### 3.4.1 Hopper and Hydraulic Dredges

The Contractor shall provide:

- a. Continuous records of measurement of bulk density and mass flow rate with time, and location - cutterhead/draghead coordinates (horizontal and vertical). Data shall be recorded electronically and shall be made available in time increments as designated by the Contracting Officer and in either printed record or electronic format as designated by the Contracting Officer.
- b. Records of continuous loading of hoppers, barges, or scows based on hull displacement (load charts).

These records shall be submitted to the Contracting Officer daily with the Quality Control Reports.

#### 3.4.2 Barges and Scows

The Contractor shall provide a record of the measurements of the draft of the hull and freeboard of bins of each barge or scow when empty and prior

to disposal operations. Measurement for displacement shall be taken at each corner, on the outside of the barge or scow, immediately before the start of a disposal operation. These records shall be submitted to the Contracting Officer daily with the Quality Control Reports.

### 3.5 DREDGE QUANTITIES FOR PAST 3-YEAR DREDGE CYCLE

Quantity of material available within the dredge prism as of the previous 3 dredge cycles, pre-dredge surveys, is shown in the following table, as well amount of material removed to the dredge prism. The estimated quantity specified in the Bid Schedule is based upon these numbers and the estimated budget for the particular cycle.

<u>Area</u>	<u>Available Quantity (Cubic Meters)</u>	<u>Removed (Cubic Meters)</u>
	January 2001 pre-dredge	
Entrance Channel	206,900	48,600
Oceanside Channel	12,400	0
Del Mar Channel	152,000	12,400
	December 2001 pre-dredge	
Entrance Channel	315,000	260,000
Oceanside Channel	-	0
Del Mar Channel	146,000	0
	February 2003 pre-dredge	
Entrance Channel	190,000	154,000
Oceanside Channel	26,000	11,500
Del Mar Channel	160,000	77,000

Quantities shown include overdepth. Removed quantities are based upon quantities from within the dredge prism. Quantities removed from beyond the dredge prism are not represented. Overdepth dredging will be allowed to the limits specified in paragraphs: Overdepth and Excessive Dredging.

### 3.6 OVERDEPTH AND SIDE SLOPES

#### 3.6.1 Overdepth

To cover inaccuracies of the dredging process, a 0.6 meter allowable overdepth applies to this contract. Material dredged from below the allowable overdepth will not be estimated and will not be included in the measurement of work.

#### 3.6.2 Side Slopes

Material actually removed within limits approved by the Contracting Officer, shall provide for final side slopes not flatter than those indicated on the drawings and will be estimated and paid for. The Contractor may dredge material in original position or may dredge below the pay slope plane at the bottom of the slope to allow for sloughing of upslope material capable of falling into the cut (box dredge). However, material removed below any pay slope plane will not be estimated for payment. In computing the limiting amount of side slope dredging, the overdepth indicated on the drawings, measured vertically, will be used. The quantity of material to be paid for shall not be in excess of that originally lying above this limiting slope. Side slopes are given for pay

purposes only and are not necessarily the angle of repose of the soil. Sloughing side slopes shall not be the basis for claims against the Government. End slopes, where indicated on the drawings, shall be treated in the same manner as side slopes.

Box cutting of side slopes will not be allowed near the breakwaters and jetties.

### 3.6.3 Excessive Dredging

Material taken from beyond the allowable overdepth limits may be deducted from the total amount dredged as excessive overdepth dredging, or excessive side-slopes dredging. Materials dredged from below the depth limit which result in extra costs shall be the responsibility of the Contractor. Nothing here shall be construed to prevent the inclusion in the measurement of material dredged for the removal of shoals performed in accordance with the applicable provisions of the paragraphs: FINAL EXAMINATION AND ACCEPTANCE or SHOALING.

### 3.6.4 Advance Maintenance Depth

For the Entrance Channel and Advance Maintenance Areas, any material removed from below the advance maintenance depth (indicated on the drawings) will not be included in the measurement of work accomplished. Due to inaccuracies of the dredging process, the Contractor will only be required to remove material to within 0.6 meters above the advance maintenance dredge depth. However, any material removed to the advance maintenance dredge depth will be included in the measurement of work accomplished.

### 3.7 SAMPLING OF MATERIAL

The Contractor shall obtain each dredge cycle representative Sediment Samples at the discharge point as material is being discharged onto the beach, or in the case of a hopper dredge or scow, as material is placed into the hopper bin or scow. The exact location and depth of each sample shall be as directed by the Contracting Officer during the dredging operation. The number of required samples for each dredge cycle shall be as follows:

<u>Area</u>	<u>Number of Samples Required</u>
Entrance Channel	3
Oceanside Channel	3
Del Mar Channel	3

The samples shall be taken at evenly spaced intervals of time and volume as each of the areas is dredged. Each sample (water extracted) shall be not less than one (1) liter of slurry and shall be obtained in clear plastic bottles. The sample bottles shall be labeled in indelible ink with the sample number, date sampled, and name of person obtaining sample. Sample bottle lids shall be securely fastened to prevent spillage or leakage during shipment. Sample bottles shall be placed in a suitable shipping container with adequate cushioning to prevent breakage during shipment. The samples shall be delivered to the address specified herein below at weekly intervals, or at such other times as may be determined by the Contracting Officer.

A Dredge Sample Data Form with the description of the dredge cut location by coordinates and stationing, dredge cut elevation, placement location and description of where sample was taken, date, time, sample number, and the name of the person who collected the sample shall accompany each sample. The sample form shall be placed in a waterproof sealed plastic bag for protection during shipment. A copy of a sample form is provided at the end of this section.

A copy of the sample form shall be submitted to the Contracting Officer's Representative along with the transmittal form.

The Contractor shall notify the Contracting Officer's Representative 48 hours in advance of sample collection. Samples shall be delivered to:

U.S. Army Corps of Engineers  
ATTN: Baseyard Soils Laboratory  
645 North Durfee Avenue  
South El Monte, CA 91733-4399  
Attn: Art Moncayo

Tel: (626) 401-4095

### 3.8 CONTRACTOR'S SURVEYS

#### 3.8.1 Survey Data

Reference is made to SECTION 00800: SPECIAL CONTRACT REQUIREMENTS, QUANTITY SURVEYS, FAR 52.236-16 which requires final payment computations to be based upon Government original and final surveys. Progress payments or evidence (condition surveys) supporting extreme weather (storm) related shoaling, will be based upon Contractor's hydrographic surveys. The Contractor's survey shall provide full coverage of an entire area, such as Entrance Channel, Oceanside Channel, or Del Mar Channel, for which progress payment or evidence of storm-related shoaling is being submitted.

It is further emphasized that only condition surveys supporting extreme weather (storm) - related shoaling will be considered for payment in addition to the government surveys, provided that the Contractor's surveys clearly show the condition before and after each shoaling event and the condition after removal of material from the shoaled area. Survey data which does not meet all applicable requirements and quality assurance verifications will not constitute a valid request for payment of shoaling.

Contractor's hydrographic surveys shall be performed electronically

(automated) and the data shall be provided and submitted to the Government on an electronic media (IBM compatible, ASCII format) in delimited files of easting, northing, and depth (x,y,z), where the depth is indicated as negative if recorded below MLLW. The first lines of the data file will list the information as follows:

- \* Project Name (Oceanside Harbor Maintenance Dredging)
- \* Surveyor's Name and Company
- \* Area Surveyed
- \* Type of Survey and Date of Survey (i.e. Pre-dredge, 1/22/2003)
- \* Vertical Datum
- \* Horizontal Datum
- \* Tide Gage Location

These first 7 lines will be preceded by an asterisk (\*), which indicates a comment line.

A plot of soundings will accompany the x,y,z data and all data shall be collected and plotted in metric units (meters).

### 3.8.2 Sounding Data Standards

The Contractor's hydrographic surveys for progress payment or evidence supporting extreme(storm) weather-related shoaling shall meet or exceed the survey standards listed in EM 1110-2-1003 (Hydrographic Surveying) for Class I surveys. Surveys shall be in the State Plane Coordinate System of 1983 - meters (SPCS 83), Zone 6, State of California, and be performed by an independent hydrographic survey contractor with at least three (3) years of experience in hydrographic surveying of navigable channels and have either a current Land Surveyor's or a Professional Engineer's license, authorized to certify surveys in the State of California. The Hydrographic Surveyor firm selected by the Contractor must be approved by the Contracting Officer prior to performing surveys for this contract.

### 3.8.3 Positioning System

It is required that hydrographic surveys shall be conducted using an Automated Range-Azimuth Positioning System or Differential Global Positioning System (DGPS) with positional accuracy of +/- 3 meters (1 DRMS) or exceed the survey standards listed in EM 1110-1-1003 and EM 1110-2-1003 that is linked to an automated (digital) depth recording device capable of continuous logging of x,y,z positional data with depth measurement resolution to the nearest five-hundredths (5/100) of a meter. Digital depths shall be supplemented by analog depth records if survey is performed by single beam echosounder. Sounding lines shall be verified by crosslines at least 10 percent of the principal lines and along the centerline of channel. Distance between successive soundings (sounding interval) shall be no more than 2 meters. Soundings shall be reduced to sounding datum (Mean Lower Low Water) by using actual tides and other appropriate corrections resulting in an accuracy of +/- 0.2 meters from actual depth.

### 3.8.4 Survey Firm Acceptance

For the Contracting Officer to approve the selected survey firm, the Contractor must provide documentation indicating that modern electronic horizontal positioning and sounding system equipment will be used for the surveys to be performed as well as documentation verifying the experience of the operators using the equipment. Typical information that will be required, as a minimum, includes the name, model, and year of manufacture



of the electronic equipment, the electronic frequencies of the horizontal positioning equipment and sounding equipment, and the manufacturer's stated positioning and sounding accuracies, and capability of the equipment proposed for usage. In addition, the Contractor must provide information that a safe and suitable vessel meeting U.S. Coast Guard requirements is available and will be used for operation in the waters where the surveys are to be performed. The Contractor shall submit credentials/qualifications as evidence that qualified, experienced staff are available and will be used for the operation of the vessel as well as for the electronic positioning and sounding equipment.

#### 3.8.5 Data Processing

The Contractor shall use a Data Processing System to map the sounding data and calculate quantities. Reduced sounding data shall then be imported into the Data Processing System where cross-sections are compared to dredge templates and volume quantities are calculated. The software shall be capable of digital terrain modeling and shall produce, as a minimum, sounding sheets, cross section profiles, 3-dimensional area profiles, and quantity volume calculations using the Triangulated Irregular Network (TIN) method.

#### 3.9 PRE-DREDGE AND FINAL SURVEYS

The Government will perform a pre-dredge survey for each dredge cycle. The Government survey will be performed as close to commencement of dredging as possible, and not more than 14 calendar days prior to commencement of work.

For the post-dredge survey, the Contractor shall notify the Contracting Officer not less than ten (10) working days prior to completion of the entire work for each dredge cycle. The Government will perform the final survey for each dredge cycle as soon as possible after completion of the entire work, generally within 5 calendar days. All areas found to be in compliance with the contract requirements will be accepted and measured for payment in accordance with SECTION 01270: MEASUREMENT AND PAYMENT.

If the Government is unable to perform the final survey(s) due to the failure of the Contractor to complete the work in accordance with his prior notification, the Contracting Officer will charge the cost of the survey plant and standby labor, at \$3,000.00 per day, to the Contractor. Preliminary data from the final Government survey will be available within ten (10) calendar days. If the preliminary survey data indicates that the dredged area is not at the required depth, the Contractor will be directed to resume dredging and to complete the work to project depth. Adjustment in cost for additional Government post-dredge surveys shall be as specified in paragraph: FINAL EXAMINATION AND ACCEPTANCE.

#### 3.10 METHOD OF SOUNDINGS

The material removed will be measured by cubic meter in place, by means of soundings taken before and after dredging. Soundings will be taken by either lead line, trigonometric leveling (total station)/differential leveling, 200 kHz single-beam acoustic methods, acoustic multi-beam swath methods, or in combination, as determined by the Government; results of soundings by any of these methods, singularly or in combination, will be the basis for payment. The Contractor has the option of being present when such soundings are made.

#### 3.11 SHOALING

If, before the contract is completed, shoaling occurs in any section (area) previously accepted, including shoaling in the finished channel, because of the natural lowering of the side slopes or from sediments transported inside the project area, re-dredging at contract price, within the limit of available funds, may be done if agreeable to both the Contractor and the Contracting Officer.

### 3.12 REPORTING REQUIREMENT

The Contractor will be required to prepare and maintain a Daily Report of Operations and furnish copies thereof to the Contracting Officer's representative. The daily reports shall document dredging operations for all shifts in a 24-hour period. Further instruction on the preparation of the report will be furnished at a pre-construction conference. Copies of sample submittals are provided at the end of the Contractor's Quality Control section.

### 3.13 FINAL EXAMINATION AND ACCEPTANCE

As soon as practicable after the completion of the entire work, a final examination of the work will be conducted by the Contracting Officer. Should any shoals, lumps, or other lack of contract depth be disclosed by this examination, the Contractor will be required to remove same dredging at the contract rate for dredging. However, if the bottom is soft and the shoal areas are small and form no material obstruction to navigation, the removal of such shoal may be waived by the discretion of the Contracting Officer. The Contractor or his authorized representative will be notified when soundings are to be made, and will be permitted to accompany the survey party. When the area is found to be in a satisfactory condition, it will be accepted finally. Should more than two sounding operations by the Government over an area be necessary by reason of work for the removal of shoals disclosed at a prior sounding, the cost of such third and any subsequent sounding operations will be charged against the Contractor at the rate of \$3,000.00 per day for each day in which the Government plant is engaged in sounding and/or is en route to or from the site or held at or near the said site for such operations.

Final acceptance of the whole or a part of the work and the deductions or corrections of deductions made thereon will not be reopened after having once been made, except on evidence of collusion, fraud, or obvious error, and the acceptance of a completed section shall not change the time of payment of the retained percentages of the whole or any part of the work.

## Dredge Sample Data Form

## OCEANSIDE HARBOR MAINTENANCE DREDGING

Contract No.: \_\_\_\_\_ Sample No.: \_\_\_\_\_  
Contractor Name: \_\_\_\_\_ Date: \_\_\_\_\_  
Name of Dredge: \_\_\_\_\_ Time: \_\_\_\_\_  
Type of Dredge: \_\_\_Clamshell \_\_\_Hopper \_\_\_Hydraulic Cutterhead \_\_\_other  
If other, specify: \_\_\_\_\_

**Cut Location**

area: \_\_\_\_\_ northing: \_\_\_\_\_  
station: \_\_\_\_\_ easting: \_\_\_\_\_  
range: \_\_\_\_\_  
elevation: \_\_\_\_\_

**Placement Location**

area: \_\_\_\_\_ northing: \_\_\_\_\_  
station: \_\_\_\_\_ easting: \_\_\_\_\_  
range: \_\_\_\_\_  
elevation: \_\_\_\_\_

Sample Obtained By: \_\_\_\_\_

Sample Obtained From: \_\_\_\_\_

---

---

Note: A copy of this completed form should accompany the sample when shipped to the laboratory for testing.

-- End of Section --